

Sub Regional RTEP Committee: Western DEOK Supplemental Projects

November 20, 2020

Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: DEOK 2020-008

Process Stage: Needs Meeting 11-20-2020



Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

Problem Statement:

Duke Energy Distribution has requested a new delivery point near Half Acre Road in Clermont County, OH. A new industrial customer has requested 36MW of distribution service by 10-01-2022. The new load exceeds the capacity of existing distribution facilities in the area.



Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: DEOK 2020-003

Process Stage: Solutions Meeting 11-20-2020

Previously Presented: Needs Meeting 07-17-2020




Project Driver: Customer Service

Specific Assumption Reference:

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

Problem Statement:

A customer fed by Meadow substation is expecting a 10MW load increase by the summer of 2022. Meadow has two incoming 69kV feeders, one from Trenton and a normally opened one from Yankee-Jackson via the tap to Meadow. If the feeder from Trenton is opened Meadow throws over to the feeder from the tap. In this state the additional 10MWs of customer load will drive the Yankee to Meadow tap section of the feeder to 106% of its emergency rating.





DEOK Transmission Zone M-3 Process

Need Number: DEOK 2020-003

Process Stage: Solutions Meeting 11-20-2020

Potential Solution:

Reconductor the one mile section of feeder from Yankee to Meadow tap. Replace 8 poles to achieve proper clearance. Capacity of the line will increase from 97 MVA to 151 MVA.




Alternatives: none

Transmission Cost Estimate: \$974,771

Proposed In-Service Date: 12-31-2021

Project Status: Development

Model: 2020 RTEP



Appendix

High Level M-3 Meeting Schedule

| Assumptions | Activity | Timing |
|--|---|---|
| | Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| | Stakeholder comments | 10 days after Assumptions Meeting |
| Needs | Activity | Timing |
| | TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| | Stakeholder comments | 10 days after Needs Meeting |
| Solutions | Activity | Timing |
| | TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| | Stakeholder comments | 10 days after Solutions Meeting |
| Submission of Supplemental Projects & Local Plan | Activity | Timing |
| | Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| | Post selected solution(s) | Following completion of DNH analysis |
| | Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| | Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

11/10/2020 – V1 – Original version posted to pjm.com