

# Sub Regional RTEP Committee: Western DEOK Supplemental Projects

April 16, 2021

# Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** DEOK 2021-006

**Process Stage:** Needs Meeting 04-16-2021



**Project Driver:** Infrastructure Resilience

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 8

**Problem Statement:**

Brown TB1 is a 138/69/34 kV 3-winding transformer. The tertiary winding is connected to a 34 kV distribution bus. This old design exposes the transmission transformer to faults from the distribution system.



# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** DEOK 2021-004

**Process Stage:** Needs Meeting 03-19-2021




**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Problem Statement:**

Duke Energy Distribution has asked for a new delivery point in North Bend, OH. The distribution transformers that serve this area from Neumann and Saylor Park are peaking at 100% of rated capacity. Several large residential developments are planned or are currently under construction in this area.





# DEOK Transmission Zone M-3 Process North Bend

**Need Number:** DEOK 2021-004

**Process Stage:** Solutions Meeting 04-16-2021

**Previously Presented:** Needs Meeting 03-19-2021

**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Potential Solution:**

Install a new substation, North Bend. Loop the nearby Miami Fort– Midway 138 kV feeder through North Bend switch connecting the feeder to the bus. Install a 138 kV circuit switcher, a 138/13 kV 22 MVA transformer, a 13 kV circuit breaker for the low side of the transformer, and 13 kV bus work with circuit breakers for two distribution line exits. Reconfigure distribution lines in the area to include the new capacity available from North Bend substation.




**Alternatives:** none

**Transmission Cost Estimate:** \$7.2M

**Proposed In-Service Date:** 12-01-2023

**Project Status:** Scoping

**Model:** 2020 RTEP



**Need Number:** DEOK 2021-005

**Process Stage:** Needs Meeting 03-19-2021



**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Problem Statement:**

Duke Energy Distribution has asked for additional capacity at Newtown substation. Obsolete 4 kV distribution facilities at Madeira, Milford, Clertoma and Terrace Park are being retired. 10 MVA of 13 kV capacity is required.



**Need Number:** DEOK 2021-005

**Process Stage:** Solutions Meeting 04-16-2021

**Previously Presented:** Needs Meeting 03-19-2021

**Project Driver:** Customer Service

**Specific Assumption Reference:**

Duke Energy Ohio & Kentucky Local Planning Assumptions slide 9

**Potential Solution:**

Expand Newtown substation. Move the Beckjord - Newtown 138 kV feeder by removing the existing line switch, take-off tower and foundations, and installing a new line switch and take-off tower with new foundations. Install new 138 kV bus work, two bus switches and a motor operated air break switch to feed a new 138/13 kV 22 MVA transformer. Install 13 kV switchgear. Reconfigure distribution lines in the area to be fed by the new transformer and switchgear.




**Alternatives:** none

**Transmission Cost Estimate:** \$1.7M

**Proposed In-Service Date:** 12-01-2023

**Project Status:** Scoping

**Model:** 2020 RTEP





# Appendix

# High Level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

# Revision History

4/2/2021 – V1 – Original version posted to pjm.com