



# Reliability Analysis Update

Transmission Expansion Advisory  
Committee  
May 12, 2016



# 2016 RTEP Timeline


- Cases
  - 2016 RTEP summer case finalized
  - 2016 RTEP winter case sent to TO for modeling updates
  - 2016 RTEP light load case sent to TO for modeling updates
- Analysis
  - Completed and validated the N-1, generation deliverability analysis and common mode outage analysis, preliminary results are posted.
  - Currently working to complete the preliminary load deliverability and N-1-1 analysis
- Windows
  - 2016 RTEP Window #2 anticipated opening date at the end of June 2016




# 2016 RTEP Proposal Window #1 Proposal Review and Recommendations

- February 2016
  - Preliminary violations reviewed with the PJM TEAC
- March - April 2016
  - 2016 RTEP Window 1 Proposal evaluations
- April 20, 2016
  - Preliminary 2016 RTEP Proposal Window #1 Webcast posted to PJM.com
- May 12, 2016
  - Recommendation to PJM TEAC
- July 2016
  - Seek PJM Board Approval

- Scope
  - Generator Deliverability and Common Mode Outage Violations
  - End of life facilities
- Preliminary Files Released: 2/5/2016
- Window Opened: 2/16/2016
- Window Closed: 3/17/2016 – Proposal definitions, simulation data and planning cost estimate due
- Detailed Project Costs due: 4/1/2016 – Additional 15 days to develop and provide detailed cost data – See the window documentation for additional information



- 13 flow gates addressed
- 25 Proposals from 7 entities
  - 3 Transmission Owner Upgrades
    - Cost range of \$7.7M to \$48.5M
  - 21 Greenfield Projects
    - Cost range of \$15.6M - \$111.5 M



- Factors considered when selecting a proposal
  - Performance
  - Mitigation of applicable criteria violations
    - End of Life
  - Cost
  - Risk





# Chesterfield – Messer Road – Charles City Road 230kV

# 2016 RTEP Proposals Submitted for Window #1


- **Generation Deliverability and Common Mode Outage ( FG# 60, 61, 62, 66, 68, 70, 71, 72, 76, 78, 248, 249)**
- The Chesterfield – Messer Road – Charles City Road 230kV circuit is overloaded for several contingencies
  - This facility is also a Dominion local transmission owner End of Life criterion violation in the near term planning horizon
- Proposals Considered

Proposal Id	Cost Estimate
2016_1-3B	\$22 M
2016_1-3F*	\$58.8 M
2016_1-3G	\$7.7 M
2016_1-5A	\$41.7 M
2016_1-5B	\$15.6 M
2016_1-5C	\$26 M



New 500/230kV Facilities	230kV Upgrade	Rebuild of Existing Infrastructure
2016_1-5A, 2016_1-5B, 2016_1-5C, 2016_1-3F	2016_1-3G	2016_1-3B
<ul style="list-style-type: none"> <li>Doesn't address End of Life facility</li> <li>New ROW</li> </ul>	<ul style="list-style-type: none"> <li>Caused additional violations in combination with 500kV solutions</li> </ul>	<ul style="list-style-type: none"> <li>The proposed rebuild of existing infrastructure fixes the reliability criteria violation</li> <li>Significant Margin</li> <li>Existing ROW</li> <li>Addresses End of Life</li> </ul>

- **Generation Deliverability and Common Mode Outage ( FG# 60, 61, 62, 66, 68, 70, 71, 72, 76, 78, 248, 249) & DOM End of Life Facility**
  - The Chesterfield – Messer Road – Charles City Road 230kV circuit
  
- **Recommended Solution:**
  - Rebuild 21.32 miles of existing line between Chesterfield and Lakeside 230 kV. (B2745)
  
- **Estimated Project Cost: \$ 22 M**
  
- **Required IS Date: 6/1/2020**





# Carson – Rogers Road 500 kV




# 2016 RTEP Proposals Submitted for Window #1

- **Generation Deliverability ( FG# 102)**
- The Carson – Rogers Rd 500 kV circuit is overloaded for single contingency loss of the Carson – Rawlings 500 kV circuit.
- Proposals Considered

2016_1-1A	2016_1-1B	2016_1-2A	2016_1-2B
2016_1-2C	2016_1-3A	2016_1-3C	2016_1-3D*
2016_1-3E	2016_1-4A	2016_1-4B*	2016_1-6A
2016_1-6B	2016_1-6C	2016_1-6D	2016_1-7A
2016_1-7B	2016_1-7C	2016_1-7D	

- **Cost Estimates: ( \$24 M to \$115 M)**






# 2016 RTEP Proposals Submitted for Window #1

2 <sup>nd</sup> 500kV Circuit	230kV Clubhouse Option	Rebuild of Existing Infrastructure
<p>2016_1-1A, 2016_1-3D, 2016_1-7C, 2016_1-6B, 2016_1-1B, 2016_1-2B, 2016_1-3C, 2016_1-7A, 2016_1-7B, 2016_1-2A, 2016_1-6A, 2016_1-6C</p>	<p>2016_1-2C, 2016_1-3E, 2016_1-4A, 2016_1-7D, 2016_1-4B, 2016_1-6D</p>	<p>2016_1-3A</p>
<ul style="list-style-type: none"> <li>• All 2<sup>nd</sup> 500 kV Proposals mitigated the 500 kV reliability criteria violation</li> <li>• Caused additional violations in 2021 analysis</li> <li>• Significant New ROW</li> </ul>	<ul style="list-style-type: none"> <li>• All 230 kV Clubhouse Proposals mitigated the 500 kV reliability criteria violation</li> <li>• Line loading exceeds 90% for all Clubhouse Proposals in the year 2020 analysis</li> </ul>	<ul style="list-style-type: none"> <li>• The proposed rebuild of existing infrastructure fixes the reliability criteria violation</li> <li>• Significant Margin Existing ROW</li> <li>• Addresses long-term End of Life need</li> </ul>

- **Generation Deliverability Violation ( FG# 102)**
  - The Carson – Rogers Rd 500 kV circuit.
- **Recommended Solution:**
  - Rebuild the Carson – Rogers Rd 500kV circuit. (B2744)
- **Estimated Project Cost: \$ 48.5 M**
- **Required IS Date: 6/1/2020**








# Artificial Island Update

# Artificial Island Area Network




- Consideration of increased cost estimates for the current approved scope of work
- Examining configuration changes to terminate the planned Silver Run – Salem 230 kV transmission line at Hope Creek
- Continue to develop current design in parallel with the investigation into alternative configurations

- Ongoing Activities
- Conducted discussions with PSE&G and LS Power and identified several alternative line routing and substation location options for interconnection at Hope Creek
  - Considerations for options being reviewed
    - Electrical performance
    - ROW – use of existing easements or obtaining new easements
    - Impacts to Artificial Island plans for site
    - Permitting Impacts in vicinity of AI site
    - Physical Site constraints
    - Cost
    - Schedule

- Complete work to identify viable alternatives to interconnect at Hope Creek
  - Determine if alternate routes/substation locations are viable
  - Complete analysis of electrical performance
  - Develop cost estimate(s)
  - Assess constructability impacts
- Provide recommendation for AI interconnection
- Process scope change to project if appropriate

# Supplemental Projects

- Supplemental Project
- Loop in the Meadow Lake - Olive 345 kV circuit into NIPSCO's Reynolds 765/345kV station (S1141)
- Part of MISO MVP project
- Estimated Project Cost: \$2M
- Projected IS Date: 5/1/2017



# Questions?

Email: [RTEP@pjm.com](mailto:RTEP@pjm.com)



- Revision History
  - V1 - Original version posted to PJM.com – 5/10/2016
  - V2 – Added baseline upgrade ID #'s and removed slide– 5/11/2016
  - V3 Removed slide from supplemental projects section – 5/11/2016