

# TEAC Committee ComEd Supplemental Project

April 14, 2020

# Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** ComEd 2020-002

**Process Stage:** Need Meeting April 14, 2020

**Project Drivers:**


- Equipment Material Condition, Performance, and Risk
- Operational Flexibility and Efficiency

**Specific Assumption References:**

- Transmission infrastructure replacements (EOL/condition/obsolescence) that are consistent with efficient asset management decisions
- Internal and/or regulatory design guidelines or PJM minimum design standards
- Enhancing system functionality, flexibility, or operability

**Problem Statement:**

Itasca 345 kV configuration does not comply with current standards. It is a straight bus design with four lines and two transformers with only two 345 kV circuit breakers, one of which is obsolete and has poor test scores. Two lines are connected directly to the bus with disconnect switches. Transformers do not have high side circuit breakers. 345 kV/138 kV Transformer 82 has partial discharge gassing due to a design deficiency and questionable acoustic test results. 2 out of 5 similar transformers have failed in service.



**Need Number:** ComEd 2020-003

**Process Stage:** Need Meeting April 14, 2020

**Project Drivers:**


- Equipment Material Condition, Performance, and Risk
- Operational Flexibility and Efficiency

**Specific Assumption References:**

- Transmission infrastructure replacements (EOL/condition/obsolescence) that are consistent with efficient asset management decisions
- Internal and/or regulatory design guidelines or PJM minimum design standards
- Enhancing system functionality, flexibility, or operability

**Problem Statement:**

Elmhurst 345 kV configuration does not comply with current standards. It is a straight bus design with two 345 kV bus tie circuit breakers protecting two lines and three transformers. Lines and transformers are directly connected to the bus via switches. Lines and transformers trip together. Both 345 kV circuit breakers are obsolete and are in need of bushing replacements due to leaking oil.



**Need Number:** ComEd 2020-004

**Process Stage:** Need Meeting April 14, 2020

**Project Drivers:**


- Operational Flexibility and Efficiency

**Specific Assumption References:**

- Internal and/or regulatory design guidelines or PJM minimum design standards
- Enhancing system functionality, flexibility, or operability

**Problem Statement:**

McCook 345 kV bus does not comply with current standards. It is a straight bus design with two lines and two transformers with the lines directly connected to the bus via disconnects. Loss of a line also trips a transformer.



# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** ComEd-2020-001

**Process Stage:** Solutions 4/14/2020

**Previously Presented:**

Needs Meeting 3/10/2020

**Project Driver:**

Equipment Material Condition, Performance and Risk


**Specific Assumption Reference:**

Transmission infrastructure replacements (EOL/condition/obsolescence) that are consistent with efficient asset management decisions

**Problem Statement:**

Lisle 345/138 kV Transformer #83 acoustic testing shows higher than expected vibration levels and increased frequencies associated with looseness in the core/coil assembly.

- Looseness has worsened since previous testing
- Shell form design that cannot be re-blocked
- Dissolved gas analysis shows insulation degradation.
- Last unit of 5 that were purchased with this design. 3 of the 5 failed catastrophically and one other was condemned before failure



**Need Number:** ComEd-2020-001

**Process Stage:** Solutions Meeting 4/14/2020

**Proposed Solution:**

Replace Lisle Transformer 83, add high-side CB, \$8.5M


**Alternatives Considered:**

None

**Projected In-Service:** 12/31/2021

**Project Status:** Engineering & Procurement

**Model:** N/A





# Appendix

# High Level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

# Revision History

3/31/2020 – V1 – Original version posted to pjm.com