

# Presentation to the PJM NEMSTF

## Interconnection Issues

---



## Interconnecting Solar Projects on the PSE&G Distribution System

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

- ❑ This presentation is intended to be a brief discussion of the effects of interconnecting of large amounts of solar generation on the distribution system.
- ❑ The presentation will also discuss typical utility planning concepts, codes and standards, and federal vs. NJ interconnection procedures.
- ❑ My thanks to NREL (proceedings from the High Penetration PV Workshop from 2010) - <http://www.nrel.gov/docs/fy10osti/48378.pdf>), DOE, and others for some of the information in this presentation!

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

- ❑ In NJ interconnection regulations only apply to generators connected to the distribution system
  - Net Metering, or a “retail sale” of electricity to the host utility under a FERC Qualifying Facility (QF) tariff
  - Distribution interconnections of “wholesale sales to PJM” projects on non-PJM jurisdictional distribution facilities are State regulated
  - Typical projects are renewables (solar predominantly) and other small generators, in all customer classes
- ❑ NJ’s regulations generally conform with the FERC Small Generator Interconnection Procedures (SGIP), but have some significant differences
- ❑ Technical standards focused on IEEE 1547, and for inverters, UL 1741 for connection to the grid

# Presentation to the PJM NEMSTF

## Interconnection Issues


---

### Net Metering

- ❑ Net metering interconnections in NJ follow a specific regulatory process for accepting customer-generator requests for connection of Class I renewable generators under NJ's net metering rules.
- ❑ The following flow chart, although somewhat out of date, shows parts of the process, beginning with the application by the customer-generator, and going through inspection.
- ❑ There are 2 screen shots from our work management system (DWMS) to show some of the steps involved.
- ❑ The second flow chart shows the Level 2/3 process, for projects > 10kW, or that require Level 3 review.

# Presentation to the PJM NEMSTF

## Interconnection Issues



# Presentation to the PJM NEMSTF Interconnection Issues

Change Service Notification: COF-Electric Request

Service notification Edit Goto Extras Environment System Help

Partner Status + Determine tasks Organization... Contract selection

Notification: 500102529 E1 NET METER SOLAR

Status: NOPR OSTS SOAS

Sales ord.: 40016996

Customer/Pr: **Catalog Selection**

Coding	Subject Code/Job Type
<b>DGINTER</b>	DG Interconnections
E200	Net Metering Photovoltaic
E201	Net Metering - Wind
E202	Net Metering - Other
E203	Cogen - Export
E204	Cogen - Non-Export
E205	Merchant Plant
<b>E1BUD</b>	BUD Underground Area
<b>E1CONUUG</b>	Conventional Underground Area
<b>E10HAREA</b>	Overhead Wire Area
<b>E1STLITE</b>	Lighting

Execution  
Priority

Main Work  
Planner gr  
COF Perso  
Elec/Persc  
Sales area

Reference  
FunctLoca

Action box  
Log telephone call

P00 (1) (100) sappa02 INS 0.093

# Presentation to the PJM NEMSTF

## Interconnection Issues

Change Service Notification: COF-Electric Request

Service notification Edit Goto Extras Environment System Help

Partner + Determine tasks Organization... Contract selection

Notification: 500097226 E1 NET METER APPLICATION FEE

Status: NOPR OST5 SQAS

Sales ord.: 40015883 Tasks

Customer/Partner Information Job Description Service Characteristics Tasks Activities Linked Documents

No.	Code group	Task	Task code text	Task text	Task	Status	User st
1	E1NOTIFI	02ST	LCS Receive BPU Notice		<input checked="" type="checkbox"/>	TSOS	
2	E1NOTIFI	04ST	LCS - Net Metering Application ...			TSCO	
3	E1NOTIFI	08ST	LCS -Customer One-line Received			TSCO	
4	E1NOTIFI	24ET	ELE-Answer Customer Request		<input checked="" type="checkbox"/>	TSOS	
5	E1NOTIFI	42CT	COF-Communicate Eng. Respon...		<input checked="" type="checkbox"/>	TSOS	
6	E1NOTIFI	46CT	COF-Obtain Customer Payment/...	CPPC rec'd ck. 1306 \$100.00		TSCO	
7	E1NOTIFI	50ST	LCS Phone line ordered & Installed		<input checked="" type="checkbox"/>	TSOS	
8	E1NOTIFI	56ST	LCS Meter Ordered & In-stock		<input checked="" type="checkbox"/>	TSOS	
9	E1NOTIFI	60CT	COF-Create Meter Order - Enter #		<input checked="" type="checkbox"/>	TSOS	
10	E1NOTIFI	61ST	LCS - BPU Inspection Complete ...		<input checked="" type="checkbox"/>	TSOS	
11	E1NOTIFI	62ET	ELE-PSE&G Inspection Required		<input checked="" type="checkbox"/>	TSOS	
12	E1NOTIFI	66ET	ELE-Muni. Inspect./Cut-in Card ...		<input checked="" type="checkbox"/>	TSOS	
13	E1NOTIFI	76ET	ELE - LCS Notified Meter Set Co...		<input checked="" type="checkbox"/>	TSOS	

Action box

Log telephone call


Entry 1 of 13

P00 (1) (100) sappa06 INS 0.422

# Presentation to the PJM NEMSTF

## Interconnection Issues

Net Metering Process Flow Diagram - Level 2 3





# Presentation to the PJM NEMSTF

## Interconnection Issues

---

### New Study Request from PJM

- ❑ Distribution Planning develops plan of supply options, and sends “Request for Estimate” to local electric division to develop estimate
- ❑ DWMS notification created, updates to settlement rule table made, and Division informed
- ❑ Engineering Technician creates engineering work order, completes estimate, and sends to Division Staff Engineer
- ❑ Division Staff Engineer reviews estimate and sends to Planning
- ❑ Metering submits metering estimate to Planning
- ❑ Planning submits completed Feasibility/Impact Study to PJM

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

- ❑ PJM Agreement (WMPA or ISA/CSA) signed and executed
- ❑ If a WMPA, or a PSE&G retail tariff for QF purchases, then a PSE&G Interconnection Agreement (IA) is executed
  - If an IA, Generator releases project and makes first payment
- ❑ If a PJM ISA/CSA, then PJM is project manager
  - Generator submits 3 months security deposit to PJM
- ❑ Electric Division where project is located holds project kick-off meeting for implementation phase
- ❑ Construction/Commissioning of interconnection complete
- ❑ Project Closeout – same for PJM ISA/CSA or PSE&G IA
  - Division complete DWMS work orders
  - Complete reconciliation with generator (refund or payment)

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

### Planning Criteria

- ❑ A utility's planning criteria are intended to be a guide to provide for the safe, reliable and low cost development of the utility's electrical system as loads increase and reinforcements and/or new facilities are required.



# Presentation to the PJM NEMSTF

## Interconnection Issues

---

- ❑ With all facilities in service:
  - Loads on the system must be within normal equipment ratings
  - Must provide acceptable voltages to connected customers
  
- ❑ With the outage of any single piece of equipment (N-1 Criteria Violation):
  - Affected load must be within the emergency rating of the remaining facilities
  - System must provide minimum emergency voltages

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

- ❑ Load Forecasting
  - Substation
  - Feeder
- ❑ Distribution Circuit Reinforcement
  - Ratings
  - N-1 Criteria
- ❑ New Business
  - Connected vs. Estimated Loads
  - Load Build-up Schedules and Load Shifting
  - Distributed Generation

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

### ❑ Substation & Area Capacity

- Firm N-1 Criteria
- Includes Automatic 13-kV ICT Transfers

### ❑ Capacity Processing

- Load vs. Capacity Analysis

### ❑ Load Relief Modeling

- Power Factor Correction
- Load Transfers
- Distributed Generation

### ❑ System Reinforcement Modeling

- Interstation Capacity Ties (ICT)
- Station Reinforcement
- New Station
- Generation

# Presentation to the PJM NEMSTF

## Interconnection Issues

### Effects of Distributed Generation (DG) on Distribution System

- ❑ Voltage Regulation
  - Steady state conditions, fluctuating conditions (flicker), cap bank and tap changer cycling issues, reverse power flow issues, voltage unbalance
- ❑ Fault Currents and Protection Coordination
  - Impact on fault levels, device coordination, interrupting ratings, ground fault current detection desensitization
- ❑ Ground Fault Overvoltages
  - Important especially for non-effectively grounded DG, which is how PV devices are often configured
- ❑ Islanding
  - Important especially in complex situations with multiple DG present, or with fast reclosing and no live-line reclose blocking

NREL High Penetration PV Workshop : Defining High Penetration PV –Multiple Definitions and Where to Apply Them - Phil Barker, Nova Energy Specialists

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

### Key Issues for Solar Photovoltaics (PV) Projects

- ❑ Lack of data, and system analysis techniques and tools to sufficiently model and simulate specific impacts of solar on the grid (Voltage effects, Ground Fault Protection, Islanding, Power Quality, etc.)
- ❑ Need for intelligent bundling of PV with demand side management, communications and controls, and storage technologies
- ❑ Need to enhance system protection and coordination capability through the use of advanced instrumentation, measurement and controls devices
- ❑ Must develop methods, equipment and technologies to effectively mitigate the intermittency of solar
- ❑ Development and investigation of codes and standards to determine limitations on grid integration equipment capabilities and to establish stakeholder consensus



# Presentation to the PJM NEMSTF

## Interconnection Issues

### PV Inverter Technical Challenges

- ❑ Implementing Reactive (VAR) Control, Low Voltage Ride Through (LVRT), and Dynamic Control – are technically achievable
- ❑ Most inverter modification can be done through software upgrades
- ❑ Minor hardware changes at minimal additional cost would include:
  - Additional sensors
  - Uninterruptible Power Supplies (UPS) for LVRT capability
- ❑ In VAR Control mode inverter will operate at higher current levels when not at unity power factor – will also have impacts on efficiency and reliability, especially if running at night for regulation purposes.

*NREL High Penetration PV Workshop: PV Inverters with VAR Control, LVRT, and Dynamic Control - Ray Hudson –BEW Engineering*

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

### PV Interconnection Goals

- Ensure safe and reliable two-way electricity flow
- Develop smart grid interoperability
- Develop advanced communication and control functionalities of inverters
- Integrate renewable systems models into power system planning and operation tools
- Integrate with energy storage, load management, and demand response to enhance system flexibility
- Understand high-penetration limiting conditions
- Understand how various climates and cloud transients affect system reliability

*U.S. Department of Energy Solar Energy Technologies Program Goals*

# Presentation to the PJM NEMSTF

## Interconnection Issues

---

**Any Questions?**

