



PJM Interconnection, L.L.C.
2750 Monroe Blvd.
Audubon, PA 19403

Pauline Foley
Associate General Counsel
T: (610) 666-8248 | F: (610) 666-8211
pauline.foley@pjm.com

March 14, 2019

Honorable Kimberly D. Bose, Secretary
Federal Energy Regulatory Commission
888 First Street, N.E., Room 1A
Washington, D.C. 20426

*Re: PJM Interconnection, L.L.C., Docket No. ER19-1301-000
[30-Day Comment Period Requested]*

Dear Secretary Bose:

In accordance with PJM Open Access Transmission Tariff, Schedule 12 (“Tariff” or “Schedule 12”)¹ and Amended and Restated Operating Agreement of PJM Interconnection, L.L.C., Schedule 6, section 1.6 (“Operating Agreement” or “Schedule 6”), and pursuant to section 205 of the Federal Power Act,² PJM Interconnection, L.L.C. (“PJM”) hereby submits amendments to the Tariff, Schedule 12-Appendix A to incorporate cost responsibility assignments for 45 new baseline upgrades in the recent update to the Regional Transmission Expansion Plan (“RTEP”) approved by the PJM Board of Managers (“PJM Board”) on February 12, 2019. PJM requests that the revised Tariff sections become effective on June 12, 2019, **90 days after the date of this filing.**

¹ All capitalized terms that are not otherwise defined herein have the meaning as defined in the Tariff, Operating Agreement, and Reliability Assurance Agreement among Load Serving Entities in the PJM Region (“RAA”).

² 16 U.S.C, section 824d.

I. DESCRIPTION OF FILING

A. Description of the PJM Board Approved Updated RTEP Upgrades

On February 12, 2019, the PJM Board approved changes to the RTEP, which included approximately \$467 million in additional baseline transmission enhancements and expansions. With these approvals, the PJM Board has authorized a total of more than \$38 billion in investments since 2000.

B. Schedule 12 Requirements to Designate Cost Responsibility Assignments

This filing represents PJM's forty-eighth filing of cost responsibility assignments for new RTEP baseline upgrades since the Federal Energy Regulatory Commission ("Commission") directed such filings under Schedule 12. Pursuant to Schedule 12, PJM is required to designate in Tariff, Schedule 12-Appendix A, cost responsibility assignments for all transmission enhancements and expansions included in the RTEP.³ Similarly, Schedule 12 requires that within 30 days of the PJM Board's approval of each RTEP, or addition to the RTEP, PJM shall designate in Schedule 12-Appendix A, and in a report filed with the Commission, the "Responsible Customers" that will be subject to charges related to transmission enhancements and expansions included in the RTEP.⁴

Schedule 12 further provides that customers designated to be responsible for assignments of cost responsibility that PJM files with the Commission shall have 30 days from the date of such filing to submit comments regarding the proposed cost responsibility assignments.⁵

³ See Tariff, Schedule 12, section (b)(viii) (PJM "shall designate in the Schedule 12-Appendix A . . . the cost responsibility assignments determined pursuant to this Schedule 12").

⁴ *Id.*; See also Operating Agreement, Schedule 6, section 1.6.

⁵ *Id.*

C. Description of Proposed Amendments to Schedule 12-Appendix A

On March 22, 2013, the Commission accepted revisions to Schedule 12 modifying the cost allocation methodologies for transmission projects included in the RTEP.⁶ These revisions were filed by the PJM Transmission Owners in compliance with Order No. 1000 and revised the methodologies for allocating cost responsibility for all RTEP transmission expansions, including reliability and economic projects, replacement projects, and high voltage direct current transmission projects. These revisions only apply to the cost allocations for projects included in the RTEP on a prospective basis and do not disturb the cost allocations for projects previously included in the RTEP. Therefore, the cost responsibility assignments for RTEP projects approved after the March 22 Order are segregated in a separate appendix from the previously-approved cost responsibility assignments for RTEP upgrades. Going forward, cost responsibility assignments for all new RTEP projects are located in Schedule 12-Appendix A.

As required by Schedule 12, PJM hereby submits amendments to Schedule 12-Appendix A to include the new cost responsibility assignments for RTEP upgrades approved by the PJM Board on February 12, 2019.⁷ The revised Tariff sections containing new language, including new cost responsibility assignments, are reflected in redline and clean format in Attachments B and C, respectively, to this transmittal letter.⁸

⁶ *PJM Interconnection, L.L.C., et al.*, 142 FERC ¶ 61,214 at PP 411, 448 (2013) (“March 22 Order”).

⁷ See Tariff, Schedule 12, section (b)(viii).

⁸ The revised Tariff sections do not include any proposed rates or charges for recovery of any system upgrade costs. In accordance with Tariff, Schedule 12, recovery of the costs of such facilities that the RTEP requires Transmission Owners to construct, own and/or finance is governed by the Transmission Owners’ established rates.

1. Assignment of Cost Responsibility for Regional Facilities

The new transmission enhancements or expansions included in this most recent update to the RTEP approved by the PJM Board on February 12, 2019, are not Regional Facilities.⁹ Thus, PJM does not include any cost responsibility assignments for such facilities in Schedule 12-Appendix A with this filing.

2. Assignments of Cost Responsibility for Lower Voltage Facilities Needed for Reliability

a. Cost Responsibility Assignments that Address Transmission Enhancements Costing More than \$5 Million and Require DFAX Analysis

Consistent with the Tariff, Schedule 12, PJM submits amendments to the Tariff, Schedule 12-Appendix A to include the cost responsibility assignments for transmission enhancements or expansions that are not Regional Facilities (“Lower Voltage Facilities”).¹⁰ Four (4) enhancements or expansions¹¹ included in this filing, approved by the PJM Board on February 12, 2019, are Lower Voltage Facilities required to address reliability needs for which PJM applied the solution-based DFAX analysis described in the Tariff, Schedule 12, section (b)(iii).

⁹ Regional Facilities include transmission enhancements and expansions that, among other things, will operate at or above 500 kV or will be double-circuit 345 kV facilities as defined in PJM Tariff, Schedule 12, section (b)(i).

¹⁰ See Tariff, Schedule 12, section (b)(ii)(A) (“If the Lower Voltage Facility is a Reliability Project, [PJM] shall use the DFAX analysis described in section (b)(iii) of this Schedule 12 . . .”).

¹¹ The Lower Voltage Facilities include: b2443.6, b2443.7, b3079 and b3090.

b. Cost Responsibility Assignments for Transmission Enhancements that Address Reliability Violations on Transmission Facilities Operating At or Below 200 kV

By order dated August 26, 2016,¹² the Commission accepted, subject to condition, PJM's April 1, 2016 filing exempting from PJM's competitive proposal window process, except under certain circumstances, reliability violations on transmission facilities operating below 200 kV.¹³ In its September 26, 2016 compliance filing, PJM, as authorized by the PJM Transmission Owners acting through the Consolidated Transmission Owners Agreement, proposed to amend Schedule 12 to include a new Tariff, Schedule 12, section (b)(xvi), to provide that solutions for reliability violations on a facility operating at or below 200 kV not included in a competitive proposal window pursuant to Schedule 6, section 1.5.8(c) will be allocated 100 percent to the zone in which the transmission facilities are located. On February 2, 2017, the Commission accepted, effective August 26, 2016, the proposed revisions to both the Tariff, Schedule 12 and the PJM Operating Agreement, Schedule 6.

Consistent with Tariff, Schedule 12, section (b)(xvi), PJM proposes revisions to Schedule 12-Appendix A to include cost responsibility assignments 100 percent to the zone in which the facilities are to be located for twenty-three (23) reliability enhancements operating at or below 200 kV that were not included in a competitive proposal window.¹⁴

¹² *PJM Interconnection, L.L.C.*, 156 FERC ¶ 61,132 (Aug. 26, 2016) ("August 26 Order").

¹³ *PJM Interconnection, L.L.C.*, Revisions to PJM Operating Agreement, Schedule 6, Section 1.5 (Lower Voltage Facilities Threshold), Docket No. ER16-1335-000 (April 1, 2016).

¹⁴ The following upgrades are transmission facilities operating at or below 200 kV that were not included in a competitive proposal window: b3061, b3063, b3064, b3066, b3067, b3068, b3069, b3070, b3071, b3072, b3073, b3074, b3075, b3076, b3077, b3078, b3080, b3081, b3082, b3083, b3084, b3085, and b3095.

c. Cost Responsibility Assignments that Address FERC Form No. 715 Local Planning Criteria

On February 12, 2016, the Commission accepted, effective May 25, 2015, the PJM Transmission Owners' proposal to allocate 100 percent of the costs of a certain category of RTEP projects, which would not otherwise be included in the RTEP but for the fact they solely address local transmission owner planning criteria, to the zone of the Transmission Owner that filed the criteria in its FERC Form No. 715.¹⁵ Consistent with Schedule 12, section (b)(xv), which details the cost allocation methodology for projects selected solely to address FERC Form No. 715 criteria, PJM proposes revisions to Schedule 12-Appendix A to include cost responsibility assignments for thirteen (13) Lower Voltage Facility enhancements or expansions that solely address FERC Form No. 715 local planning criteria.¹⁶

d. Cost Responsibility Assignments that Address Transmission Enhancements Costing Less than \$5 Million

Schedule 12, section (b)(vi) provides that, notwithstanding Schedule 12, sections (b)(i), (b)(ii), (b)(iv) and (b)(v), cost responsibility for an enhancement or expansion for which the good faith estimate of the cost of such enhancement or expansion included for the first time in the RTEP does not equal or exceed \$5 million shall be assigned to the zone where the enhancement or expansion is to be located. Consistent with Schedule 12, section (b)(vi), PJM proposes revisions to Schedule 12-Appendix A to include cost responsibility assignments for one (1)

¹⁵ *PJM Interconnection, L.L.C.*, 154 FERC ¶ 61,096 at P 13 (Feb. 12, 2016) ("February 12 Order"). On August 3, 2018, the United States Court of Appeals for the District of Columbia found that the Commission acted arbitrarily and capriciously by accepting the cost allocation methodology for Regional Facilities addressing FERC Form No. 715 criteria and remanded the open orders back to the Commission for review. *See Old Dominion Electric Cooperative v. FERC*, No. 17-1040 (D.C. Cir. 2018). Such decision should have no impact on the 13 upgrades filed herein and approved by the PJM Board on February 12, 2019, as they are all Lower Voltage Facilities.

¹⁶ The following upgrades were selected solely to address Form 715 criteria: b3059, b3060, b3086.1, b3086.2, b3086.3, b3086.4, b3086.5, b3087.1, b3087.2, b3087.3, b3088, b3089 and b3094.

enhancements or expansions needed for reliability.¹⁷ Therefore, consistent with Schedule 12, section (b)(vi), cost responsibility for such enhancements or expansions shall be allocated 100 percent to the zone of the Transmission Owner where the enhancements or expansions are to be located.

e. Cost Responsibility Assignments that Address Spare Parts, Replacement Equipment and Circuit Breakers

The Tariff, Schedule 12, section (b)(iv)(C) provides that cost responsibility for circuit breakers and associated equipment independently included in the RTEP and not a part of the design specifications of a transmission element of a Required Transmission Enhancement shall be assigned to the zone of the owner of the spare part, if the owner of the spare part is a Transmission Owner listed in Tariff, Attachment J.

PJM proposes revisions to Schedule 12-Appendix A to include cost responsibility assignment for four (4) enhancements needed to address spare parts, replacement equipment and circuit breakers.¹⁸ Therefore, consistent with Tariff, Schedule 12, section (b)(iv)(C), cost responsibility for such enhancement shall be allocated 100 percent to the zone of the Transmission Owner of the spare parts.

D. Cost Responsibility Assignment Summary

For informational purposes, PJM also includes as Attachment A to this transmittal letter a Cost Responsibility Assignment Summary for the enhancements or expansions approved by the PJM Board on February 12, 2019. In addition to specifying the cost responsibility assignments for the enhancements or expansions, the summary sheets provide the criteria violation and test, a

¹⁷ The Lower Voltage Facilities allocated pursuant to Schedule 12, section (b)(vi) include the following reliability upgrade: b3055.

¹⁸ The upgrades allocated pursuant to Schedule 12, section (b)(iv)(C) include: b3019.1, b3019.2, 3062 and 3065.

description of the upgrade, in-service date, estimated upgrade costs, and the entity designated with construction responsibility for each enhancement or expansion.

II. COMMENT PERIOD

The Tariff, Schedule 12 section (b)(viii) provides that customers designated to be responsible for assignments of cost responsibility shall have 30 days from the date of such filing to seek review regarding the proposed cost responsibility assignments. Consistent with this provision, PJM requests that the comment date for this filing be set 30 days from the date of this filing, *i.e.*, April 13, 2019.¹⁹ To accommodate such a comment date, PJM requests an effective date of June 12, 2019 (90 days from the date of this filing) for all revised Tariff sections submitted in this docket.²⁰

III. DOCUMENTS ENCLOSED

PJM encloses the following:

1. This transmittal letter;
2. Attachment A – Cost Responsibility Assignment Summary sheets;
3. Attachment B – Revised Tariff, Schedule 12-Appendix A (in redlined form); and
4. Attachment C – Revised Tariff, Schedule 12-Appendix A (in clean form).

¹⁹ Since April 13, 2019 falls on a Saturday, comments are due on Monday, April 15, 2019. *See* 18 C.F.R. § 385.2007(a)(2) (2018).

²⁰ *See, e.g., PJM Interconnection, L.L.C., Errata Notice of Extending Comment Period*, Docket Nos. ER06-456-018, *et al.* (Dec. 2, 2008) (granting extension of time for filing protests or comments to accommodate Schedule 12 of the PJM Tariff); *PJM Interconnection, L.L.C., Errata Notice Extending Comment Date*, Docket No. ER08-229-000 (Nov. 30, 2007) (same); *PJM Interconnection, L.L.C., Notice Extending Comment Date*, Docket No. ER07-1186-000 (July 31, 2007) (same).

IV. CORRESPONDENCE AND COMMUNICATIONS

Correspondence and communications with respect to this filing should be sent to the following persons:

Craig Glazer
Vice President–Federal Government Policy
PJM Interconnection, L.L.C.
1200 G Street, N.W., Suite 600
Washington, D.C. 20005
Ph: (202) 423-4743
Fax: (202) 393-7741
craig.glazer@pjm.com

Pauline Foley
Associate General Counsel
PJM Interconnection, L.L.C.
2750 Monroe Blvd.
Audubon, PA 19403
Ph: (610) 666-8248
Fax: (610) 666-4281
pauline.foley@pjm.com

V. SERVICE

PJM has served a copy of this filing on all PJM Members and on the affected state utility regulatory commissions in the PJM Region by posting this filing electronically. In accordance with the Commission’s regulations,²¹ PJM will post a copy of this filing to the FERC filings section of its internet site, located at the following link: <http://www.pjm.com/documents/ferc-manuals/ferc-filings.aspx> with a specific link to the newly-filed document, and will send an e-mail on the same date as this filing to all PJM Members and all state utility regulatory commissions in the PJM Region²² alerting them that this filing has been made by PJM and is available by following such link. If the document is not immediately available by using the referenced link, the document will be available through the referenced link within twenty-four hours of the filing. Also, a copy of this filing will be available on the Commission’s eLibrary

²¹ See 18 C.F.R. sections 35.2(e) and 385.201(f)(3) (2018).


²² PJM already maintains, updates, and regularly uses electronic mailing lists for all PJM Members and affected state commissions.

Honorable Kimberly D. Bose, Secretary
Re: PJM Interconnection, L.L.C.
March 14, 2019
Page 10

website located at the following link: <http://www.ferc.gov/docs-filing/elibrary.asp> in accordance with the Commission's regulations and Order No. 714.

Respectfully submitted,

Craig Glazer
Vice President – Federal Government Policy
PJM Interconnection, L.L.C.
1200 G Street, NW, Suite 600
Washington, DC 20005
Ph: (202) 423-4743
Fax: (202) 393-7741
craig.glazer@pjm.com

By: 
Pauline Foley
Associate General Counsel
PJM Interconnection, L.L.C.
2750 Monroe Blvd.
Audubon, PA 19403
Ph: (610) 666-8248
Fax: (610) 666-4281
pauline.foley@pjm.com

*Counsel for
PJM Interconnection, L.L.C.*

Attachment A

Cost Responsibility Assignment Summary Sheets

Baseline Upgrade b2443.6

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Possum Point 500/230 kV transformer
 - Contingency: Loss of the Possum Point - Ox 500 kV line
 - Criteria test: N-1

- Overview of Reliability Solution
 - Description of Upgrade: Install a second 500/230 kV transformer at Possum Point substation and replace bus work and associated equipment as needed
 - Required Upgrade In-Service Date: June 01, 2023
 - Estimated Upgrade Cost: \$ 21.00 M
 - Construction Responsibility: Dominion

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion. No zone has greater than 1% distribution factor.

Baseline Upgrade b2443.7

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Possum Point 500/230 kV transformer
 - Contingency: Loss of the Possum Point - Ox 500 kV line
 - Criteria test: N-1

- Overview of Reliability Solution
 - Description of Upgrade: Replace 19 63kA 230 kV breakers with 19 80kA 230 kV breakers
 - Required Upgrade In-Service Date: June 01, 2023
 - Estimated Upgrade Cost: \$ 19.00 M
 - Construction Responsibility: Dominion

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion. No zone has greater than 1% distribution factor.

Baseline Upgrade b3019.1

- Overview of Reliability Problem
 - Criteria Violation: Overdutied breaker
 - Contingency: Rebuild of Bristers-Chancellor 500 kV line #552
 - Criteria test: Short Circuit

- Overview of Reliability Solution
 - Description of Upgrade: Update the nameplate for Morrisville 500 kV breaker "H1T594" to be 50kA
 - Required Upgrade In-Service Date: June 01, 2018
 - Estimated Upgrade Cost: \$ 2000
 - Construction Responsibility: Dominion

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion.

Baseline Upgrade b3019.2

- Overview of Reliability Problem
 - Criteria Violation: Overdutied breaker
 - Contingency: Rebuild of Bristers-Chancellor 500 kV line #552
 - Criteria test: Short Circuit

- Overview of Reliability Solution
 - Description of Upgrade: Update the nameplate for Morrisville 500 kV breaker "H1T545" to be 50kA
 - Required Upgrade In-Service Date: June 01, 2018
 - Estimated Upgrade Cost: \$ 2000
 - Construction Responsibility: Dominion

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion.

Baseline Upgrade b3055

- Overview of Reliability Problem
 - Criteria Violation: High voltage on 230 kV bus at Radnor Heights and Davis substations
 - Contingency: Breaker failure
 - Criteria test: N-1 Voltage
- Overview of Reliability Solution
 - Description of Upgrade: Install spare 230/69 kV transformer at Davis substation
 - Required Upgrade In-Service Date: June 01, 2023
 - Estimated Upgrade Cost: \$ 0.54 M
 - Construction Responsibility: Dominion
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion

Baseline Upgrade b3059

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation – “End of Life” criteria
 - Contingency: Loss of 230 kV Line #2173 Loudoun to Elklick
 - Criteria test: Dominion FERC 715 Criteria

- Overview of Reliability Solution
 - Description of Upgrade: Rebuild 230 kV Line #2173 Loudoun to Elklick
 - Required Upgrade In-Service Date: December 31, 2022
 - Estimated Upgrade Cost: \$ 13.50 M
 - Construction Responsibility: Dominion

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion.

Baseline Upgrade b3060

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation – “End of Life” criteria
 - Contingency: Loss of Elk Lick-Bull Run 230 kV Line (#295) and partial loss of Clifton-Walney 230 kV Line (#265)
 - Criteria test: Dominion FERC 715 Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild 4.6 mile Elklick - Bull Run 230 kV Line #295 and the portion (3.85 miles) of the Clifton - Walney 230 kV Line #265 which shares structures with Line #295
 - Required Upgrade In-Service Date: October 30, 2018
 - Estimated Upgrade Cost: \$ 15.50 M
 - Construction Responsibility: Dominion
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion.

Baseline Upgrade b3061

- Overview of Reliability Problem
 - Criteria Violation: Overload of the West Mifflin - Dravosburg and Dravosburg - Elrama 138 kV lines
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the West Mifflin - Dravosburg (Z-73) and Dravosburg - Elrama (Z-75) 138 kV lines
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 5.70 M
 - Construction Responsibility: DL
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3062

- Overview of Reliability Problem
 - Criteria Violation: Overload of the West Mifflin - Dravosburg and Dravosburg - Elrama 138 kV lines
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Install 138 kV tie breaker at West Mifflin
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 4.00 M
 - Construction Responsibility: DL
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL.

Baseline Upgrade b3063

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Wilson - Dravosburg 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Wilson - Dravosburg (Z-72) 138 kV line (approx. 5 miles)
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 4.80 M
 - Construction Responsibility: DL

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL.

Baseline Upgrade b3064

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Elrama - Wilson 138 kV line
 - Contingency: Tower contingency loss of the Elrama - Wilson and Elrama - Dravosburg 138 kV lines
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Expand Elrama 138 kV substation to loop in the existing US Steel Clariton - Piney Fork 138 kV line
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 8.75 M
 - Construction Responsibility: DL
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3065

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Elrama - Wilson 138 kV line
 - Contingency: Tower contingency loss of the Elrama - Wilson and Elrama - Dravosburg 138 kV lines
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Install 138 kV tie breaker at Wilson
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 4.00 M
 - Construction Responsibility: DL
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL.

Baseline Upgrade b3066

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Cranberry - Jackson 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Cranberry - Jackson 138 kV line (2.1 miles), reconductor 138 kV bus at Cranberry bus and replace 138 kV line switches at Jackson bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 3.44 M
 - Construction Responsibility: ATSI

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to ATSI.

Baseline Upgrade b3067

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Jackson - Maple 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Jackson - Maple 138 kV line (4.7 miles), replace line switches at Jackson 138 kV and replace the line traps and relays at Maple 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 7.86 M
 - Construction Responsibility: ATSI

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to ATSI. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3068

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Yukon - Westraver 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Yukon - Westraver 138 kV line (2.8 miles), replace the line drops and relays at Yukon 138 kV and replace switches at Westraver 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 2.50 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS.

Baseline Upgrade b3069

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Westraver - Route 51 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Westraver - Route 51 138 kV line (5.63 miles) and replace line switches at Westraver 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 7.50 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3070

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Yukon - Route 51 #1 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Yukon - Route 51 #1 138 kV line (8 miles), replace the line drops, relays and line disconnect switch at Yukon 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 10.00 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3071

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Yukon - Route 51 #2 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Yukon - Route 51 #2 138 kV line (8 miles) and replace relays at Yukon 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 10.00 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3072

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Yukon - Route 51 #3 138 kV line
 - Contingency: Tower contingency tripping the Yukon - Route 51 #1 and #2 138 kV lines
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Yukon - Route 51 #3 138 kV line (8 miles) and replace relays at Yukon 138 kV bus
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 10.00 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3073

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Blairsville E - Blairsville 138 kV line
 - Contingency: Single contingency tripping the Keystone - Cabot 500 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Replace the Blairsville East 138/115 kV transformer and associated equipment such as breaker disconnects and bus conductor
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 5.00 M
 - Construction Responsibility: PENELEC

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to PENELEC. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3074

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Armstrong #3 345/138 kV transformer
 - Contingency: Single contingency tripping the Handsome Lake - Wayne 345 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the 138 kV bus at Armstrong substation
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 0.50 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS

Baseline Upgrade b3075

- Overview of Reliability Problem
 - Criteria Violation: Overload of the 500/138 kV transformer at Cabot
 - Contingency: Breaker failure contingency tripping the Cabot - Cranberry 500 kV line and the Cabot #2 and #4 500/138 kV transformers
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Replace the 500/138 kV transformer breaker and reconductor 138 kV bus at Cabot substation
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 0.50 M
 - Construction Responsibility: APS
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS

Baseline Upgrade b3076

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Edgewater - Loyalhanna bus 3 138 kV transformer
 - Contingency: Single contingency tripping the South Bend - Yukon 500 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Edgewater - Loyalhanna 138 kV line (0.67 mile)
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 2.00 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS

Baseline Upgrade b3077

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Franklin Pike B - Wayne 115 kV line
 - Contingency: Single contingency tripping the Erie West - Wayne 345 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Franklin Pike B - Wayne 115 kV line (6.78 miles)
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 15.00 M
 - Construction Responsibility: PENELEC

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to PENELEC. The driver for this upgrade is less than 200 kV.

Baseline Upgrade b3078

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Morgan Street - Venango Junction 138 kV line
 - Contingency: Single contingency tripping the Erie West - Wayne 345 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the 138 kV bus and replace the line trap, relays Morgan Street. Reconductor the 138 kV bus at Venango Junction
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 1.00 M
 - Construction Responsibility: PENELEC

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to PENELEC

Baseline Upgrade b3079

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Wylie Ridge #7 500/345 kV transformer
 - Contingency: Breaker failure contingency tripping the Wylie Ridge - AA2-121 Tap 345 kV line and the Wylie Ridge #7 and #8 transformers
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Replace the Wylie Ridge 500/345 kV transformer #7
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 6.37 M
 - Construction Responsibility: APS
- Cost Allocation
 - The cost for this network upgrade is allocated 72.30% to ATSI and 27.70% to DL.

Transmission Zone	Planned Load (MW)	DFAX	DFAX Allocation
ATSI	13,018	0.0151	72.30%
DL	2,878	0.0261	27.70%

Baseline Upgrade b3080

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Seneca - Markwest Libery Bluestone 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the 138 kV bus at Seneca
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 0.07 M
 - Construction Responsibility: ATSI

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to ATSI

Baseline Upgrade b3081

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Seneca - Krendale 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Replace the 138 kV breaker and reconductor the 138 kV bus at Krendale
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 1.00 M
 - Construction Responsibility: ATSI

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to ATSI

^^

Baseline Upgrade b3082

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Geneva - Franklin Pike B 115 kV line
 - Contingency: Single contingency tripping the Erie West - Wayne 345 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Construct 4-breaker 115 kV ring bus at Geneva
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 7.00 M
 - Construction Responsibility: PENELEC

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to PENELEC. The driver for this upgrade is less than 200 kV

Baseline Upgrade b3083

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Karns City - Bulter 138 kV line
 - Contingency: Single contingency tripping the Erie West - Wayne 345 kV line
 - Criteria test: Generator Deliverability

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the 138 kV bus at Butler and reconductor the 138 kV bus and replace line trap at Karns City
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 2.00 M
 - Construction Responsibility: APS

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to APS

Baseline Upgrade b3084

- Overview of Reliability Problem
 - Criteria Violation: Overload of the Oakland - Panther Hollow 138 kV line
 - Contingency: Multiple contingencies
 - Criteria test: N-1-1

- Overview of Reliability Solution
 - Description of Upgrade: Reconductor the Oakland - Panther Hollow 138 kV line (approx. 1 mile)
 - Required Upgrade In-Service Date: June 01, 2021
 - Estimated Upgrade Cost: \$ 2.75 M
 - Construction Responsibility: DL

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to DL

Baseline Upgrade b3085

- Overview of Reliability Problem
 - Criteria Violation: Overload of the George Washington - Kammer 138 kV line
 - Contingency: Tower contingency tripping the Beverly - Hollow and Kammer - Lamping 345 kV lines
 - Criteria test: Generator Deliverability
- Overview of Reliability Solution
 - Description of Upgrade: Reconductor Kammer - George Washington 138 kV line (approx. 0.08 mile). Replace the wave trap at Kammer 138 kV
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 0.50 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3086.1

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Overload of the New Liberty - Findlay 34 kV line
 - Contingency: Multiple contingencies
 - Criteria test: N-1, N-1-1 Thermal
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild New Liberty – Findlay 34 kV line Str's 1 – 37 (1.5 miles), utilizing 795 26/7 ACSR conductor
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 3.40 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3086.2

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Overload of the New Liberty – North Baltimore 34 kV Line
 - Contingency: Multiple contingencies
 - Criteria test: N-1, N-1-1 Thermal
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild New Liberty – North Baltimore 34 kV line Str's 1-11 (0.5 mile), utilizing 795 26/7 ACSR conductor
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 1.80 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3086.3

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Overload of the West Melrose – Whirlpool 34 kV Line
 - Contingency: Multiple contingencies
 - Criteria test: N-1, N-1-1 Thermal
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild West Melrose – Whirlpool 34 kV line Str's 55-80 (1 mile), utilizing 795 26/7 ACSR conductor
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 2.37 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3086.4

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Voltage deviations of 34 kV buses: Ash Ave, Bernard Sw, BP Pumping, Cory, Crestwood, Cygnet-Buckeye, DTR, East Mt Cory, Ebersole, Hamman Sw, Harris, Henry, Landmark, McIntosh, Midland Switch, Mungen, North Crestwood Sw, North Woodcock, Plaza St, Portage, Rawson, South Mt Cory Sw, West Findlay, West Melrose, Woodcock Sw
 - Contingency: Multiple contingencies
 - Criteria test: N-1, N-1-1 Voltage
- Overview of Reliability Solution
 - Description of Upgrade: North Findlay station: Install a 138 kV 3000A 63kA line breaker and low side 34.5 kV 2000A 40kA breaker, high side 138 kV circuit switcher on T1
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 1.70 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3086.5

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Voltage deviations of 34 kV buses: Ash Ave, Bernard Sw, BP Pumping, Cory, Crestwood, Cygnet-Buckeye, DTR, East Mt Cory, Ebersole, Hamman Sw, Harris, Henry, Landmark, McIntosh, Midland Switch, Mungen, North Crestwood Sw, North Woodcock, Plaza St, Portage, Rawson, South Mt Cory Sw, West Findlay, West Melrose, Woodcock Sw
 - Contingency: Multiple contingencies
 - Criteria test: N-1, N-1-1 Voltage
- Overview of Reliability Solution
 - Description of Upgrade: Ebersole station: Install second 90 MVA 138/69/34 kV transformer. Install two low side (69 kV) 2000A 40kA breakers for T1 and T2
 - Required Upgrade In-Service Date: June 01, 2022
 - Estimated Upgrade Cost: \$ 3.75 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3087.1

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - The Cedar Creek - Fords Branch 46 kV line, Cedar Creek 138/69/46kV transformer, Breaks - Draffin-Henry Clay 46kV line, Breaks 69/46KV transformer, Dorton - Henry Clay and Dorton 138/46kV transformer overload; Voltage issues in the area (Fords Branch, Pike 29, Elwood, Draffin, Burdine, etc.)
 - Contingency: Multiple contingencies
 - Criteria test: AEP Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Construct a new greenfield station to the west (approx. 1.5 miles) of the existing Fords Branch Station in the new Kentucky Enterprise Industrial Park. This station will consist of six 3000A 40kA 138 kV breakers laid out in a ring arrangement, two 30 MVA 138/34.5 kV transformers, and two 30 MVA 138/12 kV transformers. The existing Fords Branch Station will be retired
 - Required Upgrade In-Service Date: December 01, 2018
 - Estimated Upgrade Cost: \$ 3.40 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3087.2

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - The Cedar Creek - Fords Branch 46 kV line, Cedar Creek 138/69/46kV transformer, Breaks - Draffin-Henry Clay 46kV line, Breaks 69/46KV transformer, Dorton - Henry Clay and Dorton 138/46kV transformer overload; Voltage issues in the area (Fords Branch, Pike 29, Elwood, Draffin, Burdine, ect.)
 - Contingency: Multiple contingencies
 - Criteria test: AEP Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Construct approximately 5 miles of new double circuit 138 kV line in order to loop the new Kewanee station into the existing Beaver Creek – Cedar Creek 138 kV circuit
 - Required Upgrade In-Service Date: December 01, 2018
 - Estimated Upgrade Cost: \$ 19.90 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3087.3

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - The Cedar Creek - Fords Branch 46 kV line, Cedar Creek 138/69/46kV transformer, Breaks - Draffin-Henry Clay 46kV line, Breaks 69/46KV transformer, Dorton - Henry Clay and Dorton 138/46kV transformer overload; Voltage issues in the area (Fords Branch, Pike 29, Elwood, Draffin, Burdine, ect.)
 - Contingency: Multiple contingencies
 - Criteria test: AEP Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Remote end work will be required at Cedar Creek Station
 - Required Upgrade In-Service Date: December 01, 2018
 - Estimated Upgrade Cost: \$ 0.50 M
 - Construction Responsibility: AEP
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP

Baseline Upgrade b3088

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Loss of Line #26 segment between Lexington and Rockbridge creates a radial line that exceeds the 700 MW-Mile limit.
 - Contingency: Loss of 115kV Line 26 Lexington-Rockbridge segment
 - Criteria test: Dominion FERC 715 Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild 4.75 mile section of Line #26 between Lexington and Rockbridge with a minimum summer emergency rating of 261 MVA
 - Required Upgrade In-Service Date: June 01, 2018
 - Estimated Upgrade Cost: \$ 8.00 M
 - Construction Responsibility: Dominion
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion

Baseline Upgrade b3089

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation - Greater than 300 MW load loss of an N-1-1 condition - loss of 65 Line and 2083 Line.
 - Contingency: Loss of 230kV Line 224
 - Criteria test: Dominion FERC 715 Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Rebuild 230 kV Line #224 between Lanexa and Northern Neck utilizing double circuit structures to current 230 kV standards. Only one circuit is to be installed on the structures with this project with a minimum summer emergency rating of 1047 MVA
 - Required Upgrade In-Service Date: June 01, 2018
 - Estimated Upgrade Cost: \$ 86.00 M
 - Construction Responsibility: Dominion
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion

Baseline Upgrade b3090

- Overview of Reliability Problem
 - Criteria Violation: Operational performance
 - Contingency: the removal of 230 kV Lines #248 and #2023 which currently are located at Potomac Yards North terminal station
 - Criteria test: Category P1, P4 & P7 criteria violations and significant load loss scenarios in the Arlington – Alexandria area
- Overview of Reliability Solution
 - Description of Upgrade: Convert the overhead portion (approx. 1500 feet) of 230 kV Lines #248 & #2023 to underground and convert Glebe substation to gas insulated substation
 - Required Upgrade In-Service Date: January 01, 2021
 - Estimated Upgrade Cost: \$ 120.00 M
 - Construction Responsibility: Dominion
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to Dominion

Transmission Zone	Planned Load (MW)	DFAX	DFAX Allocation
Dominion	20,331	0.0162	100.00%

Baseline Upgrade b3094

- Overview of Reliability Problem
 - Criteria Violation: FERC Form 715 Criteria Violation: Low voltage at Pleasant Grove 69 kV bus
 - Contingency: Loss of Bullitt County 161/69 kV transformer and LGE/KU's Mill Creek Unit #4
 - Criteria test: EKPC Criteria
- Overview of Reliability Solution
 - Description of Upgrade: Move 69 kV 12.0 MVAR capacitor bank from Greenbriar to Bullitt Co 69 kV substation
 - Required Upgrade In-Service Date: June 01, 2018
 - Estimated Upgrade Cost: \$ 0.30 M
 - Construction Responsibility: EKPC
- Cost Allocation
 - The cost for this network upgrade is allocated 100% to EKPC.

Baseline Upgrade b3095

- Overview of Reliability Problem
 - Criteria Violation: Thermal overload of Lakin-Racine 69 kV line
 - Contingency: Loss of Gavin-Meigs 69 kV and Leon-Ripley 138 kV lines
 - Criteria test: N-1-1

- Overview of Reliability Solution
 - Description of Upgrade: Rebuild Lakin – Racine Tap 69 kV line section (9.2 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor
 - Required Upgrade In-Service Date: December 01, 2022
 - Estimated Upgrade Cost: \$ 23.90 M
 - Construction Responsibility: AEP

- Cost Allocation
 - The cost for this network upgrade is allocated 100% to AEP. The driver for this upgrade is less than 200 kV.

Attachment B

Schedule 12 – Appendix A of the
PJM Open Access Transmission Tariff

(Marked / Redline Format)

SCHEDULE 12 – APPENDIX A

(7) Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone

Required	Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2212	Shawville Substation: Relocate 230 kV and 115 kV controls from the generating station building to new control building		PENELEC (100%)
b2293	Replace the Erie South 115 kV breaker 'Buffalo Rd' with 40kA breaker		PENELEC (100%)
b2294	Replace the Johnstown 115 kV breaker 'Bon Aire' with 40kA breaker		PENELEC (100%)
b2302	Replace the Erie South 115 kV breaker 'French #2' with 40kA breaker		PENELEC (100%)
b2304	Replace the substation conductor and switch at South Troy 115 kV substation		PENELEC (100%)
b2371	Install 75 MVAR capacitor at the Erie East 230 kV substation		PENELEC (100%)
b2441	Install +250/-100 MVAR SVC at the Erie South 230 kV station		PENELEC (100%)
b2442	Install three 230 kV breakers on the 230 kV side of the Lewistown #1, #2 and #3 transformers		PENELEC (100%)
b2450	Construct a new 115 kV line from Central City West to Bedford North		PENELEC (100%)
b2463	Rebuild and reconnector 115 kV line from East Towanda to S. Troy and upgrade terminal equipment at East Towanda, Tennessee Gas and South Troy		PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2494	Construct Warren 230 kV ring bus and install a second Warren 230/115 kV transformer	PENELEC (100%)
b2552.1	Reconductor the North Meshoppen – Oxbow-Lackawanna 230 kV circuit and upgrade terminal equipment (MAIT portion)	PENELEC (100%)
b2573	Replace the Warren 115 kV 'B12' breaker with a 40kA breaker	PENELEC (100%)
b2587	Reconfigure Pierce Brook 345 kV station to a ring bus and install a 125 MVAR shunt reactor at the station	PENELEC (100%)
b2621	Replace relays at East Towanda and East Sayre 115 kV substations (158/191 MVA SN/SE)	PENELEC (100%)
b2677	Replace wave trap, bus conductor and relay at Hilltop 115 kV substation. Replace relays at Prospect and Cooper substations	PENELEC (100%)
b2678	Convert the East Towanda 115 kV substation to breaker and half configuration	PENELEC (100%)
b2679	Install a 115 kV Venango Jct. line breaker at Edinboro South	PENELEC (100%)
b2680	Install a 115 kV breaker on Hooversville #1 115/23 kV transformer	PENELEC (100%)
b2681	Install a 115 kV breaker on the Eclipse #2 115/34.5 kV transformer	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2682	Install two 21.6 MVAR capacitors at the Shade Gap 115 kV substation	PENELEC (100%)
b2683	Install a 36 MVAR 115 kV capacitor and associated equipment at Morgan Street substation	PENELEC (100%)
b2684	Install a 36 MVAR 115 kV capacitor at Central City West substation	PENELEC (100%)
b2685	Install a second 115 kV 3000A bus tie breaker at Hooversville substation	PENELEC (100%)
b2735	Replace the Warren 115 kV 'NO. 2 XFMR' breaker with 40kA breaker	PENELEC (100%)
b2736	Replace the Warren 115 kV 'Warren #1' breaker with 40kA breaker	PENELEC (100%)
b2737	Replace the Warren 115 kV 'A TX #1' breaker with 40kA breaker	PENELEC (100%)
b2738	Replace the Warren 115 kV 'A TX #2' breaker with 40kA breaker	PENELEC (100%)
b2739	Replace the Warren 115 kV 'Warren #2' breaker with 40kA breaker	PENELEC (100%)
b2740	Revise the reclosing of the Hooversville 115 kV 'Ralphton' breaker	PENELEC (100%)
b2741	Revise the reclosing of the Hooversville 115 kV 'Statler Hill' breaker	PENELEC (100%)

Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2743.2	Tie in new Rice substation to Conemaugh – Hunterstown 500 kV	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2743.3	Upgrade terminal equipment at Conemaugh 500 kV on the Conemaugh – Hunterstown 500 kV circuit	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2748	Install two 28 MVAR capacitors at Tiffany 115 kV substation	PENELEC (100%)
b2767	Construct a new 345 kV breaker string with three (3) 345 kV breakers at Homer City and move the North autotransformer connection to this new breaker string	PENELEC (100%)
b2803	Reconductor 3.7 miles of the Bethlehem – Leretto 46 kV circuit and replace terminal equipment at Summit 46 kV	PENELEC (100%)
b2804	Install a new relay and replace 4/0 CU bus conductor at Huntingdon 46 kV station, on the Huntingdon – C tap 46 kV circuit	PENELEC (100%)
b2805	Install a new relay and replace 4/0 CU & 250 CU substation conductor at Hollidaysburg 46 kV station, on the Hollidaysburg – HCR Tap 46 kV circuit	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2806	Install a new relay and replace meter at the Raystown 46 kV substation, on the Raystown – Smithfield 46 kV circuit	PENELEC (100%)
b2807	Replace the CHPV and CRS relay, and adjust the IAC overcurrent relay trip setting; or replace the relay at Eldorado 46 kV substation, on the Eldorado – Gallitzin 46 kV circuit	PENELEC (100%)
b2808	Adjust the JBC overcurrent relay trip setting at Raystown 46 kV, and replace relay and 4/0 CU bus conductor at Huntingdon 46 kV substations, on the Raystown – Huntingdon 46 kV circuit	PENELEC (100%)
b2865	Replace Seward 115 kV breaker "Jackson Road" with 63kA breaker	PENELEC (100%)
b2866	Replace Seward 115 kV breaker "Conemaugh N." with 63kA breaker	PENELEC (100%)
b2867	Replace Seward 115 kV breaker "Conemaugh S." with 63kA breaker	PENELEC (100%)
b2868	Replace Seward 115 kV breaker "No.8 Xfmr" with 63kA breaker	PENELEC (100%)
b2944	Install two 345 kV 80 MVAR shunt reactors at Mainesburg station	PENELEC (100%)

Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2951	Seward, Blairsville East, Shelocta work	PENELEC (100%)
b2951.1	Upgrade Florence 115 kV line terminal equipment at Seward SS	PENELEC (100%)
b2951.2	Replace Blairsville East / Seward 115 kV line tuner, coax, line relaying and carrier set at Shelocta SS	PENELEC (100%)
b2951.3	Replace Seward / Shelocta 115 kV line CVT, tuner, coax, and line relaying at Blairsville East SS	PENELEC (100%)
b2952	Replace the North Meshoppen #3 230/115 kV transformer eliminating the old reactor and installing two breakers to complete a 230 kV ring bus at North Meshoppen	PENELEC (100%)
b2953	Replace the Keystone 500 kV breaker "NO. 14 Cabot" with 50kA breaker	PENELEC (100%)
b2954	Replace the Keystone 500 kV breaker "NO. 16 Cabot" with 50kA breaker	PENELEC (100%)
b2984	Reconfigure the bus at Glory and install a 50.4 MVAR 115 kV capacitor	PENELEC (100%)
b3007.2	Reconductor the Blairsville East to Social Hall 138 kV line and upgrade terminal equipment - PENELEC portion. 4.8 miles total. The new conductor will be 636 ACSS replacing the existing 636 ACSR conductor. At Blairsville East, the wave trap and breaker disconnects will be replaced	PENELEC (100%)

Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3008	Upgrade Blairsville East 138/115 kV transformer terminals. This project is an upgrade to the tap of the Seward – Shelocta 115 kV line into Blairsville substation. The project will replace the circuit breaker and adjust relay settings	PENELEC (100%)
b3009	Upgrade Blairsville East 115 kV terminal equipment. Replace 115 kV circuit breaker and disconnects	PENELEC (100%)
b3014	Replace the existing Shelocta 230/115 kV transformer and construct a 230 kV ring bus	PENELEC (100%)
b3016	Upgrade terminal equipment at Corry East 115 kV to increase rating of Four Mile to Corry East 115 kV line. Replace bus conductor	PENELEC (100%)
b3017.1	Rebuild Glade to Warren 230 kV line with hi-temp conductor and substation terminal upgrades. 11.53 miles. New conductor will be 1033 ACSS. Existing conductor is 1033 ACSR	ATSI (61.61%) / PENELEC (38.39%)
b3017.2	Glade substation terminal upgrades. Replace bus conductor, wave traps, and relaying	ATSI (61.61%) / PENELEC (38.39%)
b3017.3	Warren substation terminal upgrades. Replace bus conductor, wave traps, and relaying	ATSI (61.61%) / PENELEC (38.39%)
b3022	Replace Saxton 115 kV breaker 'BUS TIE' with a 40kA breaker	PENELEC (100%)

Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3024	Upgrade terminal equipment at Corry East 115 kV to increase rating of Warren to Corry East 115 kV line. Replace bus conductor	PENELEC (100%)
b3043	<i>Install one 115 kV 36 MVAR capacitor at West Fall 115 kV substation</i>	<i>PENELEC (100%)</i>
<u>b3073</u>	<u>Replace the Blairsville East 138/115 kV transformer and associated equipment such as breaker disconnects and bus conductor</u>	<u>PENELEC (100%)</u>
<u>b3077</u>	<u>Reconductor the Franklin Pike B – Wayne 115 kV line (6.78 miles)</u>	<u>PENELEC (100%)</u>
<u>b3078</u>	<u>Reconductor the 138 kV bus and replace the line trap, relays Morgan Street. Reconductor the 138 kV bus at Venango Junction</u>	<u>PENELEC (100%)</u>
<u>b3082</u>	<u>Construct 4-breaker 115 kV ring bus at Geneva</u>	<u>PENELEC (100%)</u>

SCHEDULE 12 – APPENDIX A

(14) Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2117	Reconductor 0.33 miles of the Parkersburg - Belpre line and upgrade Parkersburg terminal equipment	APS (100%)
b2118	Add 44 MVAR Cap at New Martinsville	APS (100%)
b2120	Six-Wire Lake Lynn - Lardin 138 kV circuits	APS (100%)
b2142	Replace Weirton 138 kV breaker “Wylie Ridge 210” with 63 kA breaker	APS (100%)
b2143	Replace Weirton 138 kV breaker “Wylie Ridge 216” with 63 kA breaker	APS (100%)
b2174.8	Replace relays at Mitchell substation	APS (100%)
b2174.9	Replace primary relay at Piney Fork substation	APS (100%)
b2174.10	Perform relay setting changes at Bethel Park substation	APS (100%)
b2213	Armstrong Substation: Relocate 138 kV controls from the generating station building to new control building	APS (100%)
b2214	Albright Substation: Install a new control building in the switchyard and relocate controls and SCADA equipment from the generating station building the new control center	APS (100%)
b2215	Rivesville Switching Station: Relocate controls and SCADA equipment from the generating station building to new control building	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2216	Willow Island: Install a new 138 kV cross bus at Belmont Substation and reconnect and reconfigure the 138 kV lines to facilitate removal of the equipment at Willow Island switching station	APS (100%)
b2235	130 MVAR reactor at Monocacy 230 kV	APS (100%)
b2260	Install a 32.4 MVAR capacitor at Bartonville	APS (100%)
b2261	Install a 33 MVAR capacitor at Damascus	APS (100%)
b2267	Replace 1000 Cu substation conductor and 1200 amp wave trap at Marlowe	APS (100%)
b2268	Reconductor 6.8 miles of 138kV 336 ACSR with 336 ACSS from Double Toll Gate to Riverton	APS (100%)
b2299	Reconductor from Collins Ferry - West Run 138 kV with 556 ACSS	APS (100%)
b2300	Reconductor from Lake Lynn - West Run 138 kV	APS (100%)
b2341	Install 39.6 MVAR Capacitor at Shaffers Corner 138 kV Substation	APS (100%)
b2342	Construct a new 138 kV switching station (Shuman Hill substation), which is next the Mobley 138 kV substation and install a 31.7 MVAR capacitor	APS (100%)
b2343	Install a 31.7 MVAR capacitor at West Union 138 kV substation	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2362	Install a 250 MVAR SVC at Squab Hollow 230 kV	APS (100%)
b2362.1	Install a 230 kV breaker at Squab Hollow 230 kV substation	APS (100%)
b2363	Convert the Shingletown 230 kV bus into a 6 breaker ring bus	APS (100%)
b2364	Install a new 230/138 kV transformer at Squab Hollow 230 kV substation. Loop the Forest - Elko 230 kV line into Squab Hollow. Loop the Brookville - Elko 138 kV line into Squab Hollow	APS (100%)
b2412	Install a 44 MVAR 138 kV capacitor at the Hempfield 138 kV substation	APS (100%)
b2433.1	Install breaker and a half 138 kV substation (Waldo Run) with 4 breakers to accommodate service to MarkWest Sherwood Facility including metering which is cut into Glen Falls Lamberton 138 kV line	APS (100%)
b2433.2	Install a 70 MVAR SVC at the new WaldoRun 138 kV substation	APS (100%)
b2433.3	Install two 31.7 MVAR capacitors at the new WaldoRun 138 kV substation	APS (100%)
b2424	Replace the Weirton 138 kV breaker 'WYLIE RID210' with 63 kA breakers	APS (100%)
b2425	Replace the Weirton 138 kV breaker 'WYLIE RID216' with 63 kA breakers	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2426	Replace the Oak Grove 138 kV breaker 'OG1' with 63 kA breakers	APS (100%)
b2427	Replace the Oak Grove 138 kV breaker 'OG2' with 63 kA breakers	APS (100%)
b2428	Replace the Oak Grove 138 kV breaker 'OG3' with 63 kA breakers	APS (100%)
b2429	Replace the Oak Grove 138 kV breaker 'OG4' with 63 kA breakers	APS (100%)
b2430	Replace the Oak Grove 138 kV breaker 'OG5' with 63 kA breakers	APS (100%)
b2431	Replace the Oak Grove 138 kV breaker 'OG6' with 63 kA breakers	APS (100%)
b2432	Replace the Ridgeley 138 kV breaker 'RC1' with a 40 kA rated breaker	APS (100%)
b2440	Replace the Cabot 138kV breaker 'C9-KISKI VLY' with 63kA	APS (100%)
b2472	Replace the Ringgold 138 kV breaker 'RCM1' with 40kA breakers	APS (100%)
b2473	Replace the Ringgold 138 kV breaker '#4 XMFR' with 40kA breakers	APS (100%)
b2475	Construct a new line between Oak Mound 138 kV substation and Waldo Run 138 kV substation	APS (100%)
b2545.1	Construct a new 138 kV substation (Shuman Hill substation) connected to the Fairview –Willow Island (84) 138 kV line	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2545.2	Install a ring bus station with five active positions and two 52.8 MVAR capacitors with 0.941 mH reactors	APS (100%)
b2545.3	Install a +90/-30 MVAR SVC protected by a 138 kV breaker	APS (100%)
b2545.4	Remove the 31.7 MVAR capacitor bank at Mobley 138 kV	APS (100%)
b2546	Install a 51.8 MVAR (rated) 138 kV capacitor at Nyswaner 138 kV substation	APS (100%)
b2547.1	Construct a new 138 kV six breaker ring bus Hillman substation	APS (100%)
b2547.2	Loop Smith- Imperial 138 kV line into the new Hillman substation	APS (100%)
b2547.3	Install +125/-75 MVAR SVC at Hillman substation	APS (100%)
b2547.4	Install two 31.7 MVAR 138 kV capacitors	APS (100%)
b2548	Eliminate clearance de-rate on Wylie Ridge – Smith 138 kV line and upgrade terminals at Smith 138 kV, new line ratings 294 MVA (Rate A)/350 MVA (Rate B)	APS (100%)
b2612.1	Relocate All Dam 6 138 kV line and the 138 kV line to AE units 1&2	APS (100%)
b2612.2	Install 138 kV, 3000A bus-tie breaker in the open bus-tie position next to the Shaffers corner 138 kV line	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2612.3	Install a 6-pole manual switch, foundation, control cable, and all associated facilities	APS (100%)
b2666	Yukon 138 kV Breaker Replacement	APS (100%)
b2666.1	Replace Yukon 138 kV breaker “Y-11(CHARL1)” with an 80 kA breaker	APS (100%)
b2666.2	Replace Yukon 138 kV breaker “Y-13(BETHEL)” with an 80 kA breaker	APS (100%)
b2666.3	Replace Yukon 138 kV breaker “Y-18(CHARL2)” with an 80 kA breaker	APS (100%)
b2666.4	Replace Yukon 138 kV breaker “Y-19(CHARL2)” with an 80 kA breaker	APS (100%)
b2666.5	Replace Yukon 138 kV breaker “Y-4(4B-2BUS)” with an 80 kA breaker	APS (100%)
b2666.6	Replace Yukon 138 kV breaker “Y-5(LAYTON)” with an 80 kA breaker	APS (100%)
b2666.7	Replace Yukon 138 kV breaker “Y-8(HUNTING)” with an 80 kA breaker	APS (100%)
b2666.8	Replace Yukon 138 kV breaker “Y-9(SPRINGD)” with an 80 kA breaker	APS (100%)
b2666.9	Replace Yukon 138 kV breaker “Y-10(CHRL-SP)” with an 80 kA breaker	APS (100%)
b2666.10	Replace Yukon 138 kV breaker “Y-12(1-1BUS)” with an 80 kA breaker	APS (100%)
b2666.11	Replace Yukon 138 kV breaker “Y-14(4-1BUS)” with an 80 kA breaker	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2666.12	Replace Yukon 138 kV breaker “Y-2(1B-BETHE)” with an 80 kA breaker	APS (100%)
b2666.13	Replace Yukon 138 kV breaker “Y-21(SHEPJ)” with an 80 kA breaker	APS (100%)
b2666.14	Replace Yukon 138 kV breaker “Y-22(SHEPHJT)” with an 80 kA breaker	APS (100%)
b2672	Change CT Ratio at Seneca Caverns from 120/1 to 160/1 and adjust relay settings accordingly	APS (100%)
b2688.3	Carroll Substation: Replace the Germantown 138 kV wave trap, upgrade the bus conductor and adjust CT ratios	AEP (12.91%) / APS (19.04%) / ATSI (1.24%) / ComEd (0.35%) / Dayton (1.45%) / DEOK (2.30%) / DL (1.11%) / Dominion (44.85%) / EKPC (0.78%) / PEPCO (15.85%) / RECO (0.12%)
b2689.3	Upgrade terminal equipment at structure 27A	APS (100%)
b2696	Upgrade 138 kV substation equipment at Butler, Shanor Manor and Krendale substations. New rating of line will be 353 MVA summer normal/422 MVA emergency	APS (100%)
b2700	Remove existing Black Oak SPS	APS (100%)
b2743.6	Reconfigure the Ringgold 230 kV substation to double bus double breaker scheme	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2743.6.1	Replace the two Ringgold 230/138 kV transformers	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2743.7	Rebuild/Reconductor the Ringgold – Catoctin 138 kV circuit and upgrade terminal equipment on both ends	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2747.1	Relocate the FirstEnergy Pratts 138 kV terminal CVTs at Gordonsville substation to allow for the installation of a new motor operated switch being installed by Dominion	APS (100%)
b2763	Replace the breaker risers and wave trap at Bredinville 138 kV substation on the Cabrey Junction 138 kV terminal	APS (100%)
b2764	Upgrade Fairview 138 kV breaker risers and disconnect leads; Replace 500 CU breaker risers and 556 ACSR disconnect leads with 795 ACSR	APS (100%)
b2964.1	Replace terminal equipment at Pruntytown and Glen Falls 138 kV station	APS (100%)
b2964.2	Reconductor approximately 8.3 miles of the McAlpin - White Hall Junction 138 kV circuit	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2965	Reconductor the Charleroi – Allenport 138 kV line with 954 ACSR conductor. Replace breaker risers at Charleroi and Allenport	DL (100%)
b2966	Reconductor the Yukon – Smithton – Shepler Hill Jct 138 kV line with 795 ACSS conductor. Replace Line Disconnect Switch at Yukon	APS (100%)
b2966.1	Reconductor the Yukon - Smithton - Shepler Hill Jct 138 kV line and replace terminal equipment as necessary to achieve required rating	APS (100%)
b2967	Convert the existing 6 wire Butler - Shanor Manor - Krendale 138 kV line into two separate 138 kV lines. New lines will be Butler - Keisters and Butler - Shanor Manor - Krendale 138 kV	APS (100%)
b2970	Ringgold – Catoctin Solution	APS (100%)
b2970.1	Install two new 230 kV positions at Ringgold for 230/138 kV transformers	APS (100%)
b2970.2	Install new 230 kV position for Ringgold – Catoctin 230 kV line	APS (100%)
b2970.3	Install one new 230 kV breaker at Catoctin substation	APS (100%)
b2970.4	Install new 230/138 kV transformer at Catoctin substation. Convert Ringgold – Catoctin 138 kV line to 230 kV operation	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
<p>b2996</p>	<p>Construct a new 500/138 kV substation as a 4-breaker ring bus with expansion plans for double-breaker-double-bus on the 500 kV bus and breaker-and-a-half on the 138 kV bus to provide EHV source to the Marcellus shale load growth area. Projected load growth of additional 160 MVA to current plan of 280 MVA, for a total load of 440 MVA served from Waldo Run substation. Replace primary relaying and carrier sets on Belmont and Harrison 500 kV Remote End substations. Construct additional 3-breaker string at Waldo Run 138 kV bus. Relocate the Sherwood #2 line terminal to the new string. Construct two single circuit Flint Run - Waldo Run 138 kV lines using 795 ACSR (approximately 3 miles). After terminal relocation on new 3-breaker string at Waldo Run, terminate new Flint Run 138 kV lines onto the two open terminals</p>	<p>APS (100%)</p>
<p>b3005</p>	<p>Reconductor 3.1 mile 556 ACSR portion of Cabot to Butler 138 kV with 556 ACSS and upgrade terminal equipment. 3.1 miles of line will be reconducted for this project. The total length of the line is 7.75 miles</p>	<p>APS (100%)</p>

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3006	Replace four Yukon 500/138 kV transformers with three transformers with higher rating and reconfigure 500 kV bus	APS (52.84%) / DL (47.16%)
b3007.1	Reconductor the Blairsville East to Social Hall 138 kV line and upgrade terminal equipment - AP portion. 4.8 miles total. The new conductor will be 636 ACSS replacing the existing 636 ACSR conductor. At Social Hall, meters, relays, bus conductor, a wave trap, circuit breaker and disconnects will be replaced	APS (100%)
b3010	Replace terminal equipment at Keystone and Cabot 500 kV buses. At Keystone, bus tubing and conductor, a wave trap, and meter will be replaced. At Cabot, a wave trap and bus conductor will be replaced	APS (100%)
b3011.1	Construct new Route 51 substation and connect 10 138 kV lines to new substation	DL (100%)
b3011.2	Upgrade terminal equipment at Yukon to increase rating on Yukon to Charleroi #2 138 kV line (New Yukon to Route 51 #4 138 kV line)	DL (100%)
b3011.3	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #1 138 kV line	DL (100%)
b3011.4	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #2 138 kV line	DL (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3011.5	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #3 138 kV line	DL (100%)
b3011.6	Upgrade remote end relays for Yukon – Allenport – Iron Bridge 138 kV line	DL (100%)
b3012.1	Construct new ties from FirstEnergy’s new substation to Duquesne’s new substation - AP portion. The estimated line length is approximately 4.7 miles, however, this length is subject to change based on the final route of the line. Approximately 1.7 miles could potentially be constructed by using the existing double circuit towers on the Wycoff tap. The line is planned to use 2-954 ACSS conductors per phase	DL (100%)
b3013	Reconductor Vasco Tap to Edgewater Tap 138 kV line. 4.4 miles. The new conductor will be 336 ACSS replacing the existing 336 ACSR conductor	APS (100%)
b3015.6	Reconductor Elrama to Mitchell 138 kV line – AP portion. 4.2 miles total. 2x 795 ACSS/TW 20/7	DL (100%)
b3028	Upgrade substation disconnect leads at William 138 kV substation	APS (100%)
b3051.1	<i>Ronceverte cap bank and terminal upgrades</i>	<i>APS (100%)</i>
b3052	<i>Install a 138 kV capacitor (29.7 MVAR effective) at West Winchester 138 kV</i>	<i>APS (100%)</i>

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

<u>b3068</u>	<u>Reconductor the Yukon – Westraver 138 kV line (2.8 miles), replace the line drops and relays at Yukon 138 kV and replace switches at Westraver 138 kV bus</u>		<u>APS (100%)</u>
<u>b3069</u>	<u>Reconductor the Westraver – Route 51 138 kV line (5.63 miles) and replace line switches at Westraver 138 kV bus</u>		<u>APS (100%)</u>
<u>b3070</u>	<u>Reconductor the Yukon – Route 51 #1 138 kV line (8 miles), replace the line drops, relays and line disconnect switch at Yukon 138 kV bus</u>		<u>APS (100%)</u>
<u>b3071</u>	<u>Reconductor the Yukon – Route 51 #2 138 kV line (8 miles) and replace relays at Yukon 138 kV bus</u>		<u>APS (100%)</u>
<u>b3072</u>	<u>Reconductor the Yukon – Route 51 #3 138 kV line (8 miles) and replace relays at Yukon 138 kV bus</u>		<u>APS (100%)</u>
<u>b3074</u>	<u>Reconductor the 138 kV bus at Armstrong substation</u>		<u>APS (100%)</u>
<u>b3075</u>	<u>Replace the 500/138 kV transformer breaker and reconductor 138 kV bus at Cabot substation</u>		<u>APS (100%)</u>
<u>b3076</u>	<u>Reconductor the Edgewater – Loyalhanna 138 kV line (0.67 mile)</u>		<u>APS (100%)</u>
<u>b3079</u>	<u>Replace the Wylie Ridge 500/345 kV transformer #7</u>		<u>ATSI (72.30%) / DL (27.70%)</u>
<u>b3083</u>	<u>Reconductor the 138 kV bus at Butler and reconductor the 138 kV bus and replace line trap at Karns City</u>		<u>APS (100%)</u>

SCHEDULE 12 – APPENDIX A

- (17) **AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1660.1	Cloverdale: install 6-765 kV breakers, incremental work for 2 additional breakers, reconfigure and relocate miscellaneous facilities, establish 500 kV station and 500 kV tie with 765 kV station	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: ATSI (24.65%) / Dayton (8.85%) / DEOK (19.91%) / Dominion (41.38%) / EKPC (5.21%)</p>

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1797.1	Reconductor the AEP portion of the Cloverdale - Lexington 500 kV line with 2-1780 ACSS	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: ATSI (5.74%) / Dayton (1.97%) / DEOK (4.40%) / Dominion (9.97%) / EKPC (1.12%) / PEPCO (76.80%)</p>
b2055	Upgrade relay at Brues station	AEP (100%)
b2122.3	Upgrade terminal equipment at Howard on the Howard - Brookside 138 kV line to achieve ratings of 252/291 (SN/SE)	AEP (100%)
b2122.4	Perform a sag study on the Howard - Brookside 138 kV line	AEP (100%)
b2229	Install a 300 MVAR reactor at Dequine 345 kV	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2230	Replace existing 150 MVAR reactor at Amos 765 kV substation on Amos - N. Proctorville - Hanging Rock with 300 MVAR reactor	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>
b2231	Install 765 kV reactor breaker at Dumont 765 kV substation on the Dumont - Wilton Center line	AEP (100%)
b2232	Install 765 kV reactor breaker at Marysville 765 kV substation on the Marysville - Maliszewski line	AEP (100%)
b2233	Change transformer tap settings for the Baker 765/345 kV transformer	AEP (100%)
b2252	Loop the North Muskingum - Crooksville 138 kV line into AEP's Philo 138 kV station which lies approximately 0.4 miles from the line	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2253	Install an 86.4 MVAR capacitor bank at Gorsuch 138 kV station in Ohio		AEP (100%)
b2254	Rebuild approximately 4.9 miles of Corner - Degussa 138 kV line in Ohio		AEP (100%)
b2255	Rebuild approximately 2.8 miles of Maliszewski - Polaris 138 kV line in Ohio		AEP (100%)
b2256	Upgrade approximately 36 miles of 138 kV through path facilities between Harrison 138 kV station and Ross 138 kV station in Ohio		AEP (100%)
b2257	Rebuild the Pokagon - Corey 69 kV line as a double circuit 138 kV line with one side at 69 kV and the other side as an express circuit between Pokagon and Corey stations		AEP (100%)
b2258	Rebuild 1.41 miles of #2 CU 46 kV line between Tams Mountain - Slab Fork to 138 kV standards. The line will be strung with 1033 ACSR		AEP (100%)
b2259	Install a new 138/69 kV transformer at George Washington 138/69 kV substation to provide support to the 69 kV system in the area		AEP (100%)
b2286	Rebuild 4.7 miles of Muskingum River - Wolf Creek 138 kV line and remove the 138/138 kV transformer at Wolf Creek Station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2287	Loop in the Meadow Lake - Olive 345 kV circuit into Reynolds 765/345 kV station		AEP (100%)
b2344.1	Establish a new 138/12 kV station, transfer and consolidate load from its Nicholasville and Marcellus 34.5 kV stations at this new station		AEP (100%)
b2344.2	Tap the Hydramatic – Valley 138 kV circuit (~ structure 415), build a new 138 kV line (~3.75 miles) to this new station		AEP (100%)
b2344.3	From this station, construct a new 138 kV line (~1.95 miles) to REA’s Marcellus station		AEP (100%)
b2344.4	From REA’s Marcellus station construct new 138 kV line (~2.35 miles) to a tap point on Valley – Hydramatic 138 kV ckt (~structure 434)		AEP (100%)
b2344.5	Retire sections of the 138 kV line in between structure 415 and 434 (~ 2.65 miles)		AEP (100%)
b2344.6	Retire AEP’s Marcellus 34.5/12 kV and Nicholasville 34.5/12 kV stations and also the Marcellus – Valley 34.5 kV line		AEP (100%)
b2345.1	Construct a new 69 kV line from Hartford to Keeler (~8 miles)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2345.2	Rebuild the 34.5 kV lines between Keeler - Sister Lakes and Glenwood tap switch to 69 kV (~12 miles)		AEP (100%)
b2345.3	Implement in - out at Keeler and Sister Lakes 34.5 kV stations		AEP (100%)
b2345.4	Retire Glenwood tap switch and construct a new Rothadew station. These new lines will continue to operate at 34.5 kV		AEP (100%)
b2346	Perform a sag study for Howard - North Bellville - Millwood 138 kV line including terminal equipment upgrades		AEP (100%)
b2347	Replace the North Delphos 600A switch. Rebuild approximately 18.7 miles of 138 kV line North Delphos - S073. Reconductor the line and replace the existing tower structures		AEP (100%)
b2348	Construct a new 138 kV line from Richlands Station to intersect with the Hales Branch - Grassy Creek 138 kV circuit		AEP (100%)
b2374	Change the existing CT ratios of the existing equipment along Bearskin - Smith Mountain 138kV circuit		AEP (100%)
b2375	Change the existing CT ratios of the existing equipment along East Danville-Banister 138kV circuit		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2376	Replace the Turner 138 kV breaker 'D'		AEP (100%)
b2377	Replace the North Newark 138 kV breaker 'P'		AEP (100%)
b2378	Replace the Sporn 345 kV breaker 'DD'		AEP (100%)
b2379	Replace the Sporn 345 kV breaker 'DD2'		AEP (100%)
b2380	Replace the Muskingum 345 kV breaker 'SE'		AEP (100%)
b2381	Replace the East Lima 138 kV breaker 'E1'		AEP (100%)
b2382	Replace the Delco 138 kV breaker 'R'		AEP (100%)
b2383	Replace the Sporn 345 kV breaker 'AA2'		AEP (100%)
b2384	Replace the Sporn 345 kV breaker 'CC'		AEP (100%)
b2385	Replace the Sporn 345 kV breaker 'CC2'		AEP (100%)
b2386	Replace the Astor 138 kV breaker '102'		AEP (100%)
b2387	Replace the Muskingum 345 kV breaker 'SH'		AEP (100%)
b2388	Replace the Muskingum 345 kV breaker 'SI'		AEP (100%)
b2389	Replace the Hyatt 138 kV breaker '105N'		AEP (100%)
b2390	Replace the Muskingum 345 kV breaker 'SG'		AEP (100%)
b2391	Replace the Hyatt 138 kV breaker '101C'		AEP (100%)
b2392	Replace the Hyatt 138 kV breaker '104N'		AEP (100%)
b2393	Replace the Hyatt 138 kV breaker '104S'		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2394	Replace the Sporn 345 kV breaker 'CC1'		AEP (100%)
b2409	Install two 56.4 MVAR capacitor banks at the Melmore 138 kV station in Ohio		AEP (100%)
b2410	Convert Hogan Mullin 34.5 kV line to 138 kV, establish 138 kV line between Jones Creek and Strawton, rebuild existing Mullin Elwood 34.5 kV and terminate line into Strawton station, retire Mullin station		AEP (100%)
b2411	Rebuild the 3/0 ACSR portion of the Hadley - Kroemer Tap 69 kV line utilizing 795 ACSR conductor		AEP (100%)
b2423	Install a 300 MVAR shunt reactor at AEP's Wyoming 765 kV station		Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)
			DFAX Allocation: AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2444	Willow - Eureka 138 kV line: Reconductor 0.26 mile of 4/0 CU with 336 ACSS		AEP (100%)
b2445	Complete a sag study of Tidd - Mahans Lake 138 kV line		AEP (100%)
b2449	Rebuild the 7-mile 345 kV line between Meadow Lake and Reynolds 345 kV stations		AEP (100%)
b2462	Add two 138 kV circuit breakers at Fremont station to fix tower contingency '408_2'		AEP (100%)
b2501	Construct a new 138/69 kV Yager station by tapping 2-138 kV FE circuits (Nottingham-Cloverdale, Nottingham-Harmon)		AEP (100%)
b2501.2	Build a new 138 kV line from new Yager station to Azalea station		AEP (100%)
b2501.3	Close the 138 kV loop back into Yager 138 kV by converting part of local 69 kV facilities to 138 kV		AEP (100%)
b2501.4	Build 2 new 69 kV exits to reinforce 69 kV facilities and upgrade conductor between Irish Run 69 kV Switch and Bowerstown 69 kV Switch		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2502.1	Construct new 138 kV switching station Nottingham tapping 6-138 kV FE circuits (Holloway-Brookside, Holloway-Harmon #1 and #2, Holloway-Reeds, Holloway-New Stacy, Holloway-Cloverdale). Exit a 138 kV circuit from new station to Freebyrd station		AEP (100%)
b2502.2	Convert Freebyrd 69 kV to 138 kV		AEP (100%)
b2502.3	Rebuild/convert Freebyrd-South Cadiz 69 kV circuit to 138 kV		AEP (100%)
b2502.4	Upgrade South Cadiz to 138 kV breaker and a half		AEP (100%)
b2530	Replace the Sporn 138 kV breaker 'G1' with 80kA breaker		AEP (100%)
b2531	Replace the Sporn 138 kV breaker 'D' with 80kA breaker		AEP (100%)
b2532	Replace the Sporn 138 kV breaker 'O1' with 80kA breaker		AEP (100%)
b2533	Replace the Sporn 138 kV breaker 'P2' with 80kA breaker		AEP (100%)
b2534	Replace the Sporn 138 kV breaker 'U' with 80kA breaker		AEP (100%)
b2535	Replace the Sporn 138 kV breaker 'O' with 80 kA breaker		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2536	Replace the Sporn 138 kV breaker 'O2' with 80 kA breaker		AEP (100%)
b2537	Replace the Robinson Park 138 kV breakers A1, A2, B1, B2, C1, C2, D1, D2, E1, E2, and F1 with 63 kA breakers		AEP (100%)
b2555	Reconductor 0.5 miles Tiltonsville – Windsor 138 kV and string the vacant side of the 4.5 mile section using 556 ACSR in a six wire configuration		AEP (100%)
b2556	Install two 138 kV prop structures to increase the maximum operating temperature of the Clinch River- Clinch Field 138 kV line		AEP (100%)
b2581	Temporary operating procedure for delay of upgrade b1464. Open the Corner 138 kV circuit breaker 86 for an overload of the Corner – Washington MP 138 kV line. The tower contingency loss of Belmont – Trissler 138 kV and Belmont – Edgelawn 138 kV should be added to Operational contingency		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2591	Construct a new 69 kV line approximately 2.5 miles from Colfax to Drewry's. Construct a new Drewry's station and install a new circuit breaker at Colfax station.		AEP (100%)
b2592	Rebuild existing East Coshocton – North Coshocton double circuit line which contains Newcomerstown – N. Coshocton 34.5 kV Circuit and Coshocton – North Coshocton 69 kV circuit		AEP (100%)
b2593	Rebuild existing West Bellaire – Glencoe 69 kV line with 138 kV & 69 kV circuits and install 138/69 kV transformer at Glencoe Switch		AEP (100%)
b2594	Rebuild 1.0 mile of Brantley – Bridge Street 69 kV Line with 1033 ACSR overhead conductor		AEP (100%)
b2595.1	Rebuild 7.82 mile Elkhorn City – Haysi S.S 69 kV line utilizing 1033 ACSR built to 138 kV standards		AEP (100%)
b2595.2	Rebuild 5.18 mile Moss – Haysi SS 69 kV line utilizing 1033 ACSR built to 138 kV standards		AEP (100%)
b2596	Move load from the 34.5 kV bus to the 138 kV bus by installing a new 138/12 kV XF at New Carlisle station in Indiana		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2597	Rebuild approximately 1 mi. section of Dragoon-Virgil Street 34.5 kV line between Dragoon and Dodge Tap switch and replace Dodge switch MOAB to increase thermal capability of Dragoon-Dodge Tap branch		AEP (100%)
b2598	Rebuild approximately 1 mile section of the Kline-Virgil Street 34.5 kV line between Kline and Virgil Street tap. Replace MOAB switches at Beiger, risers at Kline, switches and bus at Virgil Street.		AEP (100%)
b2599	Rebuild approximately 0.1 miles of 69 kV line between Albion and Albion tap		AEP (100%)
b2600	Rebuild Fremont – Pound line as 138 kV		AEP (100%)
b2601	Fremont Station Improvements		AEP (100%)
b2601.1	Replace MOAB towards Beaver Creek with 138 kV breaker		AEP (100%)
b2601.2	Replace MOAB towards Clinch River with 138 kV breaker		AEP (100%)
b2601.3	Replace 138 kV Breaker A with new bus-tie breaker		AEP (100%)
b2601.4	Re-use Breaker A as high side protection on transformer #1		AEP (100%)
b2601.5	Install two (2) circuit switchers on high side of transformers # 2 and 3 at Fremont Station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2602.1	Install 138 kV breaker E2 at North Proctorville		AEP (100%)
b2602.2	Construct 2.5 Miles of 138 kV 1033 ACSR from East Huntington to Darrah 138 kV substations		AEP (100%)
b2602.3	Install breaker on new line exit at Darrah towards East Huntington		AEP (100%)
b2602.4	Install 138 kV breaker on new line at East Huntington towards Darrah		AEP (100%)
b2602.5	Install 138 kV breaker at East Huntington towards North Proctorville		AEP (100%)
b2603	Boone Area Improvements		AEP (100%)
b2603.1	Purchase approximately a 200X300 station site near Slaughter Creek 46 kV station (Wilbur Station)		AEP (100%)
b2603.2	Install 3 138 kV circuit breakers, Cabin Creek to Hernshaw 138 kV circuit		AEP (100%)
b2603.3	Construct 1 mi. of double circuit 138 kV line on Wilbur – Boone 46 kV line with 1590 ACSS 54/19 conductor @ 482 Degree design temp. and 1-159 12/7 ACSR and one 86 Sq.MM. 0.646” OPGW Static wires		AEP (100%)
b2604	Bellefonte Transformer Addition		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2605	Rebuild and reconductor Kammer – George Washington 69 kV circuit and George Washington – Moundville ckt #1, designed for 138kV. Upgrade limiting equipment at remote ends and at tap stations		AEP (100%)
b2606	Convert Bane – Hammondsville from 23 kV to 69 kV operation		AEP (100%)
b2607	Pine Gap Relay Limit Increase		AEP (100%)
b2608	Richlands Relay Upgrade		AEP (100%)
b2609	Thorofare – Goff Run – Powell Mountain 138 kV Build		AEP (100%)
b2610	Rebuild Pax Branch – Scaraboro as 138 kV		AEP (100%)
b2611	Skin Fork Area Improvements		AEP (100%)
b2611.1	New 138/46 kV station near Skin Fork and other components		AEP (100%)
b2611.2	Construct 3.2 miles of 1033 ACSR double circuit from new Station to cut into Sundial-Baileysville 138 kV line		AEP (100%)
b2634.1	Replace metering BCT on Tanners Creek CB T2 with a slip over CT with higher thermal rating in order to remove 1193 MVA limit on facility (Miami Fort-Tanners Creek 345 kV line)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2643	Replace the Darrah 138 kV breaker 'L' with 40kA rated breaker		AEP (100%)
b2645	Ohio Central 138 kV Loop		AEP (100%)
b2667	Replace the Muskingum 138 kV bus # 1 and 2		AEP (100%)
b2668	Reconductor Dequine to Meadow Lake 345 kV circuit #1 utilizing dual 954 ACSR 54/7 cardinal conductor		AEP (100%)
b2669	Install a second 345/138 kV transformer at Desoto		AEP (100%)
b2670	Replace switch at Elk Garden 138 kV substation (on the Elk Garden – Lebanon 138 kV circuit)		AEP (100%)
b2671	Replace/upgrade/add terminal equipment at Bradley, Mullensville, Pinnacle Creek, Itmann, and Tams Mountain 138 kV substations. Sag study on Mullens – Wyoming and Mullens – Tams Mt. 138 kV circuits		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2687.1	Install a +/- 450 MVAR SVC at Jacksons Ferry 765 kV substation	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2687.2	Install a 300 MVAR shunt line reactor on the Broadford end of the Broadford – Jacksons Ferry 765 kV line	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>
b2697.1	Mitigate violations identified by sag study to operate Fieldale-Thornton-Franklin 138 kV overhead line conductor at its max. operating temperature. 6 potential line crossings to be addressed.	AEP (100%)
b2697.2	Replace terminal equipment at AEP’s Danville and East Danville substations to improve thermal capacity of Danville – East Danville 138 kV circuit	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2698	Replace relays at AEP's Cloverdale and Jackson's Ferry substations to improve the thermal capacity of Cloverdale – Jackson's Ferry 765 kV line		AEP (100%)
b2701.1	Construct Herlan station as breaker and a half configuration with 9-138 kV CB's on 4 strings and with 2-28.8 MVAR capacitor banks		AEP (100%)
b2701.2	Construct new 138 kV line from Herlan station to Blue Racer station. Estimated approx. 3.2 miles of 1234 ACSS/TW Yukon and OPGW		AEP (100%)
2701.3	Install 1-138 kV CB at Blue Racer to terminate new Herlan circuit		AEP (100%)
b2714	Rebuild/upgrade line between Glencoe and Willow Grove Switch 69 kV		AEP (100%)
b2715	Build approximately 11.5 miles of 34.5 kV line with 556.5 ACSR 26/7 Dove conductor on wood poles from Flushing station to Smyrna station		AEP (100%)
b2727	Replace the South Canton 138 kV breakers 'K', 'J', 'J1', and 'J2' with 80kA breakers		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2731	Convert the Sunnyside – East Sparta – Malvern 23 kV sub-transmission network to 69 kV. The lines are already built to 69 kV standards		AEP (100%)
b2733	Replace South Canton 138 kV breakers ‘L’ and ‘L2’ with 80 kA rated breakers		AEP (100%)
b2750.1	Retire Betsy Layne 138/69/43 kV station and replace it with the greenfield Stanville station about a half mile north of the existing Betsy Layne station		AEP (100%)
b2750.2	Relocate the Betsy Layne capacitor bank to the Stanville 69 kV bus and increase the size to 14.4 MVAR		AEP (100%)
b2753.1	Replace existing George Washington station 138 kV yard with GIS 138 kV breaker and a half yard in existing station footprint. Install 138 kV revenue metering for new IPP connection		AEP (100%)
b2753.2	Replace Dilles Bottom 69/4 kV Distribution station as breaker and a half 138 kV yard design including AEP Distribution facilities but initial configuration will constitute a 3 breaker ring bus		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2753.3	Connect two 138 kV 6-wired circuits from “Point A” (currently de-energized and owned by FirstEnergy) in circuit positions previously designated Burger #1 & Burger #2 138 kV. Install interconnection settlement metering on both circuits exiting Holloway		AEP (100%)
b2753.6	Build double circuit 138 kV line from Dilles Bottom to “Point A”. Tie each new AEP circuit in with a 6-wired line at Point A. This will create a Dilles Bottom – Holloway 138 kV circuit and a George Washington – Holloway 138 kV circuit		AEP (100%)
b2753.7	Retire line sections (Dilles Bottom – Bellaire and Moundsville – Dilles Bottom 69 kV lines) south of FirstEnergy 138 kV line corridor, near “Point A”. Tie George Washington – Moundsville 69 kV circuit to George Washington – West Bellaire 69 kV circuit		AEP (100%)
b2753.8	Rebuild existing 69 kV line as double circuit from George Washington – Dilles Bottom 138 kV. One circuit will cut into Dilles Bottom 138 kV initially and the other will go past with future plans to cut in		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2760	Perform a Sag Study of the Saltville – Tazewell 138 kV line to increase the thermal rating of the line		AEP (100%)
b2761.1	Replace the Hazard 161/138 kV transformer		AEP (100%)
b2761.2	Perform a Sag Study of the Hazard – Wooten 161 kV line to increase the thermal rating of the line		AEP (100%)
b2761.3	Rebuild the Hazard – Wooten 161 kV line utilizing 795 26/7 ACSR conductor (300 MVA rating)		AEP (100%)
b2762	Perform a Sag Study of Nagel – West Kingsport 138 kV line to increase the thermal rating of the line		AEP (100%)
b2776	Reconductor the entire Dequine – Meadow Lake 345 kV circuit #2		AEP (100%)
b2777	Reconductor the entire Dequine – Eugene 345 kV circuit #1		AEP (100%)
b2779.1	Construct a new 138 kV station, Campbell Road, tapping into the Grabill – South Hicksville 138 kV line		AEP (100%)
b2779.2	Reconstruct sections of the Butler-N.Hicksville and Auburn-Butler 69 kV circuits as 138 kV double circuit and extend 138 kV from Campbell Road station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2779.3	Construct a new 345/138 kV SDI Wilmington Station which will be sourced from Collingwood 345 kV and serve the SDI load at 345 kV and 138 kV, respectively		AEP (100%)
b2779.4	Loop 138 kV circuits in-out of the new SDI Wilmington 138 kV station resulting in a direct circuit to Auburn 138 kV and an indirect circuit to Auburn and Rob Park via Dunton Lake, and a circuit to Campbell Road; Reconductor 138 kV line section between Dunton Lake – SDI Wilmington		AEP (100%)
b2779.5	Expand Auburn 138 kV bus		AEP (100%)
b2787	Reconductor 0.53 miles (14 spans) of the Kaiser Jct. - Air Force Jct. Sw section of the Kaiser - Heath 69 kV circuit/line with 336 ACSR to match the rest of the circuit (73 MVA rating, 78% loading)		AEP (100%)
b2788	Install a new 3-way 69 kV line switch to provide service to AEP's Barnesville distribution station. Remove a portion of the #1 copper T-Line from the 69 kV through-path		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2789	Rebuild the Brues - Glendale Heights 69 kV line section (5 miles) with 795 ACSR (128 MVA rating, 43% loading)	AEP (100%)
b2790	Install a 3 MVAR, 34.5 kV cap bank at Caldwell substation	AEP (100%)
b2791	Rebuild Tiffin – Howard, new transformer at Chatfield	AEP (100%)
b2791.1	Rebuild portions of the East Tiffin - Howard 69 kV line from East Tiffin to West Rockaway Switch (0.8 miles) using 795 ACSR Drake conductor (129 MVA rating, 50% loading)	AEP (100%)
b2791.2	Rebuild Tiffin - Howard 69 kV line from St. Stephen’s Switch to Hinesville (14.7 miles) using 795 ACSR Drake conductor (90 MVA rating, non-conductor limited, 38% loading)	AEP (100%)
b2791.3	New 138/69 kV transformer with 138/69 kV protection at Chatfield	AEP (100%)
b2791.4	New 138/69 kV protection at existing Chatfield transformer	AEP (100%)
b2792	Replace the Elliott transformer with a 130 MVA unit, reconductor 0.42 miles of the Elliott – Ohio University 69 kV line with 556 ACSR to match the rest of the line conductor (102 MVA rating, 73% loading) and rebuild 4 miles of the Clark Street – Strouds R	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2793	Energize the spare Fremont Center 138/69 kV 130 MVA transformer #3. Reduces overloaded facilities to 46% loading		AEP (100%)
b2794	Construct new 138/69/34 kV station and 1-34 kV circuit (designed for 69 kV) from new station to Decliff station, approximately 4 miles, with 556 ACSR conductor (51 MVA rating)		AEP (100%)
b2795	Install a 34.5 kV 4.8 MVAR capacitor bank at Killbuck 34.5 kV station		AEP (100%)
b2796	Rebuild the Malvern - Oneida Switch 69 kV line section with 795 ACSR (1.8 miles, 125 MVA rating, 55% loading)		AEP (100%)
b2797	Rebuild the Ohio Central - Conesville 69 kV line section (11.8 miles) with 795 ACSR conductor (128 MVA rating, 57% loading). Replace the 50 MVA Ohio Central 138/69 kV XFMR with a 90 MVA unit		AEP (100%)
b2798	Install a 14.4 MVAR capacitor bank at West Hicksville station. Replace ground switch/MOAB at West Hicksville with a circuit switcher		AEP (100%)
b2799	Rebuild Valley - Almena, Almena - Hartford, Riverside - South Haven 69 kV lines. New line exit at Valley Station. New transformers at Almena and Hartford		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2799.1	Rebuild 12 miles of Valley – Almena 69 kV line as a double circuit 138/69 kV line using 795 ACSR conductor (360 MVA rating) to introduce a new 138 kV source into the 69 kV load pocket around Almena station	AEP (100%)
b2799.2	Rebuild 3.2 miles of Almena to Hartford 69 kV line using 795 ACSR conductor (90 MVA rating)	AEP (100%)
b2799.3	Rebuild 3.8 miles of Riverside – South Haven 69 kV line using 795 ACSR conductor (90 MVA rating)	AEP (100%)
b2799.4	At Valley station, add new 138 kV line exit with a 3000 A 40 kA breaker for the new 138 kV line to Almena and replace CB D with a 3000 A 40 kA breaker	AEP (100%)
b2799.5	At Almena station, install a 90 MVA 138/69 kV transformer with low side 3000 A 40 kA breaker and establish a new 138 kV line exit towards Valley	AEP (100%)
b2799.6	At Hartford station, install a second 90 MVA 138/69 kV transformer with a circuit switcher and 3000 A 40 kA low side breaker	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2817	Replace Delaware 138 kV breaker 'P' with a 40 kA breaker	AEP (100%)
b2818	Replace West Huntington 138 kV breaker 'F' with a 40 kA breaker	AEP (100%)
b2819	Replace Madison 138 kV breaker 'V' with a 63 kA breaker	AEP (100%)
b2820	Replace Sterling 138 kV breaker 'G' with a 40 kA breaker	AEP (100%)
b2821	Replace Morse 138 kV breakers '103', '104', '105', and '106' with 63 kA breakers	AEP (100%)
b2822	Replace Clinton 138 kV breakers '105' and '107' with 63 kA breakers	AEP (100%)
b2826.1	Install 300 MVAR reactor at Ohio Central 345 kV substation	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2826.2	Install 300 MVAR reactor at West Bellaire 345 kV substation		AEP (100%)
b2831.1	Upgrade the Tanner Creek – Miami Fort 345 kV circuit (AEP portion)		DFAX Allocation: Dayton (34.34%) / DEOK (56.45%) / EKPC (9.21%)
b2832	Six wire the Kyger Creek – Sporn 345 kV circuits #1 and #2 and convert them to one circuit		AEP (100%)
b2833	Reconductor the Maddox Creek – East Lima 345 kV circuit with 2-954 ACSS Cardinal conductor		DFAX Allocation: Dayton (100%)
b2834	Reconductor and string open position and sixwire 6.2 miles of the Chemical – Capitol Hill 138 kV circuit		AEP (100%)
b2872	Replace the South Canton 138 kV breaker ‘K2’ with a 80 kA breaker		AEP (100%)
b2873	Replace the South Canton 138 kV breaker ‘M’ with a 80 kA breaker		AEP (100%)
b2874	Replace the South Canton 138 kV breaker ‘M2’ with a 80 kA breaker		AEP (100%)
b2878	Upgrade the Clifty Creek 345 kV risers		AEP (100%)
b2880	Rebuild approximately 4.77 miles of the Cannonsburg – South Neal 69 kV line section utilizing 795 ACSR conductor (90 MVA rating)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2881	Rebuild ~1.7 miles of the Dunn Hollow – London 46 kV line section utilizing 795 26/7 ACSR conductor (58 MVA rating, non-conductor limited)	AEP (100%)
b2882	Rebuild Reusens - Peakland Switch 69 kV line. Replace Peakland Switch	AEP (100%)
b2882.1	Rebuild the Reusens - Peakland Switch 69 kV line (approximately 0.8 miles) utilizing 795 ACSR conductor (86 MVA rating, non-conductor limited)	AEP (100%)
b2882.2	Replace existing Peakland S.S with new 3 way switch phase over phase structure	AEP (100%)
b2883	Rebuild the Craneco – Pardee – Three Forks – Skin Fork 46 kV line section (approximately 7.2 miles) utilizing 795 26/7 ACSR conductor (108 MVA rating)	AEP (100%)
b2884	Install a second transformer at Nagel station, comprised of 3 single phase 250 MVA 500/138 kV transformers. Presently, TVA operates their end of the Boone Dam – Holston 138 kV interconnection as normally open preemptively for the loss of the existing Nagel	AEP (100%)
b2885	New delivery point for City of Jackson	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2885.1	Install a new Ironman Switch to serve a new delivery point requested by the City of Jackson for a load increase request	AEP (100%)
b2885.2	Install a new 138/69 kV station (Rhodes) to serve as a third source to the area to help relieve overloads caused by the customer load increase	AEP (100%)
b2885.3	Replace Coalton Switch with a new three breaker ring bus (Heppner)	AEP (100%)
b2886	Install 90 MVA 138/69 kV transformer, new transformer high and low side 3000 A 40 kA CBs, and a 138 kV 40 kA bus tie breaker at West End Fostoria	AEP (100%)
b2887	Add 2-138 kV CB's and relocate 2-138 kV circuit exits to different bays at Morse Road. Eliminate 3 terminal line by terminating Genoa - Morse circuit at Morse Road	AEP (100%)
b2888	Retire Poston substation. Install new Lemaster substation	AEP (100%)
b2888.1	Remove and retire the Poston 138 kV station	AEP (100%)
b2888.2	Install a new greenfield station, Lemaster 138 kV Station, in the clear	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2888.3	Relocate the Trimble 69 kV AEP Ohio radial delivery point to 138 kV, to be served off of the Poston – Strouds Run – Crooksville 138 kV circuit via a new three-way switch. Retire the Poston - Trimble 69 kV line		AEP (100%)
b2889	Expand Cliffview station		AEP (100%)
b2889.1	Cliffview Station: Establish 138 kV bus. Install two 138/69 kV XFRs (130 MVA), six 138 kV CBs (40 kA 3000 A) and four 69 kV CBs (40 kA 3000 A)		AEP (100%)
b2889.2	Byllesby – Wythe 69 kV: Retire all 13.77 miles (1/0 CU) of this circuit (~4 miles currently in national forest)		AEP (100%)
b2889.3	Galax – Wythe 69 kV: Retire 13.53 miles (1/0 CU section) of line from Lee Highway down to Byllesby. This section is currently double circuited with Byllesby – Wythe 69 kV. Terminate the southern 3/0 ACSR section into the newly opened position at Byllesby		AEP (100%)
b2889.4	Cliffview Line: Tap the existing Pipers Gap – Jubal Early 138 kV line section. Construct double circuit in/out (~2 miles) to newly established 138 kV bus, utilizing 795 26/7 ACSR conductor		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2890.1	Rebuild 23.55 miles of the East Cambridge – Smyrna 34.5 kV circuit with 795 ACSR conductor (128 MVA rating) and convert to 69 kV	AEP (100%)
b2890.2	East Cambridge: Install a 2000 A 69 kV 40 kA circuit breaker for the East Cambridge – Smyrna 69 kV circuit	AEP (100%)
b2890.3	Old Washington: Install 69 kV 2000 A two way phase over phase switch	AEP (100%)
b2890.4	Install 69 kV 2000 A two way phase over phase switch	AEP (100%)
b2891	Rebuild the Midland Switch to East Findlay 34.5 kV line (3.31 miles) with 795 ACSR (63 MVA rating) to match other conductor in the area	AEP (100%)
b2892	Install new 138/12 kV transformer with high side circuit switcher at Leon and a new 138 kV line exit towards Ripley. Establish 138 kV at the Ripley station with a new 138/69 kV 130 MVA transformer and move the distribution load to 138 kV service	AEP (100%)
b2936.1	Rebuild approximately 6.7 miles of 69 kV line between Mottville and Pigeon River using 795 ACSR conductor (129 MVA rating). New construction will be designed to 138 kV standards but operated at 69 kV	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2936.2	Pigeon River Station: Replace existing MOAB Sw. 'W' with a new 69 kV 3000 A 40 kA breaker, and upgrade existing relays towards HMD station. Replace CB H with a 3000 A 40 kA breaker	AEP (100%)
b2937	Replace the existing 636 ACSR 138 kV bus at Fletchers Ridge with a larger 954 ACSR conductor	AEP (100%)
b2938	Perform a sag mitigations on the Broadford – Wolf Hills 138 kV circuit to allow the line to operate to a higher maximum temperature	AEP (100%)
b2958.1	Cut George Washington – Tidd 138 kV circuit into Sand Hill and reconfigure Brues & Warton Hill line entrances	AEP (100%)
b2958.2	Add 2 138 kV 3000 A 40 kA breakers, disconnect switches, and update relaying at Sand Hill station	AEP (100%)
b2968	Upgrade existing 345 kV terminal equipment at Tanner Creek station	AEP (100%)
b2969	Replace terminal equipment on Maddox Creek - East Lima 345 kV circuit	AEP (100%)
b2976	Upgrade terminal equipment at Tanners Creek 345 kV station. Upgrade 345 kV bus and risers at Tanners Creek for the Dearborn circuit	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2988	Replace the Twin Branch 345 kV breaker “JM” with 63 kA breaker and associated substation works including switches, bus leads, control cable and new DICM		AEP (100%)
b2993	Rebuild the Torrey – South Gambrinus Switch – Gambrinus Road 69 kV line section (1.3 miles) with 1033 ACSR ‘Curlew’ conductor and steel poles		AEP (100%)
b3000	Replace South Canton 138 kV breaker ‘N’ with an 80kA breaker		AEP (100%)
b3001	Replace South Canton 138 kV breaker ‘N1’ with an 80kA breaker		AEP (100%)
b3002	Replace South Canton 138 kV breaker ‘N2’ with an 80kA breaker		AEP (100%)
<i>b3036</i>	<i>Rebuild 15.4 miles of double circuit North Delphos – Rockhill 138 kV line</i>		<i>AEP (100%)</i>
<i>b3037</i>	<i>Upgrades at the Natrium substation</i>		<i>AEP (100%)</i>
<i>b3038</i>	<i>Reconductor the Capitol Hill – Coco 138 kV line section</i>		<i>AEP (100%)</i>
<i>b3039</i>	<i>Line swaps at Muskingum 138 kV station</i>		<i>AEP (100%)</i>
<i>b3040.1</i>	<i>Rebuild Ravenswood – Racine tap 69 kV line section (~15 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor</i>		<i>AEP (100%)</i>

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

<i>b3040.2</i>	<i>Rebuild existing Ripley – Ravenswood 69 kV circuit (~9 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor</i>		<i>AEP (100%)</i>
<i>b3040.3</i>	<i>Install new 3-way phase over phase switch at Sarah Lane station to replace the retired switch at Cottageville</i>		<i>AEP (100%)</i>
<i>b3040.4</i>	<i>Install new 138/12 kV 20 MVA transformer at Polymer station to transfer load from Mill Run station to help address overload on the 69 kV network</i>		<i>AEP (100%)</i>
<i>b3040.5</i>	<i>Retire Mill Run station</i>		<i>AEP (100%)</i>
<i>b3040.6</i>	<i>Install 28.8 MVAR cap bank at South Buffalo station</i>		<i>AEP (100%)</i>
<i>b3051.2</i>	<i>Adjust CT tap ratio at Ronceverte 138 kV</i>		<i>AEP (100%)</i>
<u><i>b3085</i></u>	<u><i>Reconductor Kammer – George Washington 138 kV line (approx. 0.08 mile). Replace the wave trap at Kammer 138 kV</i></u>		<u><i>AEP (100%)</i></u>
<u><i>b3086.1</i></u>	<u><i>Rebuild New Liberty – Findlay 34 kV line Str’s 1–37 (1.5 miles), utilizing 795 26/7 ACSR conductor</i></u>		<u><i>AEP (100%)</i></u>
<u><i>b3086.2</i></u>	<u><i>Rebuild New Liberty – North Baltimore 34 kV line Str’s 1-11 (0.5 mile), utilizing 795 26/7 ACSR conductor</i></u>		<u><i>AEP (100%)</i></u>

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

<u>b3086.3</u>	<u>Rebuild West Melrose – Whirlpool 34 kV line Str’s 55–80 (1 mile), utilizing 795 26/7 ACSR conductor</u>		<u>AEP (100%)</u>
<u>b3086.4</u>	<u>North Findlay station: Install a 138 kV 3000A 63kA line breaker and low side 34.5 kV 2000A 40kA breaker, high side 138 kV circuit switcher on T1</u>		<u>AEP (100%)</u>
<u>b3086.5</u>	<u>Ebersole station: Install second 90 MVA 138/69/34 kV transformer. Install two low side (69 kV) 2000A 40kA breakers for T1 and T2</u>		<u>AEP (100%)</u>
<u>b3087.1</u>	<u>Construct a new greenfield station to the west (approx. 1.5 miles) of the existing Fords Branch Station in the new Kentucky Enterprise Industrial Park. This station will consist of six 3000A 40kA 138 kV breakers laid out in a ring arrangement, two 30 MVA 138/34.5 kV transformers, and two 30 MVA 138/12 kV transformers. The existing Fords Branch Station will be retired</u>		<u>AEP (100%)</u>
<u>b3087.2</u>	<u>Construct approximately 5 miles of new double circuit 138 kV line in order to loop the new Kewanee station into the existing Beaver Creek – Cedar Creek 138 kV circuit</u>		<u>AEP (100%)</u>

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

<u>b3087.3</u>	<u>Remote end work will be required at Cedar Creek Station</u>		<u>AEP (100%)</u>
<u>b3095</u>	<u>Rebuild Lakin – Racine Tap 69 kV line section (9.2 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor</u>		<u>AEP (100%)</u>

SCHEDULE 12 – APPENDIX A

(18) Duquesne Light Company

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2175.1	200 MVAR shunt reactor at Brunot Island 345 kV	DL (100%)
b2175.2	200 MVAR shunt reactor on future Brunot Island – Carson 345 kV circuit	DL (100%)
b2198	Revise the reclosing for the Brunot Island 138 kV breaker 'Z-40 COLLIER'	DL (100%)
b2199	Revise the reclosing for the Brunot Island 138 kV breaker 'Z-41 COLLIER'	DL (100%)
b2200	Revise the reclosing for the Crescent 138 kV breaker 'Z-29 Beaver'	DL (100%)
b2201	Revise the reclosing for the Crescent 138 kV breaker 'Z-82 VALLEY'	DL (100%)
b2202	Revise the reclosing for the Crescent 138 kV breaker 'Z-21 NORTH'	DL (100%)
b2203	Revise the reclosing for the Elrama 138 kV breaker 'Z18-USX CLAI'	DL (100%)
b2204	Revise the reclosing for the Elrama 138 kV breaker 'Z13-WEST MIF'	DL (100%)
b2205	Revise the reclosing for the Elrama 138 kV breaker 'Z15-DRAVOSBU'	DL (100%)
b2206	Revise the reclosing for the Woodville 138 kV breaker 'Z-106 PINEY'	DL (100%)
b2207	Revise the reclosing for the Woodville 138 kV breaker 'Z-64 COLLIER'	DL (100%)
b2208	Revise the reclosing for the Beaver Valley 138 kV breaker 'Z-28 CRESCEN'	DL (100%)

Duquesne Light Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2209	Revise the reclosing for the Cheswick 138 kV breaker 'Z-51 WILMERD'		DL (100%)
b2280	Replace the USAP 138kV breaker 'XFMR'		DL (100%)
b2303	Revise the reclosing to the Dravosburg 138kV breaker 'Z73 West Mifflin' from 5 sec to 15 sec		DL (100%)
b2563	Operate with the Crescent 345/138 kV #3 autotransformer in-service by replacing 8 overdutied 138 kV breakers at Crescent, 3 138 kV breakers at Beaver Valley, install #1 section 345 kV breaker for 331 circuit at Crescent		DL (100%)
b2632	Replace the Oakland 138 kV 'Z-101 Arsenal' breaker		DL (100%)
b2639	Replace the Crescent 138 kV 'NO3 – 4 138' breaker with a 63kA breaker		DL (100%)
b2640	Replace the Crescent 138 kV 'Z-143 SWCKLY' breaker with a 63kA breaker		DL (100%)
b2641	Replace the Crescent 138 kV 'Z-24 MONTOUR' breaker with a 63kA breaker		DL (100%)
b2642	Replace the Crescent 138 kV 'Z-28 BEAVER' breaker with a 63kA breaker		DL (100%)
b2689.1	Reconductor approximately 7 miles of the Woodville – Peters (Z-117) 138 kV circuit		AEC (1.00%) / APS (66.39%) / BGE (4.62%) / DOM (8.84%) / DPL (5.85%) / Neptune (0.12%) / PECO (3.40%) / PEPCO (6.32%) / PSEG (3.46%)

Duquesne Light Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2689.2	Reconfigure West Mifflin-USS Clairton (Z-15) 138 kV circuit to establish Dravosburg-USS Clairton (Z-14) 138 kV circuit and West Mifflin-Wilson (Z-15) 138 kV circuit	AEC (1.00%) / APS (66.39%) / BGE (4.62%) / DOM (8.84%) / DPL (5.85%) / Neptune (0.12%) / PECO (3.40%) / PEPCO (6.32%) / PSEG (3.46%)
b3012.2	Construct new ties from FirstEnergy's new substation to Duquesne's new substation – DL portion	DL (100%)
b3015.1	Construct new Elrama 138 kV substation and connect 7 138 kV lines to new substation	DL (100%)
b3015.2	Reconductor Elrama to Wilson 138 kV line. 4.8 miles	DL (100%)
b3015.3	Reconductor Dravosburg to West Mifflin 138 kV line. 3 miles	DL (100%)
b3015.4	Run new conductor on existing tower to establish the new Dravosburg – Elrama (Z-75) circuit. 10 miles	DL (100%)
b3015.5	Reconductor Elrama to Mitchell 138 kV line – DL portion. 4.2 miles total. 2x795 ACSS/TW 20/7	DL (100%)
b3015.7	Reconductor Wilson to West Mifflin 138 kV line. 2 miles. 795 ACSS/TW 20/7	DL (100%)
<u>b3061</u>	<u>Reconductor the West Mifflin – Dravosburg (Z-73) and Dravosburg – Elrama (Z-75) 138 kV lines</u>	<u>DL (100%)</u>
<u>b3062</u>	<u>Install 138 kV tie breaker at West Mifflin</u>	<u>DL (100%)</u>
<u>b3063</u>	<u>Reconductor the Wilson – Dravosburg (Z-72) 138 kV line (approx. 5 miles)</u>	<u>DL (100%)</u>

Duquesne Light Company (cont.)

<u>Required Transmission Enhancements</u>	<u>Annual Revenue Requirement</u>	<u>Responsible Customer(s)</u>
<u>b3064</u> <u>Expand Elrama 138 kV substation to loop in existing US Steel Clariton – Piney Fork 138 kV line</u>		<u>DL (100%)</u>
<u>b3065</u> <u>Install 138 kV tie breaker at Wilson</u>		<u>DL (100%)</u>
<u>b3084</u> <u>Reconductor the Oakland – Panther Hollow 138 kV line (approx. 1 mile)</u>		<u>DL (100%)</u>

SCHEDULE 12 – APPENDIX A

(20) Virginia Electric and Power Company

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1698.7	Replace Loudoun 230 kV breaker '203052' with 63kA rating	Dominion (100%)
b1696.1	Replace the Idylwood 230 kV '25112' breaker with 50kA breaker	Dominion (100%)
b1696.2	Replace the Idylwood 230 kV '209712' breaker with 50kA breaker	Dominion (100%)
b1793.1	Remove the Carolina 22 SPS to include relay logic changes, minor control wiring, relay resets and SCADA programming upon completion of project	Dominion (100%)
b2281	Additional Temporary SPS at Bath County	Dominion (100%)
b2350	Reconductor 211 feet of 545.5 ACAR conductor on 59 Line Elmont - Greenwood DP 115 kV to achieve a summer emergency rating of 906 amps or greater	Dominion (100%)
b2358	Install a 230 kV 54 MVAR capacitor bank on the 2016 line at Harmony Village Substation	Dominion (100%)
b2359	Wreck and rebuild approximately 1.3 miles of existing 230 kV line between Cochran Mill - X4-039 Switching Station	Dominion (100%)
b2360	Build a new 39 mile 230 kV transmission line from Dooms - Lexington on existing right-of-way	Dominion (100%)
b2361	Construct 230 kV OH line along existing Line #2035 corridor, approx. 2.4 miles from Idylwood - Dulles Toll Road (DTR) and 2.1 miles on new right-of-way along DTR to new Scott's Run Substation	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2368	Replace the Brambleton 230 kV breaker '209502' with 63kA breaker	Dominion (100%)
b2369	Replace the Brambleton 230 kV breaker '213702' with 63kA breaker	Dominion (100%)
b2370	Replace the Brambleton 230 kV breaker 'H302' with 63kA breaker	Dominion (100%)
b2373	Build a 2nd Loudoun - Brambleton 500 kV line within the existing ROW. The Loudoun - Brambleton 230 kV line will be relocated as an underbuild on the new 500 kV line	Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)
		DFAX Allocation: Dominion (100%)
b2397	Replace the Beaumeade 230 kV breaker '2079T2116' with 63kA	Dominion (100%)
b2398	Replace the Beaumeade 230 kV breaker '2079T2130' with 63kA	Dominion (100%)
b2399	Replace the Beaumeade 230 kV breaker '208192' with 63kA	Dominion (100%)
b2400	Replace the Beaumeade 230 kV breaker '209592' with 63kA	Dominion (100%)
b2401	Replace the Beaumeade 230 kV breaker '211692' with 63kA	Dominion (100%)
b2402	Replace the Beaumeade 230 kV breaker '227T2130' with 63kA	Dominion (100%)
b2403	Replace the Beaumeade 230 kV breaker '274T2130' with 63kA	Dominion (100%)

The Annual Revenue Requirement for all Virginia Electric and Power Company projects in this Section 20 shall be as specified in Attachment 7 to Appendix A of Attachment H-16A and under the procedures detailed in Attachment H-16B.

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2404	Replace the Beaumeade 230 kV breaker '227T2095' with 63kA	Dominion (100%)
b2405	Replace the Pleasant view 230 kV breaker '203T274' with 63kA	Dominion (100%)
b2443	Construct new underground 230 kV line from Glebe to Station C, rebuild Glebe Substation, construct 230 kV high side bus at Station C with option to install 800 MVA PAR	Dominion (97.11%) / ME (0.18%) / PEPSCO (2.71%)
b2443.1	Replace the Idylwood 230 kV breaker '203512' with 50kA	Dominion (100%)
b2443.2	Replace the Ox 230 kV breaker '206342' with 63kA breaker	Dominion (100%)
b2443.3	Glebe – Station C PAR	DFAX Allocation: Dominion (22.57%) / PEPSCO (77.43%)
<u>b2443.6</u>	<u>Install a second 500/230 kV transformer at Possum Point substation and replace bus work and associated equipment as needed</u>	<u>Dominion (100%)</u>
<u>b2443.7</u>	<u>Replace 19 63kA 230 kV breakers with 19 80kA 230 kV breakers</u>	<u>Dominion (100%)</u>
b2457	Replace 24 115 kV wood h-frames with 230 kV Dominion pole H-frame structures on the Clubhouse – Purdy 115 kV line	Dominion (100%)
b2458.1	Replace 12 wood H-frame structures with steel H-frame structures and install shunts on all conductor splices on Carolina – Woodland 115 kV	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2458.2	Upgrade all line switches and substation components at Carolina 115 kV to meet or exceed new conductor rating of 174 MVA	Dominion (100%)
b2458.3	Replace 14 wood H-frame structures on Carolina – Woodland 115 kV	Dominion (100%)
b2458.4	Replace 2.5 miles of static wire on Carolina – Woodland 115 kV	Dominion (100%)
b2458.5	Replace 4.5 miles of conductor between Carolina 115 kV and Jackson DP 115 kV with min. 300 MVA summer STE rating; Replace 8 wood H-frame structures located between Carolina and Jackson DP with steel H-frames	Dominion (100%)
b2460.1	Replace Hanover 230 kV substation line switches with 3000A switches	Dominion (100%)
b2460.2	Replace wave traps at Four River 230 kV and Elmont 230 kV substations with 3000A wave traps	Dominion (100%)
b2461	Wreck and rebuild existing Remington CT – Warrenton 230 kV (approx. 12 miles) as a double-circuit 230 kV line	Dominion (100%)
b2461.1	Construct a new 230 kV line approximately 6 miles from NOVEC’s Wheeler Substation a new 230 kV switching station in Vint Hill area	Dominion (100%)
b2461.2	Convert NOVEC’s Gainesville – Wheeler line (approximately 6 miles) to 230 kV	Dominion (100%)
b2461.3	Complete a Vint Hill – Wheeler – Loudoun 230 kV networked line	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2471	Replace Midlothian 500 kV breaker 563T576 and motor operated switches with 3 breaker 500 kV ring bus. Terminate Lines # 563 Carson – Midlothian, #576 Midlothian –North Anna, Transformer #2 in new ring	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2504	Rebuild 115 kV Line #32 from Halifax-South Boston (6 miles) for min. of 240 MVA and transfer Welco tap to Line #32. Moving Welco to Line #32 requires disabling auto-sectionalizing scheme	Dominion (100%)
b2505	Install structures in river to remove the 115 kV #65 line (Whitestone-Harmony Village 115 kV) from bridge and improve reliability of the line	Dominion (100%)
b2542	Replace the Loudoun 500 kV ‘H2T502’ breaker with a 50kA breaker	Dominion (100%)
b2543	Replace the Loudoun 500 kV ‘H2T584’ breaker with a 50kA breaker	Dominion (100%)
b2565	Reconductor wave trap at Carver Substation with a 2000A wave trap	Dominion (100%)
b2566	Reconductor 1.14 miles of existing line between ACCA and Hermitage and upgrade associated terminal equipment	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2582	Rebuild the Elmont – Cunningham 500 kV line	Dominion (100%)
b2583	Install 500 kV breaker at Ox Substation to remove Ox Tx#1 from H1T561 breaker failure outage.	Dominion (100%)
b2584	Relocate the Bremono load (transformer #5) to #2028 (Bremono-Charlottesville 230 kV) line and Cartersville distribution station to #2027 (Bremono-Midlothian 230 kV) line	Dominion (100%)
b2585	Reconductor 7.63 miles of existing line between Cranes and Stafford, upgrade associated line switches at Stafford	DFAX Allocation: PEPCO (100%)
b2620	Wreck and rebuild the Chesapeake – Deep Creek – Bowers Hill – Hodges Ferry 115 kV line; minimum rating 239 MVA normal/emergency, 275 MVA load dump rating	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2622	Rebuild Line #47 between Kings Dominion 115 kV and Fredericksburg 115 kV to current standards with summer emergency rating of 353 MVA at 115 kV	Dominion (100%)
b2623	Rebuild Line #4 between Bremono and Structure 8474 (4.5 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2624	Rebuild 115 kV Lines #18 and #145 between Possum Point Generating Station and NOVEC's Smoketown DP (approx. 8.35 miles) to current 230 kV standards with a normal continuous summer rating of 524 MVA at 115 kV	Dominion (100%)
b2625	Rebuild 115 kV Line #48 between Thole Street and Structure 48/71 to current standard. The remaining line to Sewells Point is 2007 vintage. Rebuild 115 kV Line #107 line, Sewells Point to Oakwood, between structure 107/17 and 107/56 to current standard.	Dominion (100%)
b2626	Rebuild 115 kV Line #34 between Skiffes Creek and Yorktown and the double circuit portion of 115 kV Line #61 to current standards with a summer emergency rating of 353 MVA at 115 kV	Dominion (100%)
b2627	Rebuild 115 kV Line #1 between Crewe 115 kV and Fort Pickett DP 115 kV (12.2 miles) to current standards with summer emergency rating of 261 MVA at 115 kV	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2628	Rebuild 115 kV Line #82 Everetts – Voice of America (20.8 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2629	Rebuild the 115 kV Lines #27 and #67 lines from Greenwich 115 kV to Burton 115 kV Structure 27/280 to current standard with a summer emergency rating of 262 MVA at 115 kV	Dominion (100%)
b2630	Install circuit switchers on Gravel Neck Power Station GSU units #4 and #5. Install two 230 kV CCVT's on Lines #2407 and #2408 for loss of source sensing	Dominion (100%)
b2636	Install three 230 kV bus breakers and 230 kV, 100 MVAR Variable Shunt Reactor at Dahlgren to provide line protection during maintenance, remove the operational hazard and provide voltage reduction during light load conditions	Dominion (100%)
b2647	Rebuild Boydton Plank Rd – Kerr Dam 115 kV Line #38 (8.3 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.	Dominion (100%)
b2648	Rebuild Carolina – Kerr Dam 115 kV Line #90 (38.7 miles) to current standards with summer emergency rating of 353 MVA 115 kV.	Dominion (100%)
b2649	Rebuild Clubhouse – Carolina 115 kV Line #130 (17.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2649.1	Rebuild of 1.7 mile tap to Metcalf and Belfield DP (MEC) due to poor condition. The existing summer rating of the tap is 48 MVA and existing conductor is 4/0 ACSR on wood H-frames. The proposed new rating is 176 MVA using 636 ACSR conductor		Dominion (100%)
b2649.2	Rebuild of 4.1 mile tap to Brinks DP (MEC) due to wood poles built in 1962. The existing summer rating of the tap is 48 MVA and existing conductor is 4/0 ACSR and 393.6 ACSR on wood H-frames. The proposed new rating is 176 MVA using 636 ACSR conductor		Dominion (100%)
b2650	Rebuild Twittys Creek – Pamplin 115 kV Line #154 (17.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.		Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2651	Rebuild Buggs Island – Plywood 115 kV Line #127 (25.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV. The line should be rebuilt for 230 kV and operated at 115 kV.		Dominion (100%)
b2652	Rebuild Greatbridge – Hickory 115 kV Line #16 and Greatbridge – Chesapeake E.C. to current standard with summer emergency rating of 353 MVA at 115 kV.		Dominion (100%)
b2653.1	Build 20 mile 115 kV line from Pantego to Trowbridge with summer emergency rating of 353 MVA.		Dominion (100%)
b2653.2	Install 115 kV four-breaker ring bus at Pantego		Dominion (100%)
b2653.3	Install 115 kV breaker at Trowbridge		Dominion (100%)
b2654.1	Build 15 mile 115 kV line from Scotland Neck to S Justice Branch with summer emergency rating of 353 MVA. New line will be routed to allow HEMC to convert Dawson’s Crossroads RP from 34.5 kV to 115 kV.		Dominion (100%)
b2654.2	Install 115 kV three-breaker ring bus at S Justice Branch		Dominion (100%)
b2654.3	Install 115 kV breaker at Scotland Neck		Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2665	Rebuild the Cunningham – Dooms 500 kV line	Dominion (100%)
b2686	Pratts Area Improvement	Dominion (100%)
b2686.1	Build a 230 kV line from Remington Substation to Gordonsville Substation utilizing existing ROW	Dominion (100%)
b2686.11	Upgrading sections of the Gordonsville – Somerset 115 kV circuit	Dominion (100%)
b2686.12	Upgrading sections of the Somerset – Doubleday 115 kV circuit	Dominion (100%)
b2686.13	Upgrading sections of the Orange – Somerset 115 kV circuit	Dominion (100%)
b2686.14	Upgrading sections of the Mitchell – Mt. Run 115 kV circuit	Dominion (100%)
b2686.2	Install a 3rd 230/115 kV transformer at Gordonsville Substation	Dominion (100%)

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2686.3	Upgrade Line 2088 between Gordonsville Substation and Louisa CT Station	Dominion (100%)
b2717.1	De-energize Davis – Rosslyn #179 and #180 69 kV lines	Dominion (100%)
b2717.2	Remove splicing and stop joints in manholes	Dominion (100%)
b2717.3	Evacuate and dispose of insulating fluid from various reservoirs and cables	Dominion (100%)
b2717.4	Remove all cable along the approx. 2.5 mile route, swab and cap-off conduits for future use, leave existing communication fiber in place	Dominion (100%)
b2719.1	Expand Perth substation and add a 115 kV four breaker ring	Dominion (100%)
b2719.2	Extend the Hickory Grove DP tap 0.28 miles to Perth and terminate it at Perth	Dominion (100%)
b2719.3	Split Line #31 at Perth and terminate it into the new ring bus with 2 breakers separating each of the line terminals to prevent a breaker failure from taking out both 115 kV lines	Dominion (100%)
b2720	Replace the Loudoun 500 kV ‘H1T569’ breakers with 50kA breaker	Dominion (100%)
b2729	Optimal Capacitors Configuration: New 175 MVAR capacitor at Brambleton, new 175 MVAR capacitor at Ashburn, new 300 MVAR capacitor at Shelhorn, new 150 MVAR capacitor at Liberty	AEC (1.97%) / BGE (14.46%) / Dominion (35.33%) / DPL (3.78%) / JCPL (3.33%) / ME (2.53%) / Neptune (0.63%) / PECO (6.30%) / PEPCO (20.36%) / PPL (3.97%) / PSEG (7.34%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2744	Rebuild the Carson – Rogers Rd 500 kV circuit	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2745	Rebuild 21.32 miles of existing line between Chesterfield – Lakeside 230 kV	Dominion (100%)
b2746.1	Rebuild Line #137 Ridge Rd – Kerr Dam 115 kV, 8.0 miles, for 346 MVA summer emergency rating	Dominion (100%)
b2746.2	Rebuild Line #1009 Ridge Rd – Chase City 115 kV, 9.5 miles, for 346 MVA summer emergency rating	Dominion (100%)
b2746.3	Install a second 4.8 MVAR capacitor bank on the 13.8 kV bus of each transformer at Ridge Rd	Dominion (100%)
b2747	Install a Motor Operated Switch and SCADA control between Dominion’s Gordonsville 115 kV bus and FirstEnergy’s 115 kV line	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2757	Install a +/-125 MVAR Statcom at Colington 230 kV	Dominion (100%)
b2758	Rebuild Line #549 Dooms – Valley 500kV	Dominion (100%)
b2759	Rebuild Line #550 Mt. Storm – Valley 500kV	Dominion (100%)
b2800	The 7 mile section from Dozier to Thompsons Corner of line #120 will be rebuilt to current standards using 768.2 ACSS conductor with a summer emergency rating of 346 MVA at 115 kV. Line is proposed to be rebuilt on single circuit steel monopole structure	Dominion (100%)
b2801	Lines #76 and #79 will be rebuilt to current standard using 768.2 ACSS conductor with a summer emergency rating of 346 MVA at 115 kV. Proposed structure for rebuild is double circuit steel monopole structure	Dominion (100%)
b2802	Rebuild Line #171 from Chase City – Boydton Plank Road tap by removing end-of-life facilities and installing 9.4 miles of new conductor. The conductor used will be at current standards with a summer emergency rating of 393 MVA at 115kV	Dominion (100%)
b2815	Build a new Pinewood 115kV switching station at the tap serving North Doswell DP with a 115kV four breaker ring bus	Dominion (100%)
b2842	Update the nameplate for Mount Storm 500 kV "57272" to be 50kA breaker	Dominion (100%)
b2843	Replace the Mount Storm 500 kV "G2TY" with 50kA breaker	Dominion (100%)
b2844	Replace the Mount Storm 500 kV "G2TZ" with 50kA breaker	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2845	Update the nameplate for Mount Storm 500 kV "G3TSX1" to be 50kA breaker	Dominion (100%)
b2846	Update the nameplate for Mount Storm 500 kV "SX172" to be 50kA breaker	Dominion (100%)
b2847	Update the nameplate for Mount Storm 500 kV "Y72" to be 50kA breaker	Dominion (100%)
b2848	Replace the Mount Storm 500 kV "Z72" with 50kA breaker	Dominion (100%)
b2871	Rebuild 230 kV line #247 from Swamp to Suffolk (31 miles) to current standards with a summer emergency rating of 1047 MVA at 230 kV	Dominion (100%)
b2876	Rebuild line #101 from Mackeys – Creswell 115 kV, 14 miles, with double circuit structures. Install one circuit with provisions for a second circuit. The conductor used will be at current standards with a summer emergency rating of 262 MVA at 115 kV	Dominion (100%)
b2877	Rebuild line #112 from Fudge Hollow – Lowmoor 138 kV (5.16 miles) to current standards with a summer emergency rating of 314 MVA at 138 kV	Dominion (100%)
b2899	Rebuild 230 kV line #231 to current standard with a summer emergency rating of 1046 MVA. Proposed conductor is 2-636 ACSR	Dominion (100%)
b2900	Build a new 230/115 kV switching station connecting to 230 kV network line #2014 (Earleys – Everetts). Provide a 115 kV source from the new station to serve Windsor DP	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2922	Rebuild 8 of 11 miles of 230 kV lines #211 and #228 to current standard with a summer emergency rating of 1046 MVA for rebuilt section. Proposed conductor is 2-636 ACSR	Dominion (100%)
b2928	Rebuild four structures of 500 kV line #567 from Chickahominy to Surry using galvanized steel and replace the river crossing conductor with 3-1534 ACSR. This will increase the line #567 line rating from 1954 MVA to 2600 MVA	Dominion (100%)
b2929	Rebuild 230 kV line #2144 from Winfall to Swamp (4.3 miles) to current standards with a standard conductor (bundled 636 ACSR) having a summer emergency rating of 1047 MVA at 230 kV	Dominion (100%)
b2960	Replace fixed series capacitors on 500 kV Line #547 at Lexington and on 500 kV Line #548 at Valley	Dominion (100%)
b2961	Rebuild approximately 3 miles of Line #205 & Line #2003 from Chesterfield to Locks & Poe respectively	Dominion (100%)
b2962	Split Line #227 (Brambleton – Beaumeade 230 kV) and terminate into existing Belmont substation	Dominion (100%)
b2962.1	Replace the Beaumeade 230 kV breaker “274T2081” with 63kA breaker	Dominion (100%)
b2962.2	Replace the NIVO 230 kV breaker “2116T2130” with 63kA breaker	Dominion (100%)
b2963	Reconductor the Woodbridge to Occoquan 230 kV line segment of Line #2001 with 1047 MVA conductor and replace line terminal equipment at Possum Point, Woodbridge, and Occoquan	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2978	Install 2-125 MVAR STATCOMs at Rawlings and 1-125 MVAR STATCOM at Clover 500 kV substations	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2980	Rebuild 115 kV Line #43 between Staunton and Harrisonburg (22.8 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2981	Rebuild 115 kV Line #29 segment between Fredericksburg and Aquia Harbor to current 230 kV standards (operating at 115 kV) utilizing steel H-frame structures with 2-636 ACSR to provide a normal continuous summer rating of 524 MVA at 115 kV (1047 MVA at 230 kV)	Dominion (100%)

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2989	Install a second 230/115 kV Transformer (224 MVA) approximately 1 mile north of Bremono and tie 230 kV Line #2028 (Bremono – Charlottesville) and 115 kV Line #91 (Bremono - Sherwood) together. A three breaker 230 kV ring bus will split Line #2028 into two lines and Line #91 will also be split into two lines with a new three breaker 115 kV ring bus. Install a temporary 230/115 kV transformer at Bremono substation for the interim until the new substation is complete		Dominion (100%)
b2990	Chesterfield to Basin 230 kV line – Replace 0.14 miles of 1109 ACAR with a conductor which will increase the line rating to approximately 706 MVA		Dominion (100%)
b2991	Chaparral to Locks 230 kV line – Replace breaker lead		Dominion (100%)
b2994	Acquire land and build a new switching station (Skippers) at the tap serving Brink DP with a 115 kV four breaker ring to split Line #130 and terminate the end points		Dominion (100%)
b3018	Rebuild Line #49 between New Road and Middleburg substations with single circuit steel structures to current 115 kV standards with a minimum summer emergency rating of 261 MVA		Dominion (100%)
b3019	Rebuild 500 kV Line #552 Bristers to Chancellor – 21.6 miles long		Dominion (100%)
<u>b3019.1</u>	<u>Update the nameplate for Morrisville 500 kV breaker “H1T594” to be 50kA</u>		<u>Dominion (100%)</u>
<u>b3019.2</u>	<u>Update the nameplate for Morrisville 500 kV breaker “H1T545” to be 50kA</u>		<u>Dominion (100%)</u>

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3020	Rebuild 500 kV Line #574 Ladysmith to Elmont – 26.2 miles long	Dominion (100%)
b3021	Rebuild 500 kV Line #581 Ladysmith to Chancellor – 15.2 miles long	Dominion (100%)
b3026	Reconductor Line #274 (Pleasant View – Ashburn – Beaumeade 230 kV) with a minimum rating of 1200 MVA. Also upgrade terminal equipment	Dominion (100%)
b3027.1	Add a 2nd 500/230 kV 840 MVA transformer at Dominion’s Ladysmith substation	Dominion (100%)
b3027.2	Reconductor 230 kV Line #2089 between Ladysmith and Ladysmith CT substations to increase the line rating from 1047 MVA to 1225 MVA	Dominion (100%)
b3027.3	Replace the Ladysmith 500 kV breaker “H1T581” with 50kA breaker	Dominion (100%)
b3027.4	Update the nameplate for Ladysmith 500 kV breaker “H1T575” to be 50kA breaker	Dominion (100%)
b3027.5	Update the nameplate for Ladysmith 500 kV breaker “568T574” (will be renumbered as “H2T568”) to be 50kA breaker	Dominion (100%)
<u>b3055</u>	<u>Install spare 230/69 kV transformer at Davis substation</u>	<u>Dominion (100%)</u>
b3056	Partial rebuild 230 kV Line #2113 Waller to Lightfoot	Dominion (100%)
b3057	Rebuild 230 kV Lines #2154 and #19 Waller to Skiffes Creek	Dominion (100%)
b3058	Partial rebuild of 230 kV Lines #265, #200 and #2051	Dominion (100%)
<u>b3059</u>	<u>Rebuild 230 kV Line #2173 Loudoun to Elclick</u>	<u>Dominion (100%)</u>

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

<u>b3060</u>	<u>Rebuild 4.6 mile Elklick – Bull Run 230 kV Line #295 and the portion (3.85 miles) of the Clifton – Walney 230 kV Line #265 which shares structures with Line #295</u>		<u>Dominion (100%)</u>
<u>b3088</u>	<u>Rebuild 4.75 mile section of Line #26 between Lexington and Rockbridge with a minimum summer emergency rating of 261 MVA</u>		<u>Dominion (100%)</u>
<u>b3089</u>	<u>Rebuild 230 kV Line #224 between Lanexa and Northern Neck utilizing double circuit structures to current 230 kV standards. Only one circuit is to be installed on the structures with this project with a minimum summer emergency rating of 1047 MVA</u>		<u>Dominion (100%)</u>
<u>b3090</u>	<u>Convert the overhead portion (approx. 1500 feet) of 230 kV Lines #248 & #2023 to underground and convert Glebe substation to gas insulated substation</u>		<u>Dominion (100%)</u>

SCHEDULE 12 – APPENDIX A

(23) American Transmission Systems, Inc.

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2019.2	Terminate Burger – Longview 138 kV, Burger – Brookside 138 kV, Burger – Cloverdale 138 kV #1, and Burger – Harmon 138 kV #2 into Holloway substation; Loop Burger – Harmon #1 138 kV and Burger – Knox 138 kV into Holloway substation	ATSI (100%)
b2019.3	Reconfigure Burger 138 kV substation to accommodate two 138 kV line exits and generation facilities	ATSI (100%)
b2019.4	Remove both Burger 138 kV substations (East and West 138 kV buses) and all 138 kV lines on the property	ATSI (100%)
b2019.5	Terminate and de-energize the 138 kV lines on the last structure before the Burger Plant property	ATSI (100%)
b2122.1	Reconductor the ATSI portion of the Howard – Brookside 138 kV line	ATSI (100%)
b2122.2	Upgrade terminal equipment at Brookside on the Howard – Brookside 138 kV line to achieve ratings of 252/291 (SN/SE)	ATSI (100%)
b2188	Revise the reclosing for the Bluebell 138 kV breaker ‘301-B-94’	ATSI (100%)
b2192	Replace the Longview 138 kV breaker ‘651-B-32’	ATSI (100%)
b2193	Replace the Lowellville 138 kV breaker ‘1-10-B 4’	ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2195	Replace the Roberts 138 kV breaker '601-B-60'	ATSI (100%)
b2196	Replace the Sammis 138 kV breaker '780-B-76'	ATSI (100%)
b2262	New Castle Generating Station – Relocate 138kV, 69kV, and 23kV controls from the generating station building to new control building	ATSI (100%)
b2263	Niles Generation Station – Relocate 138kV and 23kV controls from the generation station building to new control building	ATSI (100%)
b2265	Ashtabula Generating Station – Relocate 138kV controls from the generating station building to new control building	ATSI (100%)
b2284	Increase the design operating temperature on the Cloverdale – Barberton 138kV line	ATSI (100%)
b2285	Increase the design operating temperature on the Cloverdale – Star 138kV line	ATSI (100%)
b2301	Reconductor 0.7 miles of 605 ACSR conductor on the Beaver Black River 138kV line	ATSI (100%)
b2301.1	Wave trap and line drop replacement at Beaver (312/380 MVA SN/SE)	ATSI (100%)
b2349	Replace the East Springfield 138kV breaker 211-B-63 with 40kA	ATSI (100%)
b2367	Replace the East Akron 138kV breaker 36-B-46 with 40kA	ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2413	Replace a relay at McDowell 138 kV substation	ATSI (100%)
b2434	Build a new London – Tangy 138 kV line	ATSI (100%)
b2435	Build a new East Springfield – London #2 138 kV line	ATSI (100%)
b2459	Install +260/-150 MVAR SVC at Lake Shore	ATSI (100%)
b2492	Replace the Beaver 138 kV breaker ‘426-B-2’ with 63kA breaker	ATSI (100%)
b2493	Replace the Hoytdale 138kV breaker ‘83-B-30’ with 63kA breaker	ATSI (100%)
b2557	At Avon substation, replace the existing 345/138 kV 448 MVA #92 transformer with a 560 MVA unit	ATSI (100%)
b2558	Close normally open switch A 13404 to create a Richland J Bus – Richland K Bus 138 kV line	ATSI (100%)
b2559	Reconductor the Black River – Lorain 138 kV line and upgrade Black River and Lorain substation terminal end equipment	ATSI (100%)
b2560	Construct a second 138 kV line between West Fremont and Hayes substation on open tower position of the West Fremont –Groton –Hayes 138 kV line	ATSI (100%)
b2616	Addition of 4th 345/138 kV transformer at Harding	ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2673	Rebuild the existing double circuit tower line section from Beaver substation to Brownhelm Jct. approx. 2.8 miles		ATSI (100%)
b2674	Rebuild the 6.6 miles of Evergreen to Ivanhoe 138 kV circuit with 477 ACSS conductor		ATSI (100%)
b2675	Install 26.4 MVAR capacitor and associated terminal equipment at Lincoln Park 138 kV substation		ATSI (100%)
b2725	Build new 345/138 kV Lake Avenue substation w/ breaker and a half high side (2 strings), 2-345/138 kV transformers and breaker and a half (2 strings) low side (138 kV). Substation will tie Avon – Beaver 345 kV #1/#2 and Black River – Johnson #1/#2 lines		ATSI (100%)
b2725.1	Replace the Murray 138 kV breaker ‘453-B-4’ with 40kA breaker		ATSI (100%)
b2742	Replace the Hoytdale 138 kV ‘83-B-26’ and ‘83-B-30’ breakers with 63kA breakers		ATSI (100%)
b2753.4	Double capacity for 6 wire “Burger-Cloverdale No. 2” 138 kV line and connect at Holloway and “Point A”		ATSI (100%)
b2753.5	Double capacity for 6 wire “Burger-Longview” 138 kV line and connect at Holloway and “Point A”		ATSI (100%)
b2778	Add 2nd 345/138 kV transformer at Chamberlin substation		ATSI (100%)
b2780	Replace Bruce Mansfield 345 kV breaker ‘B57’ with an 80 kA breaker, and associated gang-operated disconnect switches D56 and D58		ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2869	Replace the Crossland 138 kV breaker "B-16" with a 40kA breaker	ATSI (100%)
b2875	Relocate the Richland to Ridgeville 138 kV line from Richland J bus to K, extend the K bus and install a new breaker	ATSI (100%)
b2896	Rebuild/Reconductor the Black River – Lorain 138 kV circuit	ATSI (100%)
b2897	Reconductor the Avon – Lorain 138 kV section and upgrade line drop at Avon	ATSI (100%)
b2898	Reconductor the Beaver – Black River 138 kV with 954Kcmil ACSS conductor and upgrade terminal equipment on both stations	ATSI (100%)
b2942.1	Install a 100 MVAR 345 kV shunt reactor at Hayes substation	ATSI (100%)
b2942.2	Install a 200 MVAR 345 kV shunt reactor at Bayshore substation	ATSI (100%)
b2972	Reconductor limiting span of Lallendorf – Monroe 345 kV	MISO (11.00%) / AEP (5.38%) / APS (4.27%) / ATSI (66.48%) / Dayton (2.71%) / Dominion (5.31%) / DL (4.85%)
b3031	Transfer load off of the Leroy Center - Mayfield Q2 138 kV line by reconfiguring the Pawnee substation primary source, via the existing switches, from the Leroy Center - Mayfield Q2 138 kV line to the Leroy Center - Mayfield Q1 138 kV line	ATSI (100%)

American Transmission Systems, Inc. (cont.)

<i>Required Transmission Enhancements</i>	<i>Annual Revenue Requirement</i>	<i>Responsible Customer(s)</i>
b3032 Greenfield - NASA 138 kV terminal upgrades: NASA substation, Greenfield exit: Revise CT tap on breaker B22 and adjust line relay settings; Greenfield substation, NASA exit: Revise CT tap on breaker B1 and adjust line relay settings; replace 336.4 ACSR line drop with 1033.5 AL		ATSI (100%)
b3033 Ottawa – Lakeview 138 kV reconductor and substation upgrades		ATSI (100%)
b3034 Lakeview – Greenfield 138 kV reconductor and substation upgrades		ATSI (100%).
<u>b3066</u> <u>Reconductor the Cranberry – Jackson 138 kV line (2.1 miles), reconductor 138 kV bus at Cranberry bus and replace 138 kV line switches at Jackson bus</u>		<u>ATSI (100%)</u>
<u>b3067</u> <u>Reconductor the Jackson – Maple 138 kV line (4.7 miles), replace line switches at Jackson 138 kV and replace the line traps and relays at Maple 138 kV bus</u>		<u>ATSI (100%)</u>
<u>b3080</u> <u>Reconductor the 138 kV bus at Seneca</u>		<u>ATSI (100%)</u>
<u>b3081</u> <u>Replace the 138 kV breaker and reconductor the 138 kV bus at Krendale</u>		<u>ATSI (100%)</u>

SCHEDULE 12 – APPENDIX A

(25) East Kentucky Power Cooperative, Inc.

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2066 Upgrade the operating temperature of the existing conductor for the JK Smith - Union City - Lake Reba Tap 138 kV line		EKPC (100%)
b2309 Upgrade the bus and jumpers with 750 MCM copper conductor at Green County 69 kV substation		EKPC (100%)
b2310 Increase the maximum operating temperature of the North Springfield - South Springfield 69 kV line to 167 degrees Fahrenheit		EKPC (100%)
b2311 Increase the maximum operating temperature of the Loretto - Sulphur Creek 69 kV line to 167 degrees Fahrenheit		EKPC (100%)
b2312 Increase the maximum operating temperature of the South Springfield - Loretto 69 kV line to 167 degrees Fahrenheit		EKPC (100%)
b2313 Construct 8.8 miles of 69 kV line between the Cave City and Bon Ayr distribution substations. Operate this line normally open		EKPC (100%)
b2314.1 Construct 8.6 miles of 69 kV line between the Mercer County Industrial and Van Arsdell distribution substation. Construct a new 69 kV switching station adjacent to Bonds Bill Substation. Loop NorthSpringfield - Van Arsdell 69 kV line through South Anders		EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2314.2	Construct a new 69 kV switching station ("South Anderson") adjacent to the LGE/KU Bonds Mill substation	EKPC (100%)
b2314.3	Loop the North Springfield - Van Arsdell 69 kV line through South Anderson. Terminate the existing 69 kV to the LGE/KU Bonds Mill substation at South Anderson and establish a second 69 kV from S. Anderson to the LGE/KU Bonds Mill sub	EKPC (100%)
b2314.4	Construct 0.12 miles of 69 kV line from South Anderson to the Powell Taylor distribution substation and serve this substation radially from South Anderson	EKPC (100%)
b2315	Increase the size of the existing HT Adams 69 kV, 7.2 MVAR capacitor bank to 14.28 MVAR	EKPC (100%)
b2316	Increase the size of the existing Hunt Farm Junction 69 kV, 8.2 MVAR capacitor bank to 16.33 MVAR	EKPC (100%)
b2317	Construct 10.9 miles of 69 kV line between the Owen County substation and the Keith distribution substation. Operate the existing Penn - Keith 69 kV line normally - open	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2318 Construct 2.7 miles of 69 kV line between the Fox Hollow substation and the Parkway distribution substations. Serve the Parkway #1 and #2 distribution substations radially from Fox Hollow. Operate the Cave City - Bon Ayr 69 kV line normally - closed		EKPC (100%)
b2319 Increase the maximum operating temperature of the Helechawa - Sublett 69 kV line to 167 degrees Fahrenheit		EKPC (100%)
b2320 Install a 69 kV, 15.31 MVAR capacitor bank at the Perryville substation		EKPC (100%)
b2321 Install a 69 kV, 25.51 MVAR capacitor bank at the Veechdale substation		EKPC (100%)
b2322 Change the CT setting on circuit breaker N35 - 804 at Dale Station to at least 800 amps to increase the relay loadability on the Dale - Three Forks 138 kV line to at least 282 MVA		EKPC (100%)
b2323 Rebuild the existing Cynthiana - Headquarters 69 kV line using 556.5 MCM ACSR conductor and operate this line normally closed		EKPC (100%)
b2324 Remove the existing 1200 - amp line traps at JK Smith and Dale associated with the JK Smith - Dale 138 kV line		EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2325	Increase the maximum operating temperature of the Glendale - Hodgenville 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2326	Increase the maximum operating temperature of the Fayette - Davis 69 kV line to 248 degrees Fahrenheit	EKPC (100%)
b2327	Increase the maximum operating temperature of the Boone - Boone Distribution 69 kV line to 302 degrees Fahrenheit	EKPC (100%)
b2328	Increase the maximum operating temperature of the West Bardstown Junction - West Bardstown 69 kV line to 284 degrees Fahrenheit	EKPC (100%)
b2329	Increase the maximum operating temperature of the Magnolia - Summersville 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2330	Increase the maximum operating temperature of the Bacon Creek - Liberty Church 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2331	Increase the maximum operating temperature of the Headquarters - Millersburg Junction 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2332	Increase the maximum operating temperature of the JK Smith - Dale 138 kV line to 275 degrees Fahrenheit	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2333	Increase the maximum operating temperature of the Elizabethtown - Tunnel Hill 69 kV line to 284 degrees Fahrenheit	EKPC (100%)
b2334	Install a 69 kV, 28.06 MVAR capacitor bank at the Owen County substation	EKPC (100%)
b2335	Install a 69 kV, 14.29 MVAR capacitor bank at the Magoffin County substation	EKPC (100%)
b2336	Increase the maximum operating temperature of the South Corbin - Bacon Creek 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2337	Increase the size of the existing Cedar Grove 69 kV, 10.8 MVAR capacitor bank to 20.41 MVAR	EKPC (100%)
b2339	Upgrade the 4/0 copper bus and jumpers at the Nelson County substation associated with the Nelson County - West Bardstown Junction 69 kV line using 500 MCM copper or equivalent equipment	EKPC (100%)
b2340	Increase the Zone 3 distance relay setting at Barren County associated with the Barren County - Horse Cave Tap 69 kV line to at least 85 MVA	EKPC (100%)
b2414	Build the 2nd Summer Shade EKPC - Summer Shade TVA 161 kV circuit	EKPC (100%)
b2544	Increase the MOT of the 266.8 MCM ACSR section (1.4 miles), of the Kargle-KU Elizabethtown 69 kV line section to 266 degrees F	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2614	Decouple the double-circuited Spurlock – Maysville Industrial Tap 138-kV & Spurlock – Flemingsburg 138-kV line segments	EKPC (100%)
b2615	Upgrade the Bullitt County 161/69 kV transformer facility	EKPC (100%)
b2655	Increase the size of the existing Leon 69 kV capacitor bank from 13.2 MVAR to 18.36 MVAR	EKPC (100%)
b2656	Reconductor the Leon – Airport Road 69 kV line section (5.72 miles) using 556.5 MCM ACTW conductor	EKPC (100%)
b2657	Add 69 kV breaker at Thelma – AEP Thelma 69 kV tie	EKPC (100%)
b2658	Increase the zone 3 distance relay setting at Barren County associated with the Barren County – Horse Cave Junction line to at least 103 MVA	EKPC (100%)
b2659	Rebuild the Seymour Tap – KU Horse Cave Tap 69 kV line section (1.98 miles) to 302 degrees F	EKPC (100%)
b2660	Increase the zone 3 distance relay setting at Elizabethtown associated with the Elizabethtown – Smithersville line section to at least 100 MVA	EKPC (100%)
b2661	Reconductor the Baker Lane – Holloway Junction 69 kV (1.28 miles) line section using 556.5 MCM ACTW wire	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2662	Increase the maximum operating temperature of the Hickory Plains – PPG 69 kV line section (0.21 miles) to 266 degrees F	EKPC (100%)
b2663	Increase the zone 3 distance relay setting at EKPC Elizabethtown associated with the EKPC Elizabethtown to KU Elizabethtown 69 kV line to at least 126 MVA	EKPC (100%)
b2664	Increase the maximum operating temperature of the Tharp Tap – KU Elizabethtown 69 kV line section (2.11 miles) to 266 degrees F. (LTE at 248 degrees F)	EKPC (100%)
b2710	Upgrade the Summer Shade bus and CT associated with the 161/69 kV transformer #1	EKPC (100%)
b2711	Install 25.5 MVAR 69 kV capacitor at Sewellton Junction 69 kV substation	EKPC (100%)
b2730	Upgrade Denny – Gregory Tap 69 kV line facility	EKPC (100%)
b2781	Increase maximum operating temperature of Davis – Nicholasville 69 kV line section 266.8 MCM conductor to 284°F (LTE of 266°F)	EKPC (100%)
b2782	Increase the maximum operating temperature of Plumville – Rectorville 69 kV line section 266.8 MCM conductor to 212°F (LTE of 185°F)	EKPC (100%)
b2783	Rebuild the Davis – Fayette 69 kV line section to 556.5 MCM (3.15 miles)	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2784	Increase overcurrent relay at West Berea 138/69 kV to at least 139 MVA Winter LTE	EKPC (100%)
b2785	Install a 13.776 MVAR cap bank at Three Links 69 kV	EKPC (100%)
b2786	Increase Williamstown cap bank to 11.225 MVAR	EKPC (100%)
b2827	Upgrade the current 5% impedance 1200A line reactor, which connects the 4SPURLOCK – 4SPUR-KENT-R and 4SPUR-KENT-R – 4KENTON 138kV line sections, to a 6.5% impedance 1600A line reactor	EKPC (100%)
b2879.2	Reconductor EKPC portion of the Stuart – Spurlock 345 kV line	EKPC (100%)
b2893	Rebuild the existing (1.5 mile), 1/0 MCM ACSR South Bardstown – West Bardstown Jct. 69 kV line using 556.5 MCM ACTW conductor	EKPC (100%)
b2902	Rebuild the Brodhead – Three Links Jct. 69 kV line section (8.2 miles) using 556.5 MCM ACTW wire	EKPC (100%)
b2903	Raise the V-low setting for Summer Shade 69 kV cap bank to 1.01 pu	EKPC (100%)
b2904	Raise the V-low setting for Newby 69 kV cap bank to 0.955 pu	EKPC (100%)
b2905	Resize the Albany 69 kV capacitor bank from 8.4 to 13.776 MVAR	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2906	Increase the Zone 3 distance relay setting at Baker Lane associated with the Baker Lane - Holloway Jct. 69 kV line to at least 142 MVA LTE Winter	EKPC (100%)
b2907	Upgrade the metering CT associated with the Clay Village - KU Clay Village 69 kV tap line section to 600 A; at least 64 MVA Winter LTE. Upgrade the distance relay associated with the Clay Village - KU Clay Village 69 kV tap line section to at least 64 MVA	EKPC (100%)
b2908	Upgrade the distance relay associated with Dale – JK Smith 138 kV line section to 362 MVA normal rating	EKPC (100%)
b2909	Increase the MOT of the EKPC Elizabethtown – Tharp Tap 69 kV line section (1.7 miles) to 302°F (LTE at 284°F)	EKPC (100%)
b2910	Upgrade the distance relay at the Hodgenville station associated with the Glendale – Hodgenville 69 kV line section to at least 90 MVA Winter LTE	EKPC (100%)
b2911	Upgrade the overcurrent relay setting associated with Powell County 138/69 kV transformer to at least 139 MVA Winter LTE	EKPC (100%)
b2912	Upgrade the existing S408-605, 600 A KU Russell Springs Tap – Russell County 69 kV disconnect switch to 1200 A	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2913	Upgrade distance relay at the Stephensburg station associated with Stephensburg – Glendale 69 kV line section to at least Winter LTE 100 MVA	EKPC (100%)
b2914	Rebuild Tharp Tap – KU Elizabethtown 69 kV line section to 795 MCM (2.11 miles)	EKPC (100%)
b2915	Resize the sideview 69 kV capacitor bank from 6.12 MVAR to 9.18 MVAR	EKPC (100%)
b2916	Upgrade the existing metering CTs (Quantity of 2) associated with the East Bardstown - KU Bardstown Industrial Tap 69 kV line section to 1200 A, at least 100 MVA Winter LTE; and upgrade the existing East Bardstown bus and jumpers from 4/0 to 500 MCM copper	EKPC (100%)
b2917	Replace the existing 100 MVA 138/69 kV transformer bank at the West Berea substation with a 150 MVA transformer	EKPC (100%)
b2918	Upgrade the 4/0 bus and jumpers associated with the West Berea Jct. – Three Links Jct. 69 kV line to 500 MCM copper or equivalent equipment at the Three Links Jct. substation	EKPC (100%)
b2919	Install a 69 kV, 15.31 MVAR capacitor bank at South Anderson substation	EKPC (100%)
b2920	Rebuild Boone - Big Bone Tap 69 kV line section using 556.5 MCM ACTW	EKPC (100%)

	conductor (6.3 miles)		
--	-----------------------	--	--

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2921	New TVA 161 kV interconnection to TVA's East Glasgow Tap - East Glasgow 161 kV line section (~1 mile due West of Fox Hollow). Add Fox Hollow 161/69 kV 150 MVA transformer. Construct new Fox Hollow - Fox Hollow Jct. 161 kV line section using 795 MCM ACSR (~1 mile) and new 161 kV switching station at point of interconnection with TVA	EKPC (100%)
b2939	Increase the conductor MOT for the Dale – JK Smith 138 kV line to 275°F. The new summer ratings would be 229/296	EKPC (100%)
b2940	Upgrade the distance relay on the Wayne Co – Wayne Co KY 161 kV line to increase the line winter rating would be 167/167	EKPC (100%)
b3044	<i>Increase the MOT of the double circuit Cooper – Somerset 69 kV line 266.8 MCM conductor from 212°F to 266°F</i>	<i>EKPC (100%)</i>
b3045	<i>Increase the MOT of Liberty Church tap – Bacon Creek tap 69 kV line 266.8 MCM conductor from 212°F to 266°F</i>	<i>EKPC (100%)</i>
b3046	<i>Increase the MOT of Summer Shade – JB Galloway Jct. 69 kV line 266.8 MCM conductor from 167°F to 212°F</i>	<i>EKPC (100%)</i>

East Kentucky Power Cooperative, Inc. (cont.)

<i>Required Transmission Enhancements</i>	<i>Annual Revenue Requirement</i>	<i>Responsible Customer(s)</i>
<p>b3047</p>	<p><i>Upgrade the existing 4/0 CU line jumpers with double 500 MCM CU associated with the Green Co - KU Green Co 69 kV line section. Also, replace the existing 600 A disconnect switches with 1200 A associated with the Green Co 161/69 kV transformer</i></p>	<p><i>EKPC (100%)</i></p>
<p><u>b3094</u></p>	<p><u>Move 69 kV 12.0 MVAR capacitor bank from Greenbriar to Bullitt Co 69 kV substation</u></p>	<p><u>EKPC (100%)</u></p>

Attachment C

Schedule 12 – Appendix A of the
PJM Open Access Transmission Tariff

(Clean Format)

SCHEDULE 12 – APPENDIX A

(7) Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2212 Shawville Substation: Relocate 230 kV and 115 kV controls from the generating station building to new control building		PENELEC (100%)
b2293 Replace the Erie South 115 kV breaker 'Buffalo Rd' with 40kA breaker		PENELEC (100%)
b2294 Replace the Johnstown 115 kV breaker 'Bon Aire' with 40kA breaker		PENELEC (100%)
b2302 Replace the Erie South 115 kV breaker 'French #2' with 40kA breaker		PENELEC (100%)
b2304 Replace the substation conductor and switch at South Troy 115 kV substation		PENELEC (100%)
b2371 Install 75 MVAR capacitor at the Erie East 230 kV substation		PENELEC (100%)
b2441 Install +250/-100 MVAR SVC at the Erie South 230 kV station		PENELEC (100%)
b2442 Install three 230 kV breakers on the 230 kV side of the Lewistown #1, #2 and #3 transformers		PENELEC (100%)
b2450 Construct a new 115 kV line from Central City West to Bedford North		PENELEC (100%)
b2463 Rebuild and re-conductor 115 kV line from East Towanda to S. Troy and upgrade terminal equipment at East Towanda, Tennessee Gas and South Troy		PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2494	Construct Warren 230 kV ring bus and install a second Warren 230/115 kV transformer	PENELEC (100%)
b2552.1	Reconductor the North Meshoppen – Oxbow-Lackawanna 230 kV circuit and upgrade terminal equipment (MAIT portion)	PENELEC (100%)
b2573	Replace the Warren 115 kV 'B12' breaker with a 40kA breaker	PENELEC (100%)
b2587	Reconfigure Pierce Brook 345 kV station to a ring bus and install a 125 MVAR shunt reactor at the station	PENELEC (100%)
b2621	Replace relays at East Towanda and East Sayre 115 kV substations (158/191 MVA SN/SE)	PENELEC (100%)
b2677	Replace wave trap, bus conductor and relay at Hilltop 115 kV substation. Replace relays at Prospect and Cooper substations	PENELEC (100%)
b2678	Convert the East Towanda 115 kV substation to breaker and half configuration	PENELEC (100%)
b2679	Install a 115 kV Venango Jct. line breaker at Edinboro South	PENELEC (100%)
b2680	Install a 115 kV breaker on Hooversville #1 115/23 kV transformer	PENELEC (100%)
b2681	Install a 115 kV breaker on the Eclipse #2 115/34.5 kV transformer	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2682	Install two 21.6 MVAR capacitors at the Shade Gap 115 kV substation	PENELEC (100%)
b2683	Install a 36 MVAR 115 kV capacitor and associated equipment at Morgan Street substation	PENELEC (100%)
b2684	Install a 36 MVAR 115 kV capacitor at Central City West substation	PENELEC (100%)
b2685	Install a second 115 kV 3000A bus tie breaker at Hooversville substation	PENELEC (100%)
b2735	Replace the Warren 115 kV 'NO. 2 XFMR' breaker with 40kA breaker	PENELEC (100%)
b2736	Replace the Warren 115 kV 'Warren #1' breaker with 40kA breaker	PENELEC (100%)
b2737	Replace the Warren 115 kV 'A TX #1' breaker with 40kA breaker	PENELEC (100%)
b2738	Replace the Warren 115 kV 'A TX #2' breaker with 40kA breaker	PENELEC (100%)
b2739	Replace the Warren 115 kV 'Warren #2' breaker with 40kA breaker	PENELEC (100%)
b2740	Revise the reclosing of the Hooversville 115 kV 'Ralphton' breaker	PENELEC (100%)
b2741	Revise the reclosing of the Hooversville 115 kV 'Statler Hill' breaker	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2743.2	Tie in new Rice substation to Conemaugh – Hunterstown 500 kV	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2743.3	Upgrade terminal equipment at Conemaugh 500 kV on the Conemaugh – Hunterstown 500 kV circuit	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2748	Install two 28 MVAR capacitors at Tiffany 115 kV substation	PENELEC (100%)
b2767	Construct a new 345 kV breaker string with three (3) 345 kV breakers at Homer City and move the North autotransformer connection to this new breaker string	PENELEC (100%)
b2803	Reconductor 3.7 miles of the Bethlehem – Leretto 46 kV circuit and replace terminal equipment at Summit 46 kV	PENELEC (100%)
b2804	Install a new relay and replace 4/0 CU bus conductor at Huntingdon 46 kV station, on the Huntingdon – C tap 46 kV circuit	PENELEC (100%)
b2805	Install a new relay and replace 4/0 CU & 250 CU substation conductor at Hollidaysburg 46 kV station, on the Hollidaysburg – HCR Tap 46 kV circuit	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2806	Install a new relay and replace meter at the Raystown 46 kV substation, on the Raystown – Smithfield 46 kV circuit	PENELEC (100%)
b2807	Replace the CHPV and CRS relay, and adjust the IAC overcurrent relay trip setting; or replace the relay at Eldorado 46 kV substation, on the Eldorado – Gallitzin 46 kV circuit	PENELEC (100%)
b2808	Adjust the JBC overcurrent relay trip setting at Raystown 46 kV, and replace relay and 4/0 CU bus conductor at Huntingdon 46 kV substations, on the Raystown – Huntingdon 46 kV circuit	PENELEC (100%)
b2865	Replace Seward 115 kV breaker "Jackson Road" with 63kA breaker	PENELEC (100%)
b2866	Replace Seward 115 kV breaker "Conemaugh N." with 63kA breaker	PENELEC (100%)
b2867	Replace Seward 115 kV breaker "Conemaugh S." with 63kA breaker	PENELEC (100%)
b2868	Replace Seward 115 kV breaker "No.8 Xfmr" with 63kA breaker	PENELEC (100%)
b2944	Install two 345 kV 80 MVAR shunt reactors at Mainesburg station	PENELEC (100%)

Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2951	Seward, Blairsville East, Shelocta work	PENELEC (100%)
b2951.1	Upgrade Florence 115 kV line terminal equipment at Seward SS	PENELEC (100%)
b2951.2	Replace Blairsville East / Seward 115 kV line tuner, coax, line relaying and carrier set at Shelocta SS	PENELEC (100%)
b2951.3	Replace Seward / Shelocta 115 kV line CVT, tuner, coax, and line relaying at Blairsville East SS	PENELEC (100%)
b2952	Replace the North Meshoppen #3 230/115 kV transformer eliminating the old reactor and installing two breakers to complete a 230 kV ring bus at North Meshoppen	PENELEC (100%)
b2953	Replace the Keystone 500 kV breaker "NO. 14 Cabot" with 50kA breaker	PENELEC (100%)
b2954	Replace the Keystone 500 kV breaker "NO. 16 Cabot" with 50kA breaker	PENELEC (100%)
b2984	Reconfigure the bus at Glory and install a 50.4 MVAR 115 kV capacitor	PENELEC (100%)
b3007.2	Reconductor the Blairsville East to Social Hall 138 kV line and upgrade terminal equipment - PENELEC portion. 4.8 miles total. The new conductor will be 636 ACSS replacing the existing 636 ACSR conductor. At Blairsville East, the wave trap and breaker disconnects will be replaced	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3008	Upgrade Blairsville East 138/115 kV transformer terminals. This project is an upgrade to the tap of the Seward – Shelocta 115 kV line into Blairsville substation. The project will replace the circuit breaker and adjust relay settings	PENELEC (100%)
b3009	Upgrade Blairsville East 115 kV terminal equipment. Replace 115 kV circuit breaker and disconnects	PENELEC (100%)
b3014	Replace the existing Shelocta 230/115 kV transformer and construct a 230 kV ring bus	PENELEC (100%)
b3016	Upgrade terminal equipment at Corry East 115 kV to increase rating of Four Mile to Corry East 115 kV line. Replace bus conductor	PENELEC (100%)
b3017.1	Rebuild Glade to Warren 230 kV line with hi-temp conductor and substation terminal upgrades. 11.53 miles. New conductor will be 1033 ACSS. Existing conductor is 1033 ACSR	ATSI (61.61%) / PENELEC (38.39%)
b3017.2	Glade substation terminal upgrades. Replace bus conductor, wave traps, and relaying	ATSI (61.61%) / PENELEC (38.39%)
b3017.3	Warren substation terminal upgrades. Replace bus conductor, wave traps, and relaying	ATSI (61.61%) / PENELEC (38.39%)
b3022	Replace Saxton 115 kV breaker 'BUS TIE' with a 40kA breaker	PENELEC (100%)

**Mid-Atlantic Interstate Transmission, LLC for the Pennsylvania Electric Company Zone
(cont.)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3024	Upgrade terminal equipment at Corry East 115 kV to increase rating of Warren to Corry East 115 kV line. Replace bus conductor	PENELEC (100%)
b3043	<i>Install one 115 kV 36 MVAR capacitor at West Fall 115 kV substation</i>	<i>PENELEC (100%)</i>
b3073	Replace the Blairsville East 138/115 kV transformer and associated equipment such as breaker disconnects and bus conductor	PENELEC (100%)
b3077	Reconductor the Franklin Pike B – Wayne 115 kV line (6.78 miles)	PENELEC (100%)
b3078	Reconductor the 138 kV bus and replace the line trap, relays Morgan Street. Reconductor the 138 kV bus at Venango Junction	PENELEC (100%)
b3082	Construct 4-breaker 115 kV ring bus at Geneva	PENELEC (100%)

SCHEDULE 12 – APPENDIX A

(14) Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2117	Reconductor 0.33 miles of the Parkersburg - Belpre line and upgrade Parkersburg terminal equipment	APS (100%)
b2118	Add 44 MVAR Cap at New Martinsville	APS (100%)
b2120	Six-Wire Lake Lynn - Lardin 138 kV circuits	APS (100%)
b2142	Replace Weirton 138 kV breaker “Wylie Ridge 210” with 63 kA breaker	APS (100%)
b2143	Replace Weirton 138 kV breaker “Wylie Ridge 216” with 63 kA breaker	APS (100%)
b2174.8	Replace relays at Mitchell substation	APS (100%)
b2174.9	Replace primary relay at Piney Fork substation	APS (100%)
b2174.10	Perform relay setting changes at Bethel Park substation	APS (100%)
b2213	Armstrong Substation: Relocate 138 kV controls from the generating station building to new control building	APS (100%)
b2214	Albright Substation: Install a new control building in the switchyard and relocate controls and SCADA equipment from the generating station building the new control center	APS (100%)
b2215	Rivesville Switching Station: Relocate controls and SCADA equipment from the generating station building to new control building	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2216	Willow Island: Install a new 138 kV cross bus at Belmont Substation and reconnect and reconfigure the 138 kV lines to facilitate removal of the equipment at Willow Island switching station	APS (100%)
b2235	130 MVAR reactor at Monocacy 230 kV	APS (100%)
b2260	Install a 32.4 MVAR capacitor at Bartonville	APS (100%)
b2261	Install a 33 MVAR capacitor at Damascus	APS (100%)
b2267	Replace 1000 Cu substation conductor and 1200 amp wave trap at Marlowe	APS (100%)
b2268	Reconductor 6.8 miles of 138kV 336 ACSR with 336 ACSS from Double Toll Gate to Riverton	APS (100%)
b2299	Reconductor from Collins Ferry - West Run 138 kV with 556 ACSS	APS (100%)
b2300	Reconductor from Lake Lynn - West Run 138 kV	APS (100%)
b2341	Install 39.6 MVAR Capacitor at Shaffers Corner 138 kV Substation	APS (100%)
b2342	Construct a new 138 kV switching station (Shuman Hill substation), which is next the Mobley 138 kV substation and install a 31.7 MVAR capacitor	APS (100%)
b2343	Install a 31.7 MVAR capacitor at West Union 138 kV substation	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2362	Install a 250 MVAR SVC at Squab Hollow 230 kV	APS (100%)
b2362.1	Install a 230 kV breaker at Squab Hollow 230 kV substation	APS (100%)
b2363	Convert the Shingletown 230 kV bus into a 6 breaker ring bus	APS (100%)
b2364	Install a new 230/138 kV transformer at Squab Hollow 230 kV substation. Loop the Forest - Elko 230 kV line into Squab Hollow. Loop the Brookville - Elko 138 kV line into Squab Hollow	APS (100%)
b2412	Install a 44 MVAR 138 kV capacitor at the Hempfield 138 kV substation	APS (100%)
b2433.1	Install breaker and a half 138 kV substation (Waldo Run) with 4 breakers to accommodate service to MarkWest Sherwood Facility including metering which is cut into Glen Falls Lamberton 138 kV line	APS (100%)
b2433.2	Install a 70 MVAR SVC at the new WaldoRun 138 kV substation	APS (100%)
b2433.3	Install two 31.7 MVAR capacitors at the new WaldoRun 138 kV substation	APS (100%)
b2424	Replace the Weirton 138 kV breaker 'WYLIE RID210' with 63 kA breakers	APS (100%)
b2425	Replace the Weirton 138 kV breaker 'WYLIE RID216' with 63 kA breakers	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2426	Replace the Oak Grove 138 kV breaker 'OG1' with 63 kA breakers	APS (100%)
b2427	Replace the Oak Grove 138 kV breaker 'OG2' with 63 kA breakers	APS (100%)
b2428	Replace the Oak Grove 138 kV breaker 'OG3' with 63 kA breakers	APS (100%)
b2429	Replace the Oak Grove 138 kV breaker 'OG4' with 63 kA breakers	APS (100%)
b2430	Replace the Oak Grove 138 kV breaker 'OG5' with 63 kA breakers	APS (100%)
b2431	Replace the Oak Grove 138 kV breaker 'OG6' with 63 kA breakers	APS (100%)
b2432	Replace the Ridgeley 138 kV breaker 'RC1' with a 40 kA rated breaker	APS (100%)
b2440	Replace the Cabot 138kV breaker 'C9-KISKI VLY' with 63kA	APS (100%)
b2472	Replace the Ringgold 138 kV breaker 'RCM1' with 40kA breakers	APS (100%)
b2473	Replace the Ringgold 138 kV breaker '#4 XMFR' with 40kA breakers	APS (100%)
b2475	Construct a new line between Oak Mound 138 kV substation and Waldo Run 138 kV substation	APS (100%)
b2545.1	Construct a new 138 kV substation (Shuman Hill substation) connected to the Fairview –Willow Island (84) 138 kV line	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2545.2	Install a ring bus station with five active positions and two 52.8 MVAR capacitors with 0.941 mH reactors	APS (100%)
b2545.3	Install a +90/-30 MVAR SVC protected by a 138 kV breaker	APS (100%)
b2545.4	Remove the 31.7 MVAR capacitor bank at Mobley 138 kV	APS (100%)
b2546	Install a 51.8 MVAR (rated) 138 kV capacitor at Nyswaner 138 kV substation	APS (100%)
b2547.1	Construct a new 138 kV six breaker ring bus Hillman substation	APS (100%)
b2547.2	Loop Smith- Imperial 138 kV line into the new Hillman substation	APS (100%)
b2547.3	Install +125/-75 MVAR SVC at Hillman substation	APS (100%)
b2547.4	Install two 31.7 MVAR 138 kV capacitors	APS (100%)
b2548	Eliminate clearance de-rate on Wylie Ridge – Smith 138 kV line and upgrade terminals at Smith 138 kV, new line ratings 294 MVA (Rate A)/350 MVA (Rate B)	APS (100%)
b2612.1	Relocate All Dam 6 138 kV line and the 138 kV line to AE units 1&2	APS (100%)
b2612.2	Install 138 kV, 3000A bus-tie breaker in the open bus-tie position next to the Shaffers corner 138 kV line	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2612.3	Install a 6-pole manual switch, foundation, control cable, and all associated facilities	APS (100%)
b2666	Yukon 138 kV Breaker Replacement	APS (100%)
b2666.1	Replace Yukon 138 kV breaker "Y-11(CHARL1)" with an 80 kA breaker	APS (100%)
b2666.2	Replace Yukon 138 kV breaker "Y-13(BETHEL)" with an 80 kA breaker	APS (100%)
b2666.3	Replace Yukon 138 kV breaker "Y-18(CHARL2)" with an 80 kA breaker	APS (100%)
b2666.4	Replace Yukon 138 kV breaker "Y-19(CHARL2)" with an 80 kA breaker	APS (100%)
b2666.5	Replace Yukon 138 kV breaker "Y-4(4B-2BUS)" with an 80 kA breaker	APS (100%)
b2666.6	Replace Yukon 138 kV breaker "Y-5(LAYTON)" with an 80 kA breaker	APS (100%)
b2666.7	Replace Yukon 138 kV breaker "Y-8(HUNTING)" with an 80 kA breaker	APS (100%)
b2666.8	Replace Yukon 138 kV breaker "Y-9(SPRINGD)" with an 80 kA breaker	APS (100%)
b2666.9	Replace Yukon 138 kV breaker "Y-10(CHRL-SP)" with an 80 kA breaker	APS (100%)
b2666.10	Replace Yukon 138 kV breaker "Y-12(1-1BUS)" with an 80 kA breaker	APS (100%)
b2666.11	Replace Yukon 138 kV breaker "Y-14(4-1BUS)" with an 80 kA breaker	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2666.12	Replace Yukon 138 kV breaker “Y-2(1B-BETHE)” with an 80 kA breaker	APS (100%)
b2666.13	Replace Yukon 138 kV breaker “Y-21(SHEPJ)” with an 80 kA breaker	APS (100%)
b2666.14	Replace Yukon 138 kV breaker “Y-22(SHEPHJT)” with an 80 kA breaker	APS (100%)
b2672	Change CT Ratio at Seneca Caverns from 120/1 to 160/1 and adjust relay settings accordingly	APS (100%)
b2688.3	Carroll Substation: Replace the Germantown 138 kV wave trap, upgrade the bus conductor and adjust CT ratios	AEP (12.91%) / APS (19.04%) / ATSI (1.24%) / ComEd (0.35%) / Dayton (1.45%) / DEOK (2.30%) / DL (1.11%) / Dominion (44.85%) / EKPC (0.78%) / PEPCO (15.85%) / RECO (0.12%)
b2689.3	Upgrade terminal equipment at structure 27A	APS (100%)
b2696	Upgrade 138 kV substation equipment at Butler, Shanor Manor and Krendale substations. New rating of line will be 353 MVA summer normal/422 MVA emergency	APS (100%)
b2700	Remove existing Black Oak SPS	APS (100%)
b2743.6	Reconfigure the Ringgold 230 kV substation to double bus double breaker scheme	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2743.6.1	Replace the two Ringgold 230/138 kV transformers	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2743.7	Rebuild/Reconductor the Ringgold – Catoctin 138 kV circuit and upgrade terminal equipment on both ends	AEP (6.46%) / APS (8.74%) / BGE (19.74%) / ComEd (2.16%) / Dayton (0.59%) / DEOK (1.02%) / DL (0.01%) / Dominion (39.95%) / EKPC (0.45%) / PEPCO (20.88%)
b2747.1	Relocate the FirstEnergy Pratts 138 kV terminal CVTs at Gordonsville substation to allow for the installation of a new motor operated switch being installed by Dominion	APS (100%)
b2763	Replace the breaker risers and wave trap at Bredinville 138 kV substation on the Cabrey Junction 138 kV terminal	APS (100%)
b2764	Upgrade Fairview 138 kV breaker risers and disconnect leads; Replace 500 CU breaker risers and 556 ACSR disconnect leads with 795 ACSR	APS (100%)
b2964.1	Replace terminal equipment at Pruntytown and Glen Falls 138 kV station	APS (100%)
b2964.2	Reconductor approximately 8.3 miles of the McAlpin - White Hall Junction 138 kV circuit	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2965	Reconductor the Charleroi – Allenport 138 kV line with 954 ACSR conductor. Replace breaker risers at Charleroi and Allenport	DL (100%)
b2966	Reconductor the Yukon – Smithton – Shepler Hill Jct 138 kV line with 795 ACSS conductor. Replace Line Disconnect Switch at Yukon	APS (100%)
b2966.1	Reconductor the Yukon - Smithton - Shepler Hill Jct 138 kV line and replace terminal equipment as necessary to achieve required rating	APS (100%)
b2967	Convert the existing 6 wire Butler - Shanor Manor - Krendale 138 kV line into two separate 138 kV lines. New lines will be Butler - Keisters and Butler - Shanor Manor - Krendale 138 kV	APS (100%)
b2970	Ringgold – Catoctin Solution	APS (100%)
b2970.1	Install two new 230 kV positions at Ringgold for 230/138 kV transformers	APS (100%)
b2970.2	Install new 230 kV position for Ringgold – Catoctin 230 kV line	APS (100%)
b2970.3	Install one new 230 kV breaker at Catoctin substation	APS (100%)
b2970.4	Install new 230/138 kV transformer at Catoctin substation. Convert Ringgold – Catoctin 138 kV line to 230 kV operation	APS (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
<p>b2996</p>	<p>Construct a new 500/138 kV substation as a 4-breaker ring bus with expansion plans for double-breaker-double-bus on the 500 kV bus and breaker-and-a-half on the 138 kV bus to provide EHV source to the Marcellus shale load growth area. Projected load growth of additional 160 MVA to current plan of 280 MVA, for a total load of 440 MVA served from Waldo Run substation. Replace primary relaying and carrier sets on Belmont and Harrison 500 kV Remote End substations. Construct additional 3-breaker string at Waldo Run 138 kV bus. Relocate the Sherwood #2 line terminal to the new string. Construct two single circuit Flint Run - Waldo Run 138 kV lines using 795 ACSR (approximately 3 miles). After terminal relocation on new 3-breaker string at Waldo Run, terminate new Flint Run 138 kV lines onto the two open terminals</p>	<p>APS (100%)</p>
<p>b3005</p>	<p>Reconductor 3.1 mile 556 ACSR portion of Cabot to Butler 138 kV with 556 ACSS and upgrade terminal equipment. 3.1 miles of line will be reconducted for this project. The total length of the line is 7.75 miles</p>	<p>APS (100%)</p>

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3006	Replace four Yukon 500/138 kV transformers with three transformers with higher rating and reconfigure 500 kV bus	APS (52.84%) / DL (47.16%)
b3007.1	Reconductor the Blairsville East to Social Hall 138 kV line and upgrade terminal equipment - AP portion. 4.8 miles total. The new conductor will be 636 ACSS replacing the existing 636 ACSR conductor. At Social Hall, meters, relays, bus conductor, a wave trap, circuit breaker and disconnects will be replaced	APS (100%)
b3010	Replace terminal equipment at Keystone and Cabot 500 kV buses. At Keystone, bus tubing and conductor, a wave trap, and meter will be replaced. At Cabot, a wave trap and bus conductor will be replaced	APS (100%)
b3011.1	Construct new Route 51 substation and connect 10 138 kV lines to new substation	DL (100%)
b3011.2	Upgrade terminal equipment at Yukon to increase rating on Yukon to Charleroi #2 138 kV line (New Yukon to Route 51 #4 138 kV line)	DL (100%)
b3011.3	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #1 138 kV line	DL (100%)
b3011.4	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #2 138 kV line	DL (100%)

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3011.5	Upgrade terminal equipment at Yukon to increase rating on Yukon to Route 51 #3 138 kV line	DL (100%)
b3011.6	Upgrade remote end relays for Yukon – Allenport – Iron Bridge 138 kV line	DL (100%)
b3012.1	Construct new ties from FirstEnergy’s new substation to Duquesne’s new substation - AP portion. The estimated line length is approximately 4.7 miles, however, this length is subject to change based on the final route of the line. Approximately 1.7 miles could potentially be constructed by using the existing double circuit towers on the Wycoff tap. The line is planned to use 2-954 ACSS conductors per phase	DL (100%)
b3013	Reconductor Vasco Tap to Edgewater Tap 138 kV line. 4.4 miles. The new conductor will be 336 ACSS replacing the existing 336 ACSR conductor	APS (100%)
b3015.6	Reconductor Elrama to Mitchell 138 kV line – AP portion. 4.2 miles total. 2x 795 ACSS/TW 20/7	DL (100%)
b3028	Upgrade substation disconnect leads at William 138 kV substation	APS (100%)
b3051.1	<i>Ronceverte cap bank and terminal upgrades</i>	<i>APS (100%)</i>
b3052	<i>Install a 138 kV capacitor (29.7 MVAR effective) at West Winchester 138 kV</i>	<i>APS (100%)</i>

Monongahela Power Company, The Potomac Edison Company, and West Penn Power Company, all doing business as Allegheny Power (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3068	Reconductor the Yukon – Westraver 138 kV line (2.8 miles), replace the line drops and relays at Yukon 138 kV and replace switches at Westraver 138 kV bus	APS (100%)
b3069	Reconductor the Westraver – Route 51 138 kV line (5.63 miles) and replace line switches at Westraver 138 kV bus	APS (100%)
b3070	Reconductor the Yukon – Route 51 #1 138 kV line (8 miles), replace the line drops, relays and line disconnect switch at Yukon 138 kV bus	APS (100%)
b3071	Reconductor the Yukon – Route 51 #2 138 kV line (8 miles) and replace relays at Yukon 138 kV bus	APS (100%)
b3072	Reconductor the Yukon – Route 51 #3 138 kV line (8 miles) and replace relays at Yukon 138 kV bus	APS (100%)
b3074	Reconductor the 138 kV bus at Armstrong substation	APS (100%)
b3075	Replace the 500/138 kV transformer breaker and reconductor 138 kV bus at Cabot substation	APS (100%)
b3076	Reconductor the Edgewater – Loyalhanna 138 kV line (0.67 mile)	APS (100%)
b3079	Replace the Wylie Ridge 500/345 kV transformer #7	ATSI (72.30%) / DL (27.70%)
b3083	Reconductor the 138 kV bus at Butler and reconductor the 138 kV bus and replace line trap at Karns City	APS (100%)

SCHEDULE 12 – APPENDIX A

- (17) **AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company)**

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1660.1	Cloverdale: install 6-765 kV breakers, incremental work for 2 additional breakers, reconfigure and relocate miscellaneous facilities, establish 500 kV station and 500 kV tie with 765 kV station	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: ATSI (24.65%) / Dayton (8.85%) / DEOK (19.91%) / Dominion (41.38%) / EKPC (5.21%)</p>

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1797.1	Reconductor the AEP portion of the Cloverdale - Lexington 500 kV line with 2-1780 ACSS	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: ATSI (5.74%) / Dayton (1.97%) / DEOK (4.40%) / Dominion (9.97%) / EKPC (1.12%) / PEPCO (76.80%)</p>
b2055	Upgrade relay at Brues station	AEP (100%)
b2122.3	Upgrade terminal equipment at Howard on the Howard - Brookside 138 kV line to achieve ratings of 252/291 (SN/SE)	AEP (100%)
b2122.4	Perform a sag study on the Howard - Brookside 138 kV line	AEP (100%)
b2229	Install a 300 MVAR reactor at Dequine 345 kV	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2230	Replace existing 150 MVAR reactor at Amos 765 kV substation on Amos - N. Proctorville - Hanging Rock with 300 MVAR reactor	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>
b2231	Install 765 kV reactor breaker at Dumont 765 kV substation on the Dumont - Wilton Center line	AEP (100%)
b2232	Install 765 kV reactor breaker at Marysville 765 kV substation on the Marysville - Maliszewski line	AEP (100%)
b2233	Change transformer tap settings for the Baker 765/345 kV transformer	AEP (100%)
b2252	Loop the North Muskingum - Crooksville 138 kV line into AEP's Philo 138 kV station which lies approximately 0.4 miles from the line	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2253	Install an 86.4 MVAR capacitor bank at Gorsuch 138 kV station in Ohio		AEP (100%)
b2254	Rebuild approximately 4.9 miles of Corner - Degussa 138 kV line in Ohio		AEP (100%)
b2255	Rebuild approximately 2.8 miles of Maliszewski - Polaris 138 kV line in Ohio		AEP (100%)
b2256	Upgrade approximately 36 miles of 138 kV through path facilities between Harrison 138 kV station and Ross 138 kV station in Ohio		AEP (100%)
b2257	Rebuild the Pokagon - Corey 69 kV line as a double circuit 138 kV line with one side at 69 kV and the other side as an express circuit between Pokagon and Corey stations		AEP (100%)
b2258	Rebuild 1.41 miles of #2 CU 46 kV line between Tams Mountain - Slab Fork to 138 kV standards. The line will be strung with 1033 ACSR		AEP (100%)
b2259	Install a new 138/69 kV transformer at George Washington 138/69 kV substation to provide support to the 69 kV system in the area		AEP (100%)
b2286	Rebuild 4.7 miles of Muskingum River - Wolf Creek 138 kV line and remove the 138/138 kV transformer at Wolf Creek Station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2287	Loop in the Meadow Lake - Olive 345 kV circuit into Reynolds 765/345 kV station		AEP (100%)
b2344.1	Establish a new 138/12 kV station, transfer and consolidate load from its Nicholasville and Marcellus 34.5 kV stations at this new station		AEP (100%)
b2344.2	Tap the Hydramatic – Valley 138 kV circuit (~ structure 415), build a new 138 kV line (~3.75 miles) to this new station		AEP (100%)
b2344.3	From this station, construct a new 138 kV line (~1.95 miles) to REA’s Marcellus station		AEP (100%)
b2344.4	From REA’s Marcellus station construct new 138 kV line (~2.35 miles) to a tap point on Valley – Hydramatic 138 kV ckt (~structure 434)		AEP (100%)
b2344.5	Retire sections of the 138 kV line in between structure 415 and 434 (~ 2.65 miles)		AEP (100%)
b2344.6	Retire AEP’s Marcellus 34.5/12 kV and Nicholasville 34.5/12 kV stations and also the Marcellus – Valley 34.5 kV line		AEP (100%)
b2345.1	Construct a new 69 kV line from Hartford to Keeler (~8 miles)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2345.2	Rebuild the 34.5 kV lines between Keeler - Sister Lakes and Glenwood tap switch to 69 kV (~12 miles)		AEP (100%)
b2345.3	Implement in - out at Keeler and Sister Lakes 34.5 kV stations		AEP (100%)
b2345.4	Retire Glenwood tap switch and construct a new Rothadew station. These new lines will continue to operate at 34.5 kV		AEP (100%)
b2346	Perform a sag study for Howard - North Bellville - Millwood 138 kV line including terminal equipment upgrades		AEP (100%)
b2347	Replace the North Delphos 600A switch. Rebuild approximately 18.7 miles of 138 kV line North Delphos - S073. Reconductor the line and replace the existing tower structures		AEP (100%)
b2348	Construct a new 138 kV line from Richlands Station to intersect with the Hales Branch - Grassy Creek 138 kV circuit		AEP (100%)
b2374	Change the existing CT ratios of the existing equipment along Bearskin - Smith Mountain 138kV circuit		AEP (100%)
b2375	Change the existing CT ratios of the existing equipment along East Danville-Banister 138kV circuit		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2376	Replace the Turner 138 kV breaker 'D'		AEP (100%)
b2377	Replace the North Newark 138 kV breaker 'P'		AEP (100%)
b2378	Replace the Sporn 345 kV breaker 'DD'		AEP (100%)
b2379	Replace the Sporn 345 kV breaker 'DD2'		AEP (100%)
b2380	Replace the Muskingum 345 kV breaker 'SE'		AEP (100%)
b2381	Replace the East Lima 138 kV breaker 'E1'		AEP (100%)
b2382	Replace the Delco 138 kV breaker 'R'		AEP (100%)
b2383	Replace the Sporn 345 kV breaker 'AA2'		AEP (100%)
b2384	Replace the Sporn 345 kV breaker 'CC'		AEP (100%)
b2385	Replace the Sporn 345 kV breaker 'CC2'		AEP (100%)
b2386	Replace the Astor 138 kV breaker '102'		AEP (100%)
b2387	Replace the Muskingum 345 kV breaker 'SH'		AEP (100%)
b2388	Replace the Muskingum 345 kV breaker 'SI'		AEP (100%)
b2389	Replace the Hyatt 138 kV breaker '105N'		AEP (100%)
b2390	Replace the Muskingum 345 kV breaker 'SG'		AEP (100%)
b2391	Replace the Hyatt 138 kV breaker '101C'		AEP (100%)
b2392	Replace the Hyatt 138 kV breaker '104N'		AEP (100%)
b2393	Replace the Hyatt 138 kV breaker '104S'		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2394	Replace the Sporn 345 kV breaker 'CC1'		AEP (100%)
b2409	Install two 56.4 MVAR capacitor banks at the Melmore 138 kV station in Ohio		AEP (100%)
b2410	Convert Hogan Mullin 34.5 kV line to 138 kV, establish 138 kV line between Jones Creek and Strawton, rebuild existing Mullin Elwood 34.5 kV and terminate line into Strawton station, retire Mullin station		AEP (100%)
b2411	Rebuild the 3/0 ACSR portion of the Hadley - Kroemer Tap 69 kV line utilizing 795 ACSR conductor		AEP (100%)
b2423	Install a 300 MVAR shunt reactor at AEP's Wyoming 765 kV station		Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)
			DFAX Allocation: AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2444	Willow - Eureka 138 kV line: Reconductor 0.26 mile of 4/0 CU with 336 ACSS		AEP (100%)
b2445	Complete a sag study of Tidd - Mahans Lake 138 kV line		AEP (100%)
b2449	Rebuild the 7-mile 345 kV line between Meadow Lake and Reynolds 345 kV stations		AEP (100%)
b2462	Add two 138 kV circuit breakers at Fremont station to fix tower contingency '408_2'		AEP (100%)
b2501	Construct a new 138/69 kV Yager station by tapping 2-138 kV FE circuits (Nottingham-Cloverdale, Nottingham-Harmon)		AEP (100%)
b2501.2	Build a new 138 kV line from new Yager station to Azalea station		AEP (100%)
b2501.3	Close the 138 kV loop back into Yager 138 kV by converting part of local 69 kV facilities to 138 kV		AEP (100%)
b2501.4	Build 2 new 69 kV exits to reinforce 69 kV facilities and upgrade conductor between Irish Run 69 kV Switch and Bowerstown 69 kV Switch		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2502.1	Construct new 138 kV switching station Nottingham tapping 6-138 kV FE circuits (Holloway-Brookside, Holloway-Harmon #1 and #2, Holloway-Reeds, Holloway-New Stacy, Holloway-Cloverdale). Exit a 138 kV circuit from new station to Freebyrd station		AEP (100%)
b2502.2	Convert Freebyrd 69 kV to 138 kV		AEP (100%)
b2502.3	Rebuild/convert Freebyrd-South Cadiz 69 kV circuit to 138 kV		AEP (100%)
b2502.4	Upgrade South Cadiz to 138 kV breaker and a half		AEP (100%)
b2530	Replace the Sporn 138 kV breaker 'G1' with 80kA breaker		AEP (100%)
b2531	Replace the Sporn 138 kV breaker 'D' with 80kA breaker		AEP (100%)
b2532	Replace the Sporn 138 kV breaker 'O1' with 80kA breaker		AEP (100%)
b2533	Replace the Sporn 138 kV breaker 'P2' with 80kA breaker		AEP (100%)
b2534	Replace the Sporn 138 kV breaker 'U' with 80kA breaker		AEP (100%)
b2535	Replace the Sporn 138 kV breaker 'O' with 80 kA breaker		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2536	Replace the Sporn 138 kV breaker 'O2' with 80 kA breaker		AEP (100%)
b2537	Replace the Robinson Park 138 kV breakers A1, A2, B1, B2, C1, C2, D1, D2, E1, E2, and F1 with 63 kA breakers		AEP (100%)
b2555	Reconductor 0.5 miles Tiltonsville – Windsor 138 kV and string the vacant side of the 4.5 mile section using 556 ACSR in a six wire configuration		AEP (100%)
b2556	Install two 138 kV prop structures to increase the maximum operating temperature of the Clinch River- Clinch Field 138 kV line		AEP (100%)
b2581	Temporary operating procedure for delay of upgrade b1464. Open the Corner 138 kV circuit breaker 86 for an overload of the Corner – Washington MP 138 kV line. The tower contingency loss of Belmont – Trissler 138 kV and Belmont – Edgelawn 138 kV should be added to Operational contingency		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2591	Construct a new 69 kV line approximately 2.5 miles from Colfax to Drewry's. Construct a new Drewry's station and install a new circuit breaker at Colfax station.		AEP (100%)
b2592	Rebuild existing East Coshocton – North Coshocton double circuit line which contains Newcomerstown – N. Coshocton 34.5 kV Circuit and Coshocton – North Coshocton 69 kV circuit		AEP (100%)
b2593	Rebuild existing West Bellaire – Glencoe 69 kV line with 138 kV & 69 kV circuits and install 138/69 kV transformer at Glencoe Switch		AEP (100%)
b2594	Rebuild 1.0 mile of Brantley – Bridge Street 69 kV Line with 1033 ACSR overhead conductor		AEP (100%)
b2595.1	Rebuild 7.82 mile Elkhorn City – Haysi S.S 69 kV line utilizing 1033 ACSR built to 138 kV standards		AEP (100%)
b2595.2	Rebuild 5.18 mile Moss – Haysi SS 69 kV line utilizing 1033 ACSR built to 138 kV standards		AEP (100%)
b2596	Move load from the 34.5 kV bus to the 138 kV bus by installing a new 138/12 kV XF at New Carlisle station in Indiana		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2597	Rebuild approximately 1 mi. section of Dragoon-Virgil Street 34.5 kV line between Dragoon and Dodge Tap switch and replace Dodge switch MOAB to increase thermal capability of Dragoon-Dodge Tap branch		AEP (100%)
b2598	Rebuild approximately 1 mile section of the Kline-Virgil Street 34.5 kV line between Kline and Virgil Street tap. Replace MOAB switches at Beiger, risers at Kline, switches and bus at Virgil Street.		AEP (100%)
b2599	Rebuild approximately 0.1 miles of 69 kV line between Albion and Albion tap		AEP (100%)
b2600	Rebuild Fremont – Pound line as 138 kV		AEP (100%)
b2601	Fremont Station Improvements		AEP (100%)
b2601.1	Replace MOAB towards Beaver Creek with 138 kV breaker		AEP (100%)
b2601.2	Replace MOAB towards Clinch River with 138 kV breaker		AEP (100%)
b2601.3	Replace 138 kV Breaker A with new bus-tie breaker		AEP (100%)
b2601.4	Re-use Breaker A as high side protection on transformer #1		AEP (100%)
b2601.5	Install two (2) circuit switchers on high side of transformers # 2 and 3 at Fremont Station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2602.1	Install 138 kV breaker E2 at North Proctorville		AEP (100%)
b2602.2	Construct 2.5 Miles of 138 kV 1033 ACSR from East Huntington to Darrah 138 kV substations		AEP (100%)
b2602.3	Install breaker on new line exit at Darrah towards East Huntington		AEP (100%)
b2602.4	Install 138 kV breaker on new line at East Huntington towards Darrah		AEP (100%)
b2602.5	Install 138 kV breaker at East Huntington towards North Proctorville		AEP (100%)
b2603	Boone Area Improvements		AEP (100%)
b2603.1	Purchase approximately a 200X300 station site near Slaughter Creek 46 kV station (Wilbur Station)		AEP (100%)
b2603.2	Install 3 138 kV circuit breakers, Cabin Creek to Hernshaw 138 kV circuit		AEP (100%)
b2603.3	Construct 1 mi. of double circuit 138 kV line on Wilbur – Boone 46 kV line with 1590 ACSS 54/19 conductor @ 482 Degree design temp. and 1-159 12/7 ACSR and one 86 Sq.MM. 0.646” OPGW Static wires		AEP (100%)
b2604	Bellefonte Transformer Addition		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2605	Rebuild and reconductor Kammer – George Washington 69 kV circuit and George Washington – Moundville ckt #1, designed for 138kV. Upgrade limiting equipment at remote ends and at tap stations		AEP (100%)
b2606	Convert Bane – Hammondsville from 23 kV to 69 kV operation		AEP (100%)
b2607	Pine Gap Relay Limit Increase		AEP (100%)
b2608	Richlands Relay Upgrade		AEP (100%)
b2609	Thorofare – Goff Run – Powell Mountain 138 kV Build		AEP (100%)
b2610	Rebuild Pax Branch – Scaraboro as 138 kV		AEP (100%)
b2611	Skin Fork Area Improvements		AEP (100%)
b2611.1	New 138/46 kV station near Skin Fork and other components		AEP (100%)
b2611.2	Construct 3.2 miles of 1033 ACSR double circuit from new Station to cut into Sundial-Baileysville 138 kV line		AEP (100%)
b2634.1	Replace metering BCT on Tanners Creek CB T2 with a slip over CT with higher thermal rating in order to remove 1193 MVA limit on facility (Miami Fort-Tanners Creek 345 kV line)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2643	Replace the Darrah 138 kV breaker 'L' with 40kA rated breaker		AEP (100%)
b2645	Ohio Central 138 kV Loop		AEP (100%)
b2667	Replace the Muskingum 138 kV bus # 1 and 2		AEP (100%)
b2668	Reconductor Dequine to Meadow Lake 345 kV circuit #1 utilizing dual 954 ACSR 54/7 cardinal conductor		AEP (100%)
b2669	Install a second 345/138 kV transformer at Desoto		AEP (100%)
b2670	Replace switch at Elk Garden 138 kV substation (on the Elk Garden – Lebanon 138 kV circuit)		AEP (100%)
b2671	Replace/upgrade/add terminal equipment at Bradley, Mullensville, Pinnacle Creek, Itmann, and Tams Mountain 138 kV substations. Sag study on Mullens – Wyoming and Mullens – Tams Mt. 138 kV circuits		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2687.1	Install a +/- 450 MVAR SVC at Jacksons Ferry 765 kV substation	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2687.2	Install a 300 MVAR shunt line reactor on the Broadford end of the Broadford – Jacksons Ferry 765 kV line	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPSCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: AEP (100%)</p>
b2697.1	Mitigate violations identified by sag study to operate Fieldale-Thornton-Franklin 138 kV overhead line conductor at its max. operating temperature. 6 potential line crossings to be addressed.	AEP (100%)
b2697.2	Replace terminal equipment at AEP’s Danville and East Danville substations to improve thermal capacity of Danville – East Danville 138 kV circuit	AEP (100%)

*Neptune Regional Transmission System, LLC

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2698	Replace relays at AEP's Cloverdale and Jackson's Ferry substations to improve the thermal capacity of Cloverdale – Jackson's Ferry 765 kV line		AEP (100%)
b2701.1	Construct Herlan station as breaker and a half configuration with 9-138 kV CB's on 4 strings and with 2-28.8 MVAR capacitor banks		AEP (100%)
b2701.2	Construct new 138 kV line from Herlan station to Blue Racer station. Estimated approx. 3.2 miles of 1234 ACSS/TW Yukon and OPGW		AEP (100%)
2701.3	Install 1-138 kV CB at Blue Racer to terminate new Herlan circuit		AEP (100%)
b2714	Rebuild/upgrade line between Glencoe and Willow Grove Switch 69 kV		AEP (100%)
b2715	Build approximately 11.5 miles of 34.5 kV line with 556.5 ACSR 26/7 Dove conductor on wood poles from Flushing station to Smyrna station		AEP (100%)
b2727	Replace the South Canton 138 kV breakers 'K', 'J', 'J1', and 'J2' with 80kA breakers		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2731	Convert the Sunnyside – East Sparta – Malvern 23 kV sub-transmission network to 69 kV. The lines are already built to 69 kV standards		AEP (100%)
b2733	Replace South Canton 138 kV breakers ‘L’ and ‘L2’ with 80 kA rated breakers		AEP (100%)
b2750.1	Retire Betsy Layne 138/69/43 kV station and replace it with the greenfield Stanville station about a half mile north of the existing Betsy Layne station		AEP (100%)
b2750.2	Relocate the Betsy Layne capacitor bank to the Stanville 69 kV bus and increase the size to 14.4 MVAR		AEP (100%)
b2753.1	Replace existing George Washington station 138 kV yard with GIS 138 kV breaker and a half yard in existing station footprint. Install 138 kV revenue metering for new IPP connection		AEP (100%)
b2753.2	Replace Dilles Bottom 69/4 kV Distribution station as breaker and a half 138 kV yard design including AEP Distribution facilities but initial configuration will constitute a 3 breaker ring bus		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2753.3	Connect two 138 kV 6-wired circuits from “Point A” (currently de-energized and owned by FirstEnergy) in circuit positions previously designated Burger #1 & Burger #2 138 kV. Install interconnection settlement metering on both circuits exiting Holloway		AEP (100%)
b2753.6	Build double circuit 138 kV line from Dilles Bottom to “Point A”. Tie each new AEP circuit in with a 6-wired line at Point A. This will create a Dilles Bottom – Holloway 138 kV circuit and a George Washington – Holloway 138 kV circuit		AEP (100%)
b2753.7	Retire line sections (Dilles Bottom – Bellaire and Moundsville – Dilles Bottom 69 kV lines) south of FirstEnergy 138 kV line corridor, near “Point A”. Tie George Washington – Moundsville 69 kV circuit to George Washington – West Bellaire 69 kV circuit		AEP (100%)
b2753.8	Rebuild existing 69 kV line as double circuit from George Washington – Dilles Bottom 138 kV. One circuit will cut into Dilles Bottom 138 kV initially and the other will go past with future plans to cut in		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2760	Perform a Sag Study of the Saltville – Tazewell 138 kV line to increase the thermal rating of the line		AEP (100%)
b2761.1	Replace the Hazard 161/138 kV transformer		AEP (100%)
b2761.2	Perform a Sag Study of the Hazard – Wooten 161 kV line to increase the thermal rating of the line		AEP (100%)
b2761.3	Rebuild the Hazard – Wooton 161 kV line utilizing 795 26/7 ACSR conductor (300 MVA rating)		AEP (100%)
b2762	Perform a Sag Study of Nagel – West Kingsport 138 kV line to increase the thermal rating of the line		AEP (100%)
b2776	Reconductor the entire Dequine – Meadow Lake 345 kV circuit #2		AEP (100%)
b2777	Reconductor the entire Dequine – Eugene 345 kV circuit #1		AEP (100%)
b2779.1	Construct a new 138 kV station, Campbell Road, tapping into the Grabill – South Hicksville 138 kV line		AEP (100%)
b2779.2	Reconstruct sections of the Butler-N.Hicksville and Auburn-Butler 69 kV circuits as 138 kV double circuit and extend 138 kV from Campbell Road station		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2779.3	Construct a new 345/138 kV SDI Wilmington Station which will be sourced from Collingwood 345 kV and serve the SDI load at 345 kV and 138 kV, respectively		AEP (100%)
b2779.4	Loop 138 kV circuits in-out of the new SDI Wilmington 138 kV station resulting in a direct circuit to Auburn 138 kV and an indirect circuit to Auburn and Rob Park via Dunton Lake, and a circuit to Campbell Road; Reconductor 138 kV line section between Dunton Lake – SDI Wilmington		AEP (100%)
b2779.5	Expand Auburn 138 kV bus		AEP (100%)
b2787	Reconductor 0.53 miles (14 spans) of the Kaiser Jct. - Air Force Jct. Sw section of the Kaiser - Heath 69 kV circuit/line with 336 ACSR to match the rest of the circuit (73 MVA rating, 78% loading)		AEP (100%)
b2788	Install a new 3-way 69 kV line switch to provide service to AEP's Barnesville distribution station. Remove a portion of the #1 copper T-Line from the 69 kV through-path		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2789	Rebuild the Brues - Glendale Heights 69 kV line section (5 miles) with 795 ACSR (128 MVA rating, 43% loading)	AEP (100%)
b2790	Install a 3 MVAR, 34.5 kV cap bank at Caldwell substation	AEP (100%)
b2791	Rebuild Tiffin – Howard, new transformer at Chatfield	AEP (100%)
b2791.1	Rebuild portions of the East Tiffin - Howard 69 kV line from East Tiffin to West Rockaway Switch (0.8 miles) using 795 ACSR Drake conductor (129 MVA rating, 50% loading)	AEP (100%)
b2791.2	Rebuild Tiffin - Howard 69 kV line from St. Stephen’s Switch to Hinesville (14.7 miles) using 795 ACSR Drake conductor (90 MVA rating, non-conductor limited, 38% loading)	AEP (100%)
b2791.3	New 138/69 kV transformer with 138/69 kV protection at Chatfield	AEP (100%)
b2791.4	New 138/69 kV protection at existing Chatfield transformer	AEP (100%)
b2792	Replace the Elliott transformer with a 130 MVA unit, reconductor 0.42 miles of the Elliott – Ohio University 69 kV line with 556 ACSR to match the rest of the line conductor (102 MVA rating, 73% loading) and rebuild 4 miles of the Clark Street – Strouds R	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement		Responsible Customer(s)
b2793	Energize the spare Fremont Center 138/69 kV 130 MVA transformer #3. Reduces overloaded facilities to 46% loading		AEP (100%)
b2794	Construct new 138/69/34 kV station and 1-34 kV circuit (designed for 69 kV) from new station to Decliff station, approximately 4 miles, with 556 ACSR conductor (51 MVA rating)		AEP (100%)
b2795	Install a 34.5 kV 4.8 MVAR capacitor bank at Killbuck 34.5 kV station		AEP (100%)
b2796	Rebuild the Malvern - Oneida Switch 69 kV line section with 795 ACSR (1.8 miles, 125 MVA rating, 55% loading)		AEP (100%)
b2797	Rebuild the Ohio Central - Conesville 69 kV line section (11.8 miles) with 795 ACSR conductor (128 MVA rating, 57% loading). Replace the 50 MVA Ohio Central 138/69 kV XFMR with a 90 MVA unit		AEP (100%)
b2798	Install a 14.4 MVAR capacitor bank at West Hicksville station. Replace ground switch/MOAB at West Hicksville with a circuit switcher		AEP (100%)
b2799	Rebuild Valley - Almena, Almena - Hartford, Riverside - South Haven 69 kV lines. New line exit at Valley Station. New transformers at Almena and Hartford		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2799.1	Rebuild 12 miles of Valley – Almena 69 kV line as a double circuit 138/69 kV line using 795 ACSR conductor (360 MVA rating) to introduce a new 138 kV source into the 69 kV load pocket around Almena station	AEP (100%)
b2799.2	Rebuild 3.2 miles of Almena to Hartford 69 kV line using 795 ACSR conductor (90 MVA rating)	AEP (100%)
b2799.3	Rebuild 3.8 miles of Riverside – South Haven 69 kV line using 795 ACSR conductor (90 MVA rating)	AEP (100%)
b2799.4	At Valley station, add new 138 kV line exit with a 3000 A 40 kA breaker for the new 138 kV line to Almena and replace CB D with a 3000 A 40 kA breaker	AEP (100%)
b2799.5	At Almena station, install a 90 MVA 138/69 kV transformer with low side 3000 A 40 kA breaker and establish a new 138 kV line exit towards Valley	AEP (100%)
b2799.6	At Hartford station, install a second 90 MVA 138/69 kV transformer with a circuit switcher and 3000 A 40 kA low side breaker	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2817	Replace Delaware 138 kV breaker 'P' with a 40 kA breaker	AEP (100%)
b2818	Replace West Huntington 138 kV breaker 'F' with a 40 kA breaker	AEP (100%)
b2819	Replace Madison 138 kV breaker 'V' with a 63 kA breaker	AEP (100%)
b2820	Replace Sterling 138 kV breaker 'G' with a 40 kA breaker	AEP (100%)
b2821	Replace Morse 138 kV breakers '103', '104', '105', and '106' with 63 kA breakers	AEP (100%)
b2822	Replace Clinton 138 kV breakers '105' and '107' with 63 kA breakers	AEP (100%)
b2826.1	Install 300 MVAR reactor at Ohio Central 345 kV substation	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2826.2	Install 300 MVAR reactor at West Bellaire 345 kV substation		AEP (100%)
b2831.1	Upgrade the Tanner Creek – Miami Fort 345 kV circuit (AEP portion)		DFAX Allocation: Dayton (34.34%) / DEOK (56.45%) / EKPC (9.21%)
b2832	Six wire the Kyger Creek – Sporn 345 kV circuits #1 and #2 and convert them to one circuit		AEP (100%)
b2833	Reconductor the Maddox Creek – East Lima 345 kV circuit with 2-954 ACSS Cardinal conductor		DFAX Allocation: Dayton (100%)
b2834	Reconductor and string open position and sixwire 6.2 miles of the Chemical – Capitol Hill 138 kV circuit		AEP (100%)
b2872	Replace the South Canton 138 kV breaker ‘K2’ with a 80 kA breaker		AEP (100%)
b2873	Replace the South Canton 138 kV breaker ‘M’ with a 80 kA breaker		AEP (100%)
b2874	Replace the South Canton 138 kV breaker ‘M2’ with a 80 kA breaker		AEP (100%)
b2878	Upgrade the Clifty Creek 345 kV risers		AEP (100%)
b2880	Rebuild approximately 4.77 miles of the Cannonsburg – South Neal 69 kV line section utilizing 795 ACSR conductor (90 MVA rating)		AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2881	Rebuild ~1.7 miles of the Dunn Hollow – London 46 kV line section utilizing 795 26/7 ACSR conductor (58 MVA rating, non-conductor limited)	AEP (100%)
b2882	Rebuild Reusens - Peakland Switch 69 kV line. Replace Peakland Switch	AEP (100%)
b2882.1	Rebuild the Reusens - Peakland Switch 69 kV line (approximately 0.8 miles) utilizing 795 ACSR conductor (86 MVA rating, non-conductor limited)	AEP (100%)
b2882.2	Replace existing Peakland S.S with new 3 way switch phase over phase structure	AEP (100%)
b2883	Rebuild the Craneco – Pardee – Three Forks – Skin Fork 46 kV line section (approximately 7.2 miles) utilizing 795 26/7 ACSR conductor (108 MVA rating)	AEP (100%)
b2884	Install a second transformer at Nagel station, comprised of 3 single phase 250 MVA 500/138 kV transformers. Presently, TVA operates their end of the Boone Dam – Holston 138 kV interconnection as normally open preemptively for the loss of the existing Nagel	AEP (100%)
b2885	New delivery point for City of Jackson	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2885.1	Install a new Ironman Switch to serve a new delivery point requested by the City of Jackson for a load increase request	AEP (100%)
b2885.2	Install a new 138/69 kV station (Rhodes) to serve as a third source to the area to help relieve overloads caused by the customer load increase	AEP (100%)
b2885.3	Replace Coalton Switch with a new three breaker ring bus (Heppner)	AEP (100%)
b2886	Install 90 MVA 138/69 kV transformer, new transformer high and low side 3000 A 40 kA CBs, and a 138 kV 40 kA bus tie breaker at West End Fostoria	AEP (100%)
b2887	Add 2-138 kV CB's and relocate 2-138 kV circuit exits to different bays at Morse Road. Eliminate 3 terminal line by terminating Genoa - Morse circuit at Morse Road	AEP (100%)
b2888	Retire Poston substation. Install new Lemaster substation	AEP (100%)
b2888.1	Remove and retire the Poston 138 kV station	AEP (100%)
b2888.2	Install a new greenfield station, Lemaster 138 kV Station, in the clear	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2888.3	Relocate the Trimble 69 kV AEP Ohio radial delivery point to 138 kV, to be served off of the Poston – Strouds Run – Crooksville 138 kV circuit via a new three-way switch. Retire the Poston - Trimble 69 kV line	AEP (100%)
b2889	Expand Cliffview station	AEP (100%)
b2889.1	Cliffview Station: Establish 138 kV bus. Install two 138/69 kV XFRs (130 MVA), six 138 kV CBs (40 kA 3000 A) and four 69 kV CBs (40 kA 3000 A)	AEP (100%)
b2889.2	Byllesby – Wythe 69 kV: Retire all 13.77 miles (1/0 CU) of this circuit (~4 miles currently in national forest)	AEP (100%)
b2889.3	Galax – Wythe 69 kV: Retire 13.53 miles (1/0 CU section) of line from Lee Highway down to Byllesby. This section is currently double circuited with Byllesby – Wythe 69 kV. Terminate the southern 3/0 ACSR section into the newly opened position at Byllesby	AEP (100%)
b2889.4	Cliffview Line: Tap the existing Pipers Gap – Jubal Early 138 kV line section. Construct double circuit in/out (~2 miles) to newly established 138 kV bus, utilizing 795 26/7 ACSR conductor	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2890.1	Rebuild 23.55 miles of the East Cambridge – Smyrna 34.5 kV circuit with 795 ACSR conductor (128 MVA rating) and convert to 69 kV	AEP (100%)
b2890.2	East Cambridge: Install a 2000 A 69 kV 40 kA circuit breaker for the East Cambridge – Smyrna 69 kV circuit	AEP (100%)
b2890.3	Old Washington: Install 69 kV 2000 A two way phase over phase switch	AEP (100%)
b2890.4	Install 69 kV 2000 A two way phase over phase switch	AEP (100%)
b2891	Rebuild the Midland Switch to East Findlay 34.5 kV line (3.31 miles) with 795 ACSR (63 MVA rating) to match other conductor in the area	AEP (100%)
b2892	Install new 138/12 kV transformer with high side circuit switcher at Leon and a new 138 kV line exit towards Ripley. Establish 138 kV at the Ripley station with a new 138/69 kV 130 MVA transformer and move the distribution load to 138 kV service	AEP (100%)
b2936.1	Rebuild approximately 6.7 miles of 69 kV line between Mottville and Pigeon River using 795 ACSR conductor (129 MVA rating). New construction will be designed to 138 kV standards but operated at 69 kV	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2936.2	Pigeon River Station: Replace existing MOAB Sw. 'W' with a new 69 kV 3000 A 40 kA breaker, and upgrade existing relays towards HMD station. Replace CB H with a 3000 A 40 kA breaker	AEP (100%)
b2937	Replace the existing 636 ACSR 138 kV bus at Fletchers Ridge with a larger 954 ACSR conductor	AEP (100%)
b2938	Perform a sag mitigations on the Broadford – Wolf Hills 138 kV circuit to allow the line to operate to a higher maximum temperature	AEP (100%)
b2958.1	Cut George Washington – Tidd 138 kV circuit into Sand Hill and reconfigure Brues & Warton Hill line entrances	AEP (100%)
b2958.2	Add 2 138 kV 3000 A 40 kA breakers, disconnect switches, and update relaying at Sand Hill station	AEP (100%)
b2968	Upgrade existing 345 kV terminal equipment at Tanner Creek station	AEP (100%)
b2969	Replace terminal equipment on Maddox Creek - East Lima 345 kV circuit	AEP (100%)
b2976	Upgrade terminal equipment at Tanners Creek 345 kV station. Upgrade 345 kV bus and risers at Tanners Creek for the Dearborn circuit	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2988	Replace the Twin Branch 345 kV breaker “JM” with 63 kA breaker and associated substation works including switches, bus leads, control cable and new DICM	AEP (100%)
b2993	Rebuild the Torrey – South Gambrinus Switch – Gambrinus Road 69 kV line section (1.3 miles) with 1033 ACSR ‘Curlew’ conductor and steel poles	AEP (100%)
b3000	Replace South Canton 138 kV breaker ‘N’ with an 80kA breaker	AEP (100%)
b3001	Replace South Canton 138 kV breaker ‘N1’ with an 80kA breaker	AEP (100%)
b3002	Replace South Canton 138 kV breaker ‘N2’ with an 80kA breaker	AEP (100%)
<i>b3036</i>	<i>Rebuild 15.4 miles of double circuit North Delphos – Rockhill 138 kV line</i>	<i>AEP (100%)</i>
<i>b3037</i>	<i>Upgrades at the Natrium substation</i>	<i>AEP (100%)</i>
<i>b3038</i>	<i>Reconductor the Capitol Hill – Coco 138 kV line section</i>	<i>AEP (100%)</i>
<i>b3039</i>	<i>Line swaps at Muskingum 138 kV station</i>	<i>AEP (100%)</i>
<i>b3040.1</i>	<i>Rebuild Ravenswood – Racine tap 69 kV line section (~15 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor</i>	<i>AEP (100%)</i>

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

<i>Required Transmission Enhancements</i>	<i>Annual Revenue Requirement</i>	<i>Responsible Customer(s)</i>
<i>b3040.2</i>	<i>Rebuild existing Ripley – Ravenswood 69 kV circuit (~9 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor</i>	<i>AEP (100%)</i>
<i>b3040.3</i>	<i>Install new 3-way phase over phase switch at Sarah Lane station to replace the retired switch at Cottageville</i>	<i>AEP (100%)</i>
<i>b3040.4</i>	<i>Install new 138/12 kV 20 MVA transformer at Polymer station to transfer load from Mill Run station to help address overload on the 69 kV network</i>	<i>AEP (100%)</i>
<i>b3040.5</i>	<i>Retire Mill Run station</i>	<i>AEP (100%)</i>
<i>b3040.6</i>	<i>Install 28.8 MVAR cap bank at South Buffalo station</i>	<i>AEP (100%)</i>
<i>b3051.2</i>	<i>Adjust CT tap ratio at Ronceverte 138 kV</i>	<i>AEP (100%)</i>
<i>b3085</i>	<i>Reconductor Kammer – George Washington 138 kV line (approx. 0.08 mile). Replace the wave trap at Kammer 138 kV</i>	<i>AEP (100%)</i>
<i>b3086.1</i>	<i>Rebuild New Liberty – Findlay 34 kV line Str’s 1–37 (1.5 miles), utilizing 795 26/7 ACSR conductor</i>	<i>AEP (100%)</i>
<i>b3086.2</i>	<i>Rebuild New Liberty – North Baltimore 34 kV line Str’s 1-11 (0.5 mile), utilizing 795 26/7 ACSR conductor</i>	<i>AEP (100%)</i>

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3086.3	Rebuild West Melrose – Whirlpool 34 kV line Str’s 55–80 (1 mile), utilizing 795 26/7 ACSR conductor	AEP (100%)
b3086.4	North Findlay station: Install a 138 kV 3000A 63kA line breaker and low side 34.5 kV 2000A 40kA breaker, high side 138 kV circuit switcher on T1	AEP (100%)
b3086.5	Ebersole station: Install second 90 MVA 138/69/34 kV transformer. Install two low side (69 kV) 2000A 40kA breakers for T1 and T2	AEP (100%)
b3087.1	Construct a new greenfield station to the west (approx. 1.5 miles) of the existing Fords Branch Station in the new Kentucky Enterprise Industrial Park. This station will consist of six 3000A 40kA 138 kV breakers laid out in a ring arrangement, two 30 MVA 138/34.5 kV transformers, and two 30 MVA 138/12 kV transformers. The existing Fords Branch Station will be retired	AEP (100%)
b3087.2	Construct approximately 5 miles of new double circuit 138 kV line in order to loop the new Kewanee station into the existing Beaver Creek – Cedar Creek 138 kV circuit	AEP (100%)

AEP Service Corporation on behalf of its Affiliate Companies (AEP Indiana Michigan Transmission Company, AEP Kentucky Transmission Company, AEP Ohio Transmission Company, AEP West Virginia Transmission Company, Appalachian Power Company, Indiana Michigan Power Company, Kentucky Power Company, Kingsport Power Company, Ohio Power Company and Wheeling Power Company) (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3087.3	Remote end work will be required at Cedar Creek Station	AEP (100%)
b3095	Rebuild Lakin – Racine Tap 69 kV line section (9.2 miles) to 69 kV standards, utilizing 795 26/7 ACSR conductor	AEP (100%)

SCHEDULE 12 – APPENDIX A

(18) Duquesne Light Company

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2175.1	200 MVAR shunt reactor at Brunot Island 345 kV	DL (100%)
b2175.2	200 MVAR shunt reactor on future Brunot Island – Carson 345 kV circuit	DL (100%)
b2198	Revise the reclosing for the Brunot Island 138 kV breaker 'Z-40 COLLIER'	DL (100%)
b2199	Revise the reclosing for the Brunot Island 138 kV breaker 'Z-41 COLLIER'	DL (100%)
b2200	Revise the reclosing for the Crescent 138 kV breaker 'Z-29 Beaver'	DL (100%)
b2201	Revise the reclosing for the Crescent 138 kV breaker 'Z-82 VALLEY'	DL (100%)
b2202	Revise the reclosing for the Crescent 138 kV breaker 'Z-21 NORTH'	DL (100%)
b2203	Revise the reclosing for the Elrama 138 kV breaker 'Z18-USX CLAI'	DL (100%)
b2204	Revise the reclosing for the Elrama 138 kV breaker 'Z13-WEST MIF'	DL (100%)
b2205	Revise the reclosing for the Elrama 138 kV breaker 'Z15-DRAVOSBU'	DL (100%)
b2206	Revise the reclosing for the Woodville 138 kV breaker 'Z-106 PINEY'	DL (100%)
b2207	Revise the reclosing for the Woodville 138 kV breaker 'Z-64 COLLIER'	DL (100%)
b2208	Revise the reclosing for the Beaver Valley 138 kV breaker 'Z-28 CRESCEN'	DL (100%)

Duquesne Light Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2209	Revise the reclosing for the Cheswick 138 kV breaker 'Z-51 WILMERD'		DL (100%)
b2280	Replace the USAP 138kV breaker 'XFMR'		DL (100%)
b2303	Revise the reclosing to the Dravosburg 138kV breaker 'Z73 West Mifflin' from 5 sec to 15 sec		DL (100%)
b2563	Operate with the Crescent 345/138 kV #3 autotransformer in-service by replacing 8 overdutied 138 kV breakers at Crescent, 3 138 kV breakers at Beaver Valley, install #1 section 345 kV breaker for 331 circuit at Crescent		DL (100%)
b2632	Replace the Oakland 138 kV 'Z-101 Arsenal' breaker		DL (100%)
b2639	Replace the Crescent 138 kV 'NO3 – 4 138' breaker with a 63kA breaker		DL (100%)
b2640	Replace the Crescent 138 kV 'Z-143 SWCKLY' breaker with a 63kA breaker		DL (100%)
b2641	Replace the Crescent 138 kV 'Z-24 MONTOUR' breaker with a 63kA breaker		DL (100%)
b2642	Replace the Crescent 138 kV 'Z-28 BEAVER' breaker with a 63kA breaker		DL (100%)
b2689.1	Reconductor approximately 7 miles of the Woodville – Peters (Z-117) 138 kV circuit		AEC (1.00%) / APS (66.39%) / BGE (4.62%) / DOM (8.84%) / DPL (5.85%) / Neptune (0.12%) / PECO (3.40%) / PEPCO (6.32%) / PSEG (3.46%)

Duquesne Light Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2689.2	Reconfigure West Mifflin-USS Clairton (Z-15) 138 kV circuit to establish Dravosburg-USS Clairton (Z-14) 138 kV circuit and West Mifflin-Wilson (Z-15) 138 kV circuit	AEC (1.00%) / APS (66.39%) / BGE (4.62%) / DOM (8.84%) / DPL (5.85%) / Neptune (0.12%) / PECO (3.40%) / PEPCO (6.32%) / PSEG (3.46%)
b3012.2	Construct new ties from FirstEnergy's new substation to Duquesne's new substation – DL portion	DL (100%)
b3015.1	Construct new Elrama 138 kV substation and connect 7 138 kV lines to new substation	DL (100%)
b3015.2	Reconductor Elrama to Wilson 138 kV line. 4.8 miles	DL (100%)
b3015.3	Reconductor Dravosburg to West Mifflin 138 kV line. 3 miles	DL (100%)
b3015.4	Run new conductor on existing tower to establish the new Dravosburg – Elrama (Z-75) circuit. 10 miles	DL (100%)
b3015.5	Reconductor Elrama to Mitchell 138 kV line – DL portion. 4.2 miles total. 2x795 ACSS/TW 20/7	DL (100%)
b3015.7	Reconductor Wilson to West Mifflin 138 kV line. 2 miles. 795 ACSS/TW 20/7	DL (100%)
b3061	Reconductor the West Mifflin – Dravosburg (Z-73) and Dravosburg – Elrama (Z-75) 138 kV lines	DL (100%)
b3062	Install 138 kV tie breaker at West Mifflin	DL (100%)
b3063	Reconductor the Wilson – Dravosburg (Z-72) 138 kV line (approx. 5 miles)	DL (100%)

Duquesne Light Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3064		DL (100%)
b3065		DL (100%)
b3084		DL (100%)

SCHEDULE 12 – APPENDIX A

(20) Virginia Electric and Power Company

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b1698.7	Replace Loudoun 230 kV breaker '203052' with 63kA rating	Dominion (100%)
b1696.1	Replace the Idylwood 230 kV '25112' breaker with 50kA breaker	Dominion (100%)
b1696.2	Replace the Idylwood 230 kV '209712' breaker with 50kA breaker	Dominion (100%)
b1793.1	Remove the Carolina 22 SPS to include relay logic changes, minor control wiring, relay resets and SCADA programming upon completion of project	Dominion (100%)
b2281	Additional Temporary SPS at Bath County	Dominion (100%)
b2350	Reconductor 211 feet of 545.5 ACAR conductor on 59 Line Elmont - Greenwood DP 115 kV to achieve a summer emergency rating of 906 amps or greater	Dominion (100%)
b2358	Install a 230 kV 54 MVAR capacitor bank on the 2016 line at Harmony Village Substation	Dominion (100%)
b2359	Wreck and rebuild approximately 1.3 miles of existing 230 kV line between Cochran Mill - X4-039 Switching Station	Dominion (100%)
b2360	Build a new 39 mile 230 kV transmission line from Dooms - Lexington on existing right-of-way	Dominion (100%)
b2361	Construct 230 kV OH line along existing Line #2035 corridor, approx. 2.4 miles from Idylwood - Dulles Toll Road (DTR) and 2.1 miles on new right-of-way along DTR to new Scott's Run Substation	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2368	Replace the Brambleton 230 kV breaker '209502' with 63kA breaker	Dominion (100%)
b2369	Replace the Brambleton 230 kV breaker '213702' with 63kA breaker	Dominion (100%)
b2370	Replace the Brambleton 230 kV breaker 'H302' with 63kA breaker	Dominion (100%)
b2373	Build a 2nd Loudoun - Brambleton 500 kV line within the existing ROW. The Loudoun - Brambleton 230 kV line will be relocated as an underbuild on the new 500 kV line	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2397	Replace the Beaumeade 230 kV breaker '2079T2116' with 63kA	Dominion (100%)
b2398	Replace the Beaumeade 230 kV breaker '2079T2130' with 63kA	Dominion (100%)
b2399	Replace the Beaumeade 230 kV breaker '208192' with 63kA	Dominion (100%)
b2400	Replace the Beaumeade 230 kV breaker '209592' with 63kA	Dominion (100%)
b2401	Replace the Beaumeade 230 kV breaker '211692' with 63kA	Dominion (100%)
b2402	Replace the Beaumeade 230 kV breaker '227T2130' with 63kA	Dominion (100%)
b2403	Replace the Beaumeade 230 kV breaker '274T2130' with 63kA	Dominion (100%)

The Annual Revenue Requirement for all Virginia Electric and Power Company projects in this Section 20 shall be as specified in Attachment 7 to Appendix A of Attachment H-16A and under the procedures detailed in Attachment H-16B.

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2404	Replace the Beaumeade 230 kV breaker '227T2095' with 63kA	Dominion (100%)
b2405	Replace the Pleasant view 230 kV breaker '203T274' with 63kA	Dominion (100%)
b2443	Construct new underground 230 kV line from Glebe to Station C, rebuild Glebe Substation, construct 230 kV high side bus at Station C with option to install 800 MVA PAR	Dominion (97.11%) / ME (0.18%) / PEPCO (2.71%)
b2443.1	Replace the Idylwood 230 kV breaker '203512' with 50kA	Dominion (100%)
b2443.2	Replace the Ox 230 kV breaker '206342' with 63kA breaker	Dominion (100%)
b2443.3	Glebe – Station C PAR	DFAX Allocation: Dominion (22.57%) / PEPCO (77.43%)
b2443.6	Install a second 500/230 kV transformer at Possum Point substation and replace bus work and associated equipment as needed	Dominion (100%)
b2443.7	Replace 19 63kA 230 kV breakers with 19 80kA 230 kV breakers	Dominion (100%)
b2457	Replace 24 115 kV wood h-frames with 230 kV Dominion pole H-frame structures on the Clubhouse – Purdy 115 kV line	Dominion (100%)
b2458.1	Replace 12 wood H-frame structures with steel H-frame structures and install shunts on all conductor splices on Carolina – Woodland 115 kV	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2458.2	Upgrade all line switches and substation components at Carolina 115 kV to meet or exceed new conductor rating of 174 MVA	Dominion (100%)
b2458.3	Replace 14 wood H-frame structures on Carolina – Woodland 115 kV	Dominion (100%)
b2458.4	Replace 2.5 miles of static wire on Carolina – Woodland 115 kV	Dominion (100%)
b2458.5	Replace 4.5 miles of conductor between Carolina 115 kV and Jackson DP 115 kV with min. 300 MVA summer STE rating; Replace 8 wood H-frame structures located between Carolina and Jackson DP with steel H-frames	Dominion (100%)
b2460.1	Replace Hanover 230 kV substation line switches with 3000A switches	Dominion (100%)
b2460.2	Replace wave traps at Four River 230 kV and Elmont 230 kV substations with 3000A wave traps	Dominion (100%)
b2461	Wreck and rebuild existing Remington CT – Warrenton 230 kV (approx. 12 miles) as a double-circuit 230 kV line	Dominion (100%)
b2461.1	Construct a new 230 kV line approximately 6 miles from NOVEC’s Wheeler Substation a new 230 kV switching station in Vint Hill area	Dominion (100%)
b2461.2	Convert NOVEC’s Gainesville – Wheeler line (approximately 6 miles) to 230 kV	Dominion (100%)
b2461.3	Complete a Vint Hill – Wheeler – Loudoun 230 kV networked line	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2471	Replace Midlothian 500 kV breaker 563T576 and motor operated switches with 3 breaker 500 kV ring bus. Terminate Lines # 563 Carson – Midlothian, #576 Midlothian –North Anna, Transformer #2 in new ring	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2504	Rebuild 115 kV Line #32 from Halifax-South Boston (6 miles) for min. of 240 MVA and transfer Welco tap to Line #32. Moving Welco to Line #32 requires disabling auto-sectionalizing scheme	Dominion (100%)
b2505	Install structures in river to remove the 115 kV #65 line (Whitestone-Harmony Village 115 kV) from bridge and improve reliability of the line	Dominion (100%)
b2542	Replace the Loudoun 500 kV ‘H2T502’ breaker with a 50kA breaker	Dominion (100%)
b2543	Replace the Loudoun 500 kV ‘H2T584’ breaker with a 50kA breaker	Dominion (100%)
b2565	Reconductor wave trap at Carver Substation with a 2000A wave trap	Dominion (100%)
b2566	Reconductor 1.14 miles of existing line between ACCA and Hermitage and upgrade associated terminal equipment	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2582	Rebuild the Elmont – Cunningham 500 kV line	Dominion (100%)
b2583	Install 500 kV breaker at Ox Substation to remove Ox Tx#1 from H1T561 breaker failure outage.	Dominion (100%)
b2584	Relocate the Bremono load (transformer #5) to #2028 (Bremono-Charlottesville 230 kV) line and Cartersville distribution station to #2027 (Bremono-Midlothian 230 kV) line	Dominion (100%)
b2585	Reconductor 7.63 miles of existing line between Cranes and Stafford, upgrade associated line switches at Stafford	DFAX Allocation: PEPCO (100%)
b2620	Wreck and rebuild the Chesapeake – Deep Creek – Bowers Hill – Hodges Ferry 115 kV line; minimum rating 239 MVA normal/emergency, 275 MVA load dump rating	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2622	Rebuild Line #47 between Kings Dominion 115 kV and Fredericksburg 115 kV to current standards with summer emergency rating of 353 MVA at 115 kV	Dominion (100%)
b2623	Rebuild Line #4 between Bremo and Structure 8474 (4.5 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2624	Rebuild 115 kV Lines #18 and #145 between Possum Point Generating Station and NOVEC's Smoketown DP (approx. 8.35 miles) to current 230 kV standards with a normal continuous summer rating of 524 MVA at 115 kV	Dominion (100%)
b2625	Rebuild 115 kV Line #48 between Thole Street and Structure 48/71 to current standard. The remaining line to Sewells Point is 2007 vintage. Rebuild 115 kV Line #107 line, Sewells Point to Oakwood, between structure 107/17 and 107/56 to current standard.	Dominion (100%)
b2626	Rebuild 115 kV Line #34 between Skiffes Creek and Yorktown and the double circuit portion of 115 kV Line #61 to current standards with a summer emergency rating of 353 MVA at 115 kV	Dominion (100%)
b2627	Rebuild 115 kV Line #1 between Crewe 115 kV and Fort Pickett DP 115 kV (12.2 miles) to current standards with summer emergency rating of 261 MVA at 115 kV	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2628	Rebuild 115 kV Line #82 Everetts – Voice of America (20.8 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2629	Rebuild the 115 kV Lines #27 and #67 lines from Greenwich 115 kV to Burton 115 kV Structure 27/280 to current standard with a summer emergency rating of 262 MVA at 115 kV	Dominion (100%)
b2630	Install circuit switchers on Gravel Neck Power Station GSU units #4 and #5. Install two 230 kV CCVT's on Lines #2407 and #2408 for loss of source sensing	Dominion (100%)
b2636	Install three 230 kV bus breakers and 230 kV, 100 MVAR Variable Shunt Reactor at Dahlgren to provide line protection during maintenance, remove the operational hazard and provide voltage reduction during light load conditions	Dominion (100%)
b2647	Rebuild Boydton Plank Rd – Kerr Dam 115 kV Line #38 (8.3 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.	Dominion (100%)
b2648	Rebuild Carolina – Kerr Dam 115 kV Line #90 (38.7 miles) to current standards with summer emergency rating of 353 MVA 115 kV.	Dominion (100%)
b2649	Rebuild Clubhouse – Carolina 115 kV Line #130 (17.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2649.1	Rebuild of 1.7 mile tap to Metcalf and Belfield DP (MEC) due to poor condition. The existing summer rating of the tap is 48 MVA and existing conductor is 4/0 ACSR on wood H-frames. The proposed new rating is 176 MVA using 636 ACSR conductor	Dominion (100%)
b2649.2	Rebuild of 4.1 mile tap to Brinks DP (MEC) due to wood poles built in 1962. The existing summer rating of the tap is 48 MVA and existing conductor is 4/0 ACSR and 393.6 ACSR on wood H-frames. The proposed new rating is 176 MVA using 636 ACSR conductor	Dominion (100%)
b2650	Rebuild Twittys Creek – Pamplin 115 kV Line #154 (17.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV.	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2651	Rebuild Buggs Island – Plywood 115 kV Line #127 (25.8 miles) to current standards with summer emergency rating of 353 MVA at 115 kV. The line should be rebuilt for 230 kV and operated at 115 kV.		Dominion (100%)
b2652	Rebuild Greatbridge – Hickory 115 kV Line #16 and Greatbridge – Chesapeake E.C. to current standard with summer emergency rating of 353 MVA at 115 kV.		Dominion (100%)
b2653.1	Build 20 mile 115 kV line from Pantego to Trowbridge with summer emergency rating of 353 MVA.		Dominion (100%)
b2653.2	Install 115 kV four-breaker ring bus at Pantego		Dominion (100%)
b2653.3	Install 115 kV breaker at Trowbridge		Dominion (100%)
b2654.1	Build 15 mile 115 kV line from Scotland Neck to S Justice Branch with summer emergency rating of 353 MVA. New line will be routed to allow HEMC to convert Dawson’s Crossroads RP from 34.5 kV to 115 kV.		Dominion (100%)
b2654.2	Install 115 kV three-breaker ring bus at S Justice Branch		Dominion (100%)
b2654.3	Install 115 kV breaker at Scotland Neck		Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2665	Rebuild the Cunningham – Dooms 500 kV line	Dominion (100%)
b2686	Pratts Area Improvement	Dominion (100%)
b2686.1	Build a 230 kV line from Remington Substation to Gordonsville Substation utilizing existing ROW	Dominion (100%)
b2686.11	Upgrading sections of the Gordonsville – Somerset 115 kV circuit	Dominion (100%)
b2686.12	Upgrading sections of the Somerset – Doubleday 115 kV circuit	Dominion (100%)
b2686.13	Upgrading sections of the Orange – Somerset 115 kV circuit	Dominion (100%)
b2686.14	Upgrading sections of the Mitchell – Mt. Run 115 kV circuit	Dominion (100%)
b2686.2	Install a 3rd 230/115 kV transformer at Gordonsville Substation	Dominion (100%)

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2686.3	Upgrade Line 2088 between Gordonsville Substation and Louisa CT Station	Dominion (100%)
b2717.1	De-energize Davis – Rosslyn #179 and #180 69 kV lines	Dominion (100%)
b2717.2	Remove splicing and stop joints in manholes	Dominion (100%)
b2717.3	Evacuate and dispose of insulating fluid from various reservoirs and cables	Dominion (100%)
b2717.4	Remove all cable along the approx. 2.5 mile route, swab and cap-off conduits for future use, leave existing communication fiber in place	Dominion (100%)
b2719.1	Expand Perth substation and add a 115 kV four breaker ring	Dominion (100%)
b2719.2	Extend the Hickory Grove DP tap 0.28 miles to Perth and terminate it at Perth	Dominion (100%)
b2719.3	Split Line #31 at Perth and terminate it into the new ring bus with 2 breakers separating each of the line terminals to prevent a breaker failure from taking out both 115 kV lines	Dominion (100%)
b2720	Replace the Loudoun 500 kV ‘H1T569’ breakers with 50kA breaker	Dominion (100%)
b2729	Optimal Capacitors Configuration: New 175 MVAR capacitor at Brambleton, new 175 MVAR capacitor at Ashburn, new 300 MVAR capacitor at Shelhorn, new 150 MVAR capacitor at Liberty	AEC (1.97%) / BGE (14.46%) / Dominion (35.33%) / DPL (3.78%) / JCPL (3.33%) / ME (2.53%) / Neptune (0.63%) / PECO (6.30%) / PEPCO (20.36%) / PPL (3.97%) / PSEG (7.34%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2744	Rebuild the Carson – Rogers Rd 500 kV circuit	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2745	Rebuild 21.32 miles of existing line between Chesterfield – Lakeside 230 kV	Dominion (100%)
b2746.1	Rebuild Line #137 Ridge Rd – Kerr Dam 115 kV, 8.0 miles, for 346 MVA summer emergency rating	Dominion (100%)
b2746.2	Rebuild Line #1009 Ridge Rd – Chase City 115 kV, 9.5 miles, for 346 MVA summer emergency rating	Dominion (100%)
b2746.3	Install a second 4.8 MVAR capacitor bank on the 13.8 kV bus of each transformer at Ridge Rd	Dominion (100%)
b2747	Install a Motor Operated Switch and SCADA control between Dominion’s Gordonsville 115 kV bus and FirstEnergy’s 115 kV line	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2757	Install a +/-125 MVAR Statcom at Colington 230 kV	Dominion (100%)
b2758	Rebuild Line #549 Dooms – Valley 500kV	Dominion (100%)
b2759	Rebuild Line #550 Mt. Storm – Valley 500kV	Dominion (100%)
b2800	The 7 mile section from Dozier to Thompsons Corner of line #120 will be rebuilt to current standards using 768.2 ACSS conductor with a summer emergency rating of 346 MVA at 115 kV. Line is proposed to be rebuilt on single circuit steel monopole structure	Dominion (100%)
b2801	Lines #76 and #79 will be rebuilt to current standard using 768.2 ACSS conductor with a summer emergency rating of 346 MVA at 115 kV. Proposed structure for rebuild is double circuit steel monopole structure	Dominion (100%)
b2802	Rebuild Line #171 from Chase City – Boydton Plank Road tap by removing end-of-life facilities and installing 9.4 miles of new conductor. The conductor used will be at current standards with a summer emergency rating of 393 MVA at 115kV	Dominion (100%)
b2815	Build a new Pinewood 115kV switching station at the tap serving North Doswell DP with a 115kV four breaker ring bus	Dominion (100%)
b2842	Update the nameplate for Mount Storm 500 kV "57272" to be 50kA breaker	Dominion (100%)
b2843	Replace the Mount Storm 500 kV "G2TY" with 50kA breaker	Dominion (100%)
b2844	Replace the Mount Storm 500 kV "G2TZ" with 50kA breaker	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2845	Update the nameplate for Mount Storm 500 kV "G3TSX1" to be 50kA breaker	Dominion (100%)
b2846	Update the nameplate for Mount Storm 500 kV "SX172" to be 50kA breaker	Dominion (100%)
b2847	Update the nameplate for Mount Storm 500 kV "Y72" to be 50kA breaker	Dominion (100%)
b2848	Replace the Mount Storm 500 kV "Z72" with 50kA breaker	Dominion (100%)
b2871	Rebuild 230 kV line #247 from Swamp to Suffolk (31 miles) to current standards with a summer emergency rating of 1047 MVA at 230 kV	Dominion (100%)
b2876	Rebuild line #101 from Mackeys – Creswell 115 kV, 14 miles, with double circuit structures. Install one circuit with provisions for a second circuit. The conductor used will be at current standards with a summer emergency rating of 262 MVA at 115 kV	Dominion (100%)
b2877	Rebuild line #112 from Fudge Hollow – Lowmoor 138 kV (5.16 miles) to current standards with a summer emergency rating of 314 MVA at 138 kV	Dominion (100%)
b2899	Rebuild 230 kV line #231 to current standard with a summer emergency rating of 1046 MVA. Proposed conductor is 2-636 ACSR	Dominion (100%)
b2900	Build a new 230/115 kV switching station connecting to 230 kV network line #2014 (Earleys – Everetts). Provide a 115 kV source from the new station to serve Windsor DP	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2922	Rebuild 8 of 11 miles of 230 kV lines #211 and #228 to current standard with a summer emergency rating of 1046 MVA for rebuilt section. Proposed conductor is 2-636 ACSR	Dominion (100%)
b2928	Rebuild four structures of 500 kV line #567 from Chickahominy to Surry using galvanized steel and replace the river crossing conductor with 3-1534 ACSR. This will increase the line #567 line rating from 1954 MVA to 2600 MVA	Dominion (100%)
b2929	Rebuild 230 kV line #2144 from Winfall to Swamp (4.3 miles) to current standards with a standard conductor (bundled 636 ACSR) having a summer emergency rating of 1047 MVA at 230 kV	Dominion (100%)
b2960	Replace fixed series capacitors on 500 kV Line #547 at Lexington and on 500 kV Line #548 at Valley	Dominion (100%)
b2961	Rebuild approximately 3 miles of Line #205 & Line #2003 from Chesterfield to Locks & Poe respectively	Dominion (100%)
b2962	Split Line #227 (Brambleton – Beaumeade 230 kV) and terminate into existing Belmont substation	Dominion (100%)
b2962.1	Replace the Beaumeade 230 kV breaker “274T2081” with 63kA breaker	Dominion (100%)
b2962.2	Replace the NIVO 230 kV breaker “2116T2130” with 63kA breaker	Dominion (100%)
b2963	Reconductor the Woodbridge to Occoquan 230 kV line segment of Line #2001 with 1047 MVA conductor and replace line terminal equipment at Possum Point, Woodbridge, and Occoquan	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2978	Install 2-125 MVAR STATCOMs at Rawlings and 1-125 MVAR STATCOM at Clover 500 kV substations	<p>Load-Ratio Share Allocation: AEC (1.61%) / AEP (14.10%) / APS (5.79%) / ATSI (7.95%) / BGE (4.11%) / ComEd (13.24%) / Dayton (2.07%) / DEOK (3.22%) / DL (1.73%) / DPL (2.48%) / Dominion (13.17%) / EKPC (2.13%) / JCPL (3.71%) / ME (1.88%) / NEPTUNE* (0.42%) / PECO (5.34%) / PENELEC (1.86%) / PEPCO (3.98%) / PPL (4.76%) / PSEG (6.19%) / RE (0.26%)</p> <p>DFAX Allocation: Dominion (100%)</p>
b2980	Rebuild 115 kV Line #43 between Staunton and Harrisonburg (22.8 miles) to current standards with a summer emergency rating of 261 MVA at 115 kV	Dominion (100%)
b2981	Rebuild 115 kV Line #29 segment between Fredericksburg and Aquia Harbor to current 230 kV standards (operating at 115 kV) utilizing steel H-frame structures with 2-636 ACSR to provide a normal continuous summer rating of 524 MVA at 115 kV (1047 MVA at 230 kV)	Dominion (100%)

*Neptune Regional Transmission System, LLC

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2989	Install a second 230/115 kV Transformer (224 MVA) approximately 1 mile north of Bremono and tie 230 kV Line #2028 (Bremono – Charlottesville) and 115 kV Line #91 (Bremono - Sherwood) together. A three breaker 230 kV ring bus will split Line #2028 into two lines and Line #91 will also be split into two lines with a new three breaker 115 kV ring bus. Install a temporary 230/115 kV transformer at Bremono substation for the interim until the new substation is complete	Dominion (100%)
b2990	Chesterfield to Basin 230 kV line – Replace 0.14 miles of 1109 ACAR with a conductor which will increase the line rating to approximately 706 MVA	Dominion (100%)
b2991	Chaparral to Locks 230 kV line – Replace breaker lead	Dominion (100%)
b2994	Acquire land and build a new switching station (Skippers) at the tap serving Brink DP with a 115 kV four breaker ring to split Line #130 and terminate the end points	Dominion (100%)
b3018	Rebuild Line #49 between New Road and Middleburg substations with single circuit steel structures to current 115 kV standards with a minimum summer emergency rating of 261 MVA	Dominion (100%)
b3019	Rebuild 500 kV Line #552 Bristers to Chancellor – 21.6 miles long	Dominion (100%)
b3019.1	Update the nameplate for Morrisville 500 kV breaker “H1T594” to be 50kA	Dominion (100%)
b3019.2	Update the nameplate for Morrisville 500 kV breaker “H1T545” to be 50kA	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b3020	Rebuild 500 kV Line #574 Ladysmith to Elmont – 26.2 miles long	Dominion (100%)
b3021	Rebuild 500 kV Line #581 Ladysmith to Chancellor – 15.2 miles long	Dominion (100%)
b3026	Reconductor Line #274 (Pleasant View – Ashburn – Beaumeade 230 kV) with a minimum rating of 1200 MVA. Also upgrade terminal equipment	Dominion (100%)
b3027.1	Add a 2nd 500/230 kV 840 MVA transformer at Dominion’s Ladysmith substation	Dominion (100%)
b3027.2	Reconductor 230 kV Line #2089 between Ladysmith and Ladysmith CT substations to increase the line rating from 1047 MVA to 1225 MVA	Dominion (100%)
b3027.3	Replace the Ladysmith 500 kV breaker “H1T581” with 50kA breaker	Dominion (100%)
b3027.4	Update the nameplate for Ladysmith 500 kV breaker “H1T575” to be 50kA breaker	Dominion (100%)
b3027.5	Update the nameplate for Ladysmith 500 kV breaker “568T574” (will be renumbered as “H2T568”) to be 50kA breaker	Dominion (100%)
b3055	Install spare 230/69 kV transformer at Davis substation	Dominion (100%)
b3056	Partial rebuild 230 kV Line #2113 Waller to Lightfoot	Dominion (100%)
b3057	Rebuild 230 kV Lines #2154 and #19 Waller to Skiffes Creek	Dominion (100%)
b3058	Partial rebuild of 230 kV Lines #265, #200 and #2051	Dominion (100%)
b3059	Rebuild 230 kV Line #2173 Loudoun to Elclick	Dominion (100%)

Virginia Electric and Power Company (cont.)

Required Transmission Enhancements	Annual Revenue Requirement		Responsible Customer(s)
b3060	Rebuild 4.6 mile Elklick – Bull Run 230 kV Line #295 and the portion (3.85 miles) of the Clifton – Walney 230 kV Line #265 which shares structures with Line #295		Dominion (100%)
b3088	Rebuild 4.75 mile section of Line #26 between Lexington and Rockbridge with a minimum summer emergency rating of 261 MVA		Dominion (100%)
b3089	Rebuild 230 kV Line #224 between Lanexa and Northern Neck utilizing double circuit structures to current 230 kV standards. Only one circuit is to be installed on the structures with this project with a minimum summer emergency rating of 1047 MVA		Dominion (100%)
b3090	Convert the overhead portion (approx. 1500 feet) of 230 kV Lines #248 & #2023 to underground and convert Glebe substation to gas insulated substation		Dominion (100%)

SCHEDULE 12 – APPENDIX A

(23) American Transmission Systems, Inc.

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2019.2		ATSI (100%)
b2019.3		ATSI (100%)
b2019.4		ATSI (100%)
b2019.5		ATSI (100%)
b2122.1		ATSI (100%)
b2122.2		ATSI (100%)
b2188		ATSI (100%)
b2192		ATSI (100%)
b2193		ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2195	Replace the Roberts 138 kV breaker '601-B-60'	ATSI (100%)
b2196	Replace the Sammis 138 kV breaker '780-B-76'	ATSI (100%)
b2262	New Castle Generating Station – Relocate 138kV, 69kV, and 23kV controls from the generating station building to new control building	ATSI (100%)
b2263	Niles Generation Station – Relocate 138kV and 23kV controls from the generation station building to new control building	ATSI (100%)
b2265	Ashtabula Generating Station – Relocate 138kV controls from the generating station building to new control building	ATSI (100%)
b2284	Increase the design operating temperature on the Cloverdale – Barberton 138kV line	ATSI (100%)
b2285	Increase the design operating temperature on the Cloverdale – Star 138kV line	ATSI (100%)
b2301	Reconductor 0.7 miles of 605 ACSR conductor on the Beaver Black River 138kV line	ATSI (100%)
b2301.1	Wave trap and line drop replacement at Beaver (312/380 MVA SN/SE)	ATSI (100%)
b2349	Replace the East Springfield 138kV breaker 211-B-63 with 40kA	ATSI (100%)
b2367	Replace the East Akron 138kV breaker 36-B-46 with 40kA	ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2413	Replace a relay at McDowell 138 kV substation	ATSI (100%)
b2434	Build a new London – Tangy 138 kV line	ATSI (100%)
b2435	Build a new East Springfield – London #2 138 kV line	ATSI (100%)
b2459	Install +260/-150 MVAR SVC at Lake Shore	ATSI (100%)
b2492	Replace the Beaver 138 kV breaker ‘426-B-2’ with 63kA breaker	ATSI (100%)
b2493	Replace the Hoytdale 138kV breaker ‘83-B-30’ with 63kA breaker	ATSI (100%)
b2557	At Avon substation, replace the existing 345/138 kV 448 MVA #92 transformer with a 560 MVA unit	ATSI (100%)
b2558	Close normally open switch A 13404 to create a Richland J Bus – Richland K Bus 138 kV line	ATSI (100%)
b2559	Reconductor the Black River – Lorain 138 kV line and upgrade Black River and Lorain substation terminal end equipment	ATSI (100%)
b2560	Construct a second 138 kV line between West Fremont and Hayes substation on open tower position of the West Fremont –Groton –Hayes 138 kV line	ATSI (100%)
b2616	Addition of 4th 345/138 kV transformer at Harding	ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2673	Rebuild the existing double circuit tower line section from Beaver substation to Brownhelm Jct. approx. 2.8 miles		ATSI (100%)
b2674	Rebuild the 6.6 miles of Evergreen to Ivanhoe 138 kV circuit with 477 ACSS conductor		ATSI (100%)
b2675	Install 26.4 MVAR capacitor and associated terminal equipment at Lincoln Park 138 kV substation		ATSI (100%)
b2725	Build new 345/138 kV Lake Avenue substation w/ breaker and a half high side (2 strings), 2-345/138 kV transformers and breaker and a half (2 strings) low side (138 kV). Substation will tie Avon – Beaver 345 kV #1/#2 and Black River – Johnson #1/#2 lines		ATSI (100%)
b2725.1	Replace the Murray 138 kV breaker ‘453-B-4’ with 40kA breaker		ATSI (100%)
b2742	Replace the Hoytdale 138 kV ‘83-B-26’ and ‘83-B-30’ breakers with 63kA breakers		ATSI (100%)
b2753.4	Double capacity for 6 wire “Burger-Cloverdale No. 2” 138 kV line and connect at Holloway and “Point A”		ATSI (100%)
b2753.5	Double capacity for 6 wire “Burger-Longview” 138 kV line and connect at Holloway and “Point A”		ATSI (100%)
b2778	Add 2nd 345/138 kV transformer at Chamberlin substation		ATSI (100%)
b2780	Replace Bruce Mansfield 345 kV breaker ‘B57’ with an 80 kA breaker, and associated gang-operated disconnect switches D56 and D58		ATSI (100%)

American Transmission Systems, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2869	Replace the Crossland 138 kV breaker "B-16" with a 40kA breaker	ATSI (100%)
b2875	Relocate the Richland to Ridgeville 138 kV line from Richland J bus to K, extend the K bus and install a new breaker	ATSI (100%)
b2896	Rebuild/Reconductor the Black River – Lorain 138 kV circuit	ATSI (100%)
b2897	Reconductor the Avon – Lorain 138 kV section and upgrade line drop at Avon	ATSI (100%)
b2898	Reconductor the Beaver – Black River 138 kV with 954Kcmil ACSS conductor and upgrade terminal equipment on both stations	ATSI (100%)
b2942.1	Install a 100 MVAR 345 kV shunt reactor at Hayes substation	ATSI (100%)
b2942.2	Install a 200 MVAR 345 kV shunt reactor at Bayshore substation	ATSI (100%)
b2972	Reconductor limiting span of Lallendorf – Monroe 345 kV	MISO (11.00%) / AEP (5.38%) / APS (4.27%) / ATSI (66.48%) / Dayton (2.71%) / Dominion (5.31%) / DL (4.85%)
b3031	Transfer load off of the Leroy Center - Mayfield Q2 138 kV line by reconfiguring the Pawnee substation primary source, via the existing switches, from the Leroy Center - Mayfield Q2 138 kV line to the Leroy Center - Mayfield Q1 138 kV line	ATSI (100%)

American Transmission Systems, Inc. (cont.)

<i>Required Transmission Enhancements</i>	<i>Annual Revenue Requirement</i>	<i>Responsible Customer(s)</i>
b3032 <i>Greenfield - NASA 138 kV terminal upgrades: NASA substation, Greenfield exit: Revise CT tap on breaker B22 and adjust line relay settings; Greenfield substation, NASA exit: Revise CT tap on breaker B1 and adjust line relay settings; replace 336.4 ACSR line drop with 1033.5 AL</i>		ATSI (100%)
b3033 <i>Ottawa – Lakeview 138 kV reconductor and substation upgrades</i>		ATSI (100%)
b3034 <i>Lakeview – Greenfield 138 kV reconductor and substation upgrades</i>		ATSI (100%).
b3066 <i>Reconductor the Cranberry – Jackson 138 kV line (2.1 miles), reconductor 138 kV bus at Cranberry bus and replace 138 kV line switches at Jackson bus</i>		ATSI (100%)
b3067 <i>Reconductor the Jackson – Maple 138 kV line (4.7 miles), replace line switches at Jackson 138 kV and replace the line traps and relays at Maple 138 kV bus</i>		ATSI (100%)
b3080 <i>Reconductor the 138 kV bus at Seneca</i>		ATSI (100%)
b3081 <i>Replace the 138 kV breaker and reconductor the 138 kV bus at Krendale</i>		ATSI (100%)

SCHEDULE 12 – APPENDIX A

(25) East Kentucky Power Cooperative, Inc.

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2066	Upgrade the operating temperature of the existing conductor for the JK Smith - Union City - Lake Reba Tap 138 kV line	EKPC (100%)
b2309	Upgrade the bus and jumpers with 750 MCM copper conductor at Green County 69 kV substation	EKPC (100%)
b2310	Increase the maximum operating temperature of the North Springfield - South Springfield 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2311	Increase the maximum operating temperature of the Loretto - Sulphur Creek 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2312	Increase the maximum operating temperature of the South Springfield - Loretto 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2313	Construct 8.8 miles of 69 kV line between the Cave City and Bon Ayr distribution substations. Operate this line normally open	EKPC (100%)
b2314.1	Construct 8.6 miles of 69 kV line between the Mercer County Industrial and Van Arsdell distribution substation. Construct a new 69 kV switching station adjacent to Bonds Bill Substation. Loop NorthSpringfield - Van Arsdell 69 kV line through South Anders	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2314.2 Construct a new 69 kV switching station ("South Anderson") adjacent to the LGE/KU Bonds Mill substation		EKPC (100%)
b2314.3 Loop the North Springfield - Van Arsdell 69 kV line through South Anderson. Terminate the existing 69 kV to the LGE/KU Bonds Mill substation at South Anderson and establish a second 69 kV from S. Anderson to the LGE/KU Bonds Mill sub		EKPC (100%)
b2314.4 Construct 0.12 miles of 69 kV line from South Anderson to the Powell Taylor distribution substation and serve this substation radially from South Anderson		EKPC (100%)
b2315 Increase the size of the existing HT Adams 69 kV, 7.2 MVAR capacitor bank to 14.28 MVAR		EKPC (100%)
b2316 Increase the size of the existing Hunt Farm Junction 69 kV, 8.2 MVAR capacitor bank to 16.33 MVAR		EKPC (100%)
b2317 Construct 10.9 miles of 69 kV line between the Owen County substation and the Keith distribution substation. Operate the existing Penn - Keith 69 kV line normally - open		EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
<p>b2318 Construct 2.7 miles of 69 kV line between the Fox Hollow substation and the Parkway distribution substations. Serve the Parkway #1 and #2 distribution substations radially from Fox Hollow. Operate the Cave City - Bon Ayr 69 kV line normally - closed</p>		<p>EKPC (100%)</p>
<p>b2319 Increase the maximum operating temperature of the Helechawa - Sublett 69 kV line to 167 degrees Fahrenheit</p>		<p>EKPC (100%)</p>
<p>b2320 Install a 69 kV, 15.31 MVAR capacitor bank at the Perryville substation</p>		<p>EKPC (100%)</p>
<p>b2321 Install a 69 kV, 25.51 MVAR capacitor bank at the Veechdale substation</p>		<p>EKPC (100%)</p>
<p>b2322 Change the CT setting on circuit breaker N35 - 804 at Dale Station to at least 800 amps to increase the relay loadability on the Dale - Three Forks 138 kV line to at least 282 MVA</p>		<p>EKPC (100%)</p>
<p>b2323 Rebuild the existing Cynthiana - Headquarters 69 kV line using 556.5 MCM ACSR conductor and operate this line normally closed</p>		<p>EKPC (100%)</p>
<p>b2324 Remove the existing 1200 - amp line traps at JK Smith and Dale associated with the JK Smith - Dale 138 kV line</p>		<p>EKPC (100%)</p>

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2325	Increase the maximum operating temperature of the Glendale - Hodgenville 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2326	Increase the maximum operating temperature of the Fayette - Davis 69 kV line to 248 degrees Fahrenheit	EKPC (100%)
b2327	Increase the maximum operating temperature of the Boone - Boone Distribution 69 kV line to 302 degrees Fahrenheit	EKPC (100%)
b2328	Increase the maximum operating temperature of the West Bardstown Junction - West Bardstown 69 kV line to 284 degrees Fahrenheit	EKPC (100%)
b2329	Increase the maximum operating temperature of the Magnolia - Summersville 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2330	Increase the maximum operating temperature of the Bacon Creek - Liberty Church 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2331	Increase the maximum operating temperature of the Headquarters - Millersburg Junction 69 kV line to 167 degrees Fahrenheit	EKPC (100%)
b2332	Increase the maximum operating temperature of the JK Smith - Dale 138 kV line to 275 degrees Fahrenheit	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2333	Increase the maximum operating temperature of the Elizabethtown - Tunnel Hill 69 kV line to 284 degrees Fahrenheit	EKPC (100%)
b2334	Install a 69 kV, 28.06 MVAR capacitor bank at the Owen County substation	EKPC (100%)
b2335	Install a 69 kV, 14.29 MVAR capacitor bank at the Magoffin County substation	EKPC (100%)
b2336	Increase the maximum operating temperature of the South Corbin - Bacon Creek 69 kV line to 212 degrees Fahrenheit	EKPC (100%)
b2337	Increase the size of the existing Cedar Grove 69 kV, 10.8 MVAR capacitor bank to 20.41 MVAR	EKPC (100%)
b2339	Upgrade the 4/0 copper bus and jumpers at the Nelson County substation associated with the Nelson County - West Bardstown Junction 69 kV line using 500 MCM copper or equivalent equipment	EKPC (100%)
b2340	Increase the Zone 3 distance relay setting at Barren County associated with the Barren County - Horse Cave Tap 69 kV line to at least 85 MVA	EKPC (100%)
b2414	Build the 2nd Summer Shade EKPC - Summer Shade TVA 161 kV circuit	EKPC (100%)
b2544	Increase the MOT of the 266.8 MCM ACSR section (1.4 miles), of the Kargle-KU Elizabethtown 69 kV line section to 266 degrees F	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2614	Decouple the double-circuited Spurlock – Maysville Industrial Tap 138-kV & Spurlock – Flemingsburg 138-kV line segments	EKPC (100%)
b2615	Upgrade the Bullitt County 161/69 kV transformer facility	EKPC (100%)
b2655	Increase the size of the existing Leon 69 kV capacitor bank from 13.2 MVAR to 18.36 MVAR	EKPC (100%)
b2656	Reconductor the Leon – Airport Road 69 kV line section (5.72 miles) using 556.5 MCM ACTW conductor	EKPC (100%)
b2657	Add 69 kV breaker at Thelma – AEP Thelma 69 kV tie	EKPC (100%)
b2658	Increase the zone 3 distance relay setting at Barren County associated with the Barren County – Horse Cave Junction line to at least 103 MVA	EKPC (100%)
b2659	Rebuild the Seymour Tap – KU Horse Cave Tap 69 kV line section (1.98 miles) to 302 degrees F	EKPC (100%)
b2660	Increase the zone 3 distance relay setting at Elizabethtown associated with the Elizabethtown – Smithersville line section to at least 100 MVA	EKPC (100%)
b2661	Reconductor the Baker Lane – Holloway Junction 69 kV (1.28 miles) line section using 556.5 MCM ACTW wire	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2662	Increase the maximum operating temperature of the Hickory Plains – PPG 69 kV line section (0.21 miles) to 266 degrees F	EKPC (100%)
b2663	Increase the zone 3 distance relay setting at EKPC Elizabethtown associated with the EKPC Elizabethtown to KU Elizabethtown 69 kV line to at least 126 MVA	EKPC (100%)
b2664	Increase the maximum operating temperature of the Tharp Tap – KU Elizabethtown 69 kV line section (2.11 miles) to 266 degrees F. (LTE at 248 degrees F)	EKPC (100%)
b2710	Upgrade the Summer Shade bus and CT associated with the 161/69 kV transformer #1	EKPC (100%)
b2711	Install 25.5 MVAR 69 kV capacitor at Sewellton Junction 69 kV substation	EKPC (100%)
b2730	Upgrade Denny – Gregory Tap 69 kV line facility	EKPC (100%)
b2781	Increase maximum operating temperature of Davis – Nicholasville 69 kV line section 266.8 MCM conductor to 284°F (LTE of 266°F)	EKPC (100%)
b2782	Increase the maximum operating temperature of Plumville – Rectorville 69 kV line section 266.8 MCM conductor to 212°F (LTE of 185°F)	EKPC (100%)
b2783	Rebuild the Davis – Fayette 69 kV line section to 556.5 MCM (3.15 miles)	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2784	Increase overcurrent relay at West Berea 138/69 kV to at least 139 MVA Winter LTE	EKPC (100%)
b2785	Install a 13.776 MVAR cap bank at Three Links 69 kV	EKPC (100%)
b2786	Increase Williamstown cap bank to 11.225 MVAR	EKPC (100%)
b2827	Upgrade the current 5% impedance 1200A line reactor, which connects the 4SPURLOCK – 4SPUR-KENT-R and 4SPUR-KENT-R – 4KENTON 138kV line sections, to a 6.5% impedance 1600A line reactor	EKPC (100%)
b2879.2	Reconductor EKPC portion of the Stuart – Spurlock 345 kV line	EKPC (100%)
b2893	Rebuild the existing (1.5 mile), 1/0 MCM ACSR South Bardstown – West Bardstown Jct. 69 kV line using 556.5 MCM ACTW conductor	EKPC (100%)
b2902	Rebuild the Brodhead – Three Links Jct. 69 kV line section (8.2 miles) using 556.5 MCM ACTW wire	EKPC (100%)
b2903	Raise the V-low setting for Summer Shade 69 kV cap bank to 1.01 pu	EKPC (100%)
b2904	Raise the V-low setting for Newby 69 kV cap bank to 0.955 pu	EKPC (100%)
b2905	Resize the Albany 69 kV capacitor bank from 8.4 to 13.776 MVAR	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2906	Increase the Zone 3 distance relay setting at Baker Lane associated with the Baker Lane - Holloway Jct. 69 kV line to at least 142 MVA LTE Winter	EKPC (100%)
b2907	Upgrade the metering CT associated with the Clay Village - KU Clay Village 69 kV tap line section to 600 A; at least 64 MVA Winter LTE. Upgrade the distance relay associated with the Clay Village - KU Clay Village 69 kV tap line section to at least 64 MVA	EKPC (100%)
b2908	Upgrade the distance relay associated with Dale – JK Smith 138 kV line section to 362 MVA normal rating	EKPC (100%)
b2909	Increase the MOT of the EKPC Elizabethtown – Tharp Tap 69 kV line section (1.7 miles) to 302°F (LTE at 284°F)	EKPC (100%)
b2910	Upgrade the distance relay at the Hodgenville station associated with the Glendale – Hodgenville 69 kV line section to at least 90 MVA Winter LTE	EKPC (100%)
b2911	Upgrade the overcurrent relay setting associated with Powell County 138/69 kV transformer to at least 139 MVA Winter LTE	EKPC (100%)
b2912	Upgrade the existing S408-605, 600 A KU Russell Springs Tap – Russell County 69 kV disconnect switch to 1200 A	EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements Annual Revenue Requirement Responsible Customer(s)

b2913	Upgrade distance relay at the Stephensburg station associated with Stephensburg – Glendale 69 kV line section to at least Winter LTE 100 MVA		EKPC (100%)
b2914	Rebuild Tharp Tap – KU Elizabethtown 69 kV line section to 795 MCM (2.11 miles)		EKPC (100%)
b2915	Resize the sideview 69 kV capacitor bank from 6.12 MVAR to 9.18 MVAR		EKPC (100%)
b2916	Upgrade the existing metering CTs (Quantity of 2) associated with the East Bardstown - KU Bardstown Industrial Tap 69 kV line section to 1200 A, at least 100 MVA Winter LTE; and upgrade the existing East Bardstown bus and jumpers from 4/0 to 500 MCM copper		EKPC (100%)
b2917	Replace the existing 100 MVA 138/69 kV transformer bank at the West Berea substation with a 150 MVA transformer		EKPC (100%)
b2918	Upgrade the 4/0 bus and jumpers associated with the West Berea Jct. – Three Links Jct. 69 kV line to 500 MCM copper or equivalent equipment at the Three Links Jct. substation		EKPC (100%)
b2919	Install a 69 kV, 15.31 MVAR capacitor bank at South Anderson substation		EKPC (100%)
b2920	Rebuild Boone - Big Bone Tap 69 kV line section using 556.5 MCM ACTW conductor (6.3 miles)		EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

Required Transmission Enhancements	Annual Revenue Requirement	Responsible Customer(s)
b2921		EKPC (100%)
b2939		EKPC (100%)
b2940		EKPC (100%)
b3044		EKPC (100%)
b3045		EKPC (100%)
b3046		EKPC (100%)

East Kentucky Power Cooperative, Inc. (cont.)

<i>Required Transmission Enhancements</i>	<i>Annual Revenue Requirement</i>		<i>Responsible Customer(s)</i>
<p><i>b3047</i></p>	<p><i>Upgrade the existing 4/0 CU line jumpers with double 500 MCM CU associated with the Green Co - KU Green Co 69 kV line section. Also, replace the existing 600 A disconnect switches with 1200 A associated with the Green Co 161/69 kV transformer</i></p>		<p><i>EKPC (100%)</i></p>
<p><i>b3094</i></p>	<p><i>Move 69 kV 12.0 MVAR capacitor bank from Greenbriar to Bullitt Co 69 kV substation</i></p>		<p><i>EKPC (100%)</i></p>